

TI-85

TI-85

ADVANCED SCIENTIFIC CALCULATOR

Owner's Manual





TEXAS INSTRUMENTS

WARRANTY CARD

TWO (2) YEAR WARRANTY

Name :

Profession :

Address :

Model :

TI-85

Date of purchase:

Telephone :

- Warranty is accepted if this card is correctly filled in by the retailer: stamp and date of purchase are required. If stamp is missing, you must send in the invoice or your receipt proving the purchase.
- To simplify your return and expedite its processing, please complete the other side of this card.

Thank you



**RETAILER'S
STAMP**

ANY DAMAGE TO THE DISPLAY
IS NOT COVERED BY WARRANTY

IN CASE OF DIFFICULTY

In **case of difficulty**, please carefully read the information in your manual, calculator and duplicate examples. Please also refer to the chapter "In **case of difficulty**".

1. In case of difficulty with the display (blank display or digits and graphs do not appear), check the display contrast: Press **ON** to switch the calculator on. Press then release the **2nd**. Press and hold the **Δ** or **▽** cursor keys to adjust the contrast.
2. In case of erratic functioning or erratic display, reset your calculator: Press **2nd** (OFF) then **ON** to switch the calculator on. Press then release **2nd**, then (MEM). Press **FB** (RESET), then press **FI** (ALL). Press **FI** (YES) to reset your calculator then adjust the display contrast.
3. Checking the batteries: try again with **new** batteries.

Warning : battery replacement is not covered by warranty.

REASON FOR RETURN

DISPLAY ☐ Dark ☐ No display ☐ Other

Describe the problem:

KEYBOARD

Indicate which keys are not working:

RANDOM FUNCTIONING: Wrong calculations, wrong display...

Please give some examples:

OTHERS :

Please specify:

TI-85

Advanced Scientific Calculator Guidebook

Guidebook
developed by:

The staff of Texas Instruments Instructional
Communications.

With contributions
by:

Brnd Christensen
Franklin Demana
Doug Feltz
Linda Ferris
Dave Hertling
Don LaTorre

Pat Milheron
John Powers
Dave Stone
Bert K. Waits
C. B. Wilson

Ideas for some of the applications and examples in this guidebook were taken from *College Algebra and Trigonometry: A Graphing Approach*, 2nd ed., by Demana, Waits, and Clemens, and *Calculus, A Graphing Approach*, preliminary ed., by Finney, Thomas, Demana, and Waits, both published by Addison-Wesley Publishing Company and used by permission of the authors.

© 1992 by Texas Instruments Incorporated.

IBM is a registered trademark of International Business Machines Corporation.
Macintosh is a registered trademark of Apple Computer, Inc.

TEXAS INSTRUMENTS TI-85



M1

M2

M3

M4

M5

F1

F2

F3

F4

F5

2nd

QUIT

EXIT

MODE

MORE

alpha

ALPHA

LINK X

x-VAR

INS

DEL

SOLVER

SIMULT

POLY

CATALOG

TOLER

GRAPH

STAT

PRGM

CUSTOM

CLEAR

10^x A

SIN⁻¹ B

COS⁻¹ C

TAN⁻¹ D

π E

LOG

SIN

COS

TAN

^

10^x F

x⁻¹ G

{ H

| I

CALC J

LN

EE

(

)

÷

√ K

MATRIX L

VECTR M

CPLX N

MATH O

x²

7

8

9

×

< P

CONS Q

CONV R

STRNG S

LIST T

,

4

5

6

-

RCL =

BASE U

TEST V

VARS W

MEM X

STO▶

1

2

3

+

OFF

CHAR Y

: Z

ANS

ENTRY

ON

0

.

(-)

ENTER

This guidebook describes how to use the TI-85 Graphics Calculator. Getting Started gives a quick overview of its features. The first two chapters give general instructions on operating the TI-85. Chapters 3 to 16 describe its interactive features. Chapter 17 provides applications showing how to use these features together.

	Using this Guidebook Effectively	x
	Glossary	xi
Getting Started	The Menu Keys	2
	The First Steps	3
	Entering Expressions: Savings Account Example	4
	Recalling and Editing a Calculation	6
	Graphing on the TI-85	7
	Entering an Equation: Illumination Example	9
	Entering an Equation in the SOLVER	10
	Solving for a Variable	11
	Additional Solutions with the SOLVER	12
	Changing the Viewing Rectangle	13
	Finding a Solution from a SOLVER Graph	14
	Defining Functions to Graph	15
	Displaying the Graph	16
	Tracing along a Function	17
	Finding a Maximum Graphically	18
	Graphing the Derivative	19
	Zooming In on the Graph	20
	Finding a Root Graphically	21
	Other Features	22
Chapter 1: Operating the TI-85	Turning the TI-85 On and Off	1-2
	Setting the Display Contrast	1-3
	The 2nd and ALPHA Keys	1-4
	The Display	1-6
	The Equation Operating System	1-8
	Entering and Editing	1-10
	Expressions and Instructions	1-12
	Last Answer	1-13
	Last Entry	1-14
	Example: Convergence of a Series	1-15
	The TI-85 Menus	1-16
	Displaying Menus	1-17
	Selecting from Menus	1-18
	Moving around the TI-85	1-20
	The CATALOG	1-22
	The CUSTOM Menu	1-23
	Setting Modes	1-24
	Error Conditions	1-29

Table of Contents (Continued)

Chapter 2:	Data Types	2-2
Entering and Using	Entering and Using Numbers	2-3
Data	Variables	2-4
	Storing Values to Variables	2-5
	Using Variable Values	2-6
	The VARS (Variables) Menu	2-7
	Accessing Variable Names	2-8
	Equation Variables	2-9
	Recalling Variable Contents	2-10
	Variable Examples	2-11
	Constants, Programs, Graphs, and Pictures	2-12
Chapter 3:	Keyboard Math Functions	3-2
Math, Calculus, and	The MATH Menu	3-3
Test Operations	The NUM (Number) Menu	3-4
	The PROB (Probability) Menu	3-6
	The ANGLE Menu	3-7
	The HYP (Hyperbolic) Menu	3-8
	The MISC (Miscellaneous) Menu	3-9
	The INTER (Interpolation) Feature	3-11
	The CALC (Calculus) Menu	3-12
	The TOLER (Tolerance) Settings	3-17
	The TEST (Relational) Menu	3-18

Chapter 4	Defining a Graph	4-2
Function Graphing	Graphing Modes	4-3
	Trace/Quit/Menu and Display	4-4
	Setting the Graph Format	4-5
	Defining a Function on the x - y List	4-5
	Setting Functions	4-11
	Defining the Viewing Rectangle	4-12
	Discontinuous Graphs	4-14
	Resizing a Graph with the Free-Moving Cursor	4-16
	Expanding a Graph with the TRACE Features	4-17
	Expanding a Graph with the ZOOM Features	4-18
	Using ZOOM Box	4-19
	Zooming from Graph	4-20
	Setting ZOOM Features	4-21
	Other ZOOM Features	4-22
	Trace and Redraw ZOOM	4-23
	TRACER/MATH Menu	4-24
	Setting the Interface for MATH Operations	4-25
	Using the MATH Operations	4-26
	Using F6 to Redraw a Graph	4-29
	Plot CHWV Menu	4-30
	Discontinuous Graphs	4-31
	Shifting Axes on a Graph	4-32
	Drawing Lines	4-35
	Drawing Vertical Lines and Tangent Lines	4-35
	Drawing Circles	4-36
	Drawing Ellipses and Inverse	4-37
	Using OBJECT to Draw a Graph	4-38
	Drawing Points	4-39
	Scaling and Redefining Graph Horizons	4-40
	Scaling and Redefining Graph Portion	4-41
	GRAPH Menu Items in the Program Editor	4-42
	GRAPH Menu Chart	4-44
	Example: Using Lists in Graphing	4-46

Table of Contents (Continued)

Chapter 5	Defining and Displaying a Polar Graph	5-2
Polar Graphing	Exploring and Analyzing a Polar Graph	5-4
	Example: Graphing a Cardioid	5-6
Chapter 6	Defining and Displaying a Parametric Graph	6-2
Parametric Graphing	Exploring and Analyzing a Parametric Graph	6-4
	Example: Simulating Motion	6-6
Chapter 7	Defining and Displaying a Differential Equation	7-2
Differential Equation	Graphing and Analyzing a Differential Equation	7-4
Graphing	Example: Plotting a Logistic Differential Equation	7-6
	Example: Solving a Differential Equation	7-8
	Example: Graphing a Differential Equation	7-10
Chapter 8	The GET Constant Menu	8-2
Constants and	Using Constants	8-4
Conversions	Creating and Editing a User-Defined Constant	8-6
	The GET Constant Menu	8-8
	Using Constants	8-10
Chapter 9	Creating and Using Strings	9-2
Strings and	The GET String Menu	9-4
Characters	The GET Character Menu	9-6
	Accessing Menu Items and Using Characters	9-8
	Accessing International Characters	9-10
Chapter 10	Using Number Bases	10-2
Number Bases	The BASE Number Base Menu	10-4
	Displaying Number Bases	10-6
	Accessing Hex Digits	10-8
	Displaying Results in Another Number Base	10-10
	Using Boolean Operators	10-12
	Manipulating Number Base Digits	10-14

Chapter 11:	Entering and Using Complex Numbers	11-2
Complex Numbers	The CPLX (Complex Number) Menu	11-3
Chapter 12:	Entering and Using Lists	12-2
Lists	The LIST Menu	12-4
	Selecting a List	12-5
	Defining and Editing Lists with the Editor	12-6
	Using Math Functions with Lists	12-7
	List Functions	12-8
	Defining and Recalling List Dimensions	12-10
Chapter 13:	Entering and Using Matrices	13-2
Matrices and Vectors	The MATRX (Matrix) Menu	13-5
	Defining and Editing Matrices with the Editor	13-6
	Using Math Functions with Matrices	13-10
	The MATRX Math Menu	13-12
	The MATRX OPS (Operations) Menu	13-14
	Defining and Recalling Matrix Dimensions	13-15
	The Row Functions	13-16
	The MATRX CPLX (Complex) Menu	13-18
	Storing and Using Portions of a Matrix	13-19
	Entering and Using Vectors	13-20
	The VECTR (Vector) Menu	13-23
	Defining and Editing Vectors with the Editor	13-24
	Using Math Functions with Vectors	13-25
	The VECTR Math Menu	13-27
	The VECTR OPS (Operations) Menu	13-28
	Converting Units	13-29
	The VECTR CPLX (Complex) Menu	13-30
Chapter 14:	Entering and Using Equations with the SOLVER	14-2
Equation Solving	Defining the Variables	14-3
	Solving One Equation	14-5
	Solving Two Equations Graphically	14-6
	Solving Three Equations	14-7
	Solving the POLY (Polynomial) Equation	14-8
	Solving the DPM (Difference) Equation	14-9
	Solving a MULT (Simultaneous) Equations	14-10
	Solving a SYSTEM (Simultaneous) Equations	14-11
	Example: Simultaneous Equations	14-12

Table of Contents (Continued)

Chapter 15:	Statistical Analysis	15-2
Statistical	The STAT (Statistical) Menu	15-3
Calculations	Selecting and Loading Lists	15-4
	Loading Lists into the Editor	15-5
	Entering and Editing Data	15-6
	Calculating Statistical Results	15-8
	Statistical Results Display	15-9
	Statistical Results	15-10
	The DRAW Menu	15-12
	Drawing Statistical Data	15-13
	Forecasting a Statistical Data Value	15-14
	Using Σ and Σ^2 Operations on Lists and Lists	15-15
	Example: Analyzing Two Variable Statistics	15-18
Chapter 16:	Using Programs	16-2
Programming	Sample Program	16-4
	The PROGRAM Program Menu	16-5
	Entering and Editing a Program	16-6
	The I/O Input/Output Menu	16-9
	The Input/Output Instructions	16-10
	The Control Menu	16-14
	The Control Instructions	16-17
	Calling Other Programs	16-19
	Using Application Operations in Programs	16-20
Chapter 17:	Characteristic Functions and Properties	17-2
Applications	The Φ Function and Properties of Φ	17-4
	Symmetry of the Roots of a Complex Number	17-6
	Fractions and Matrices	17-7
	Finding the Area between Curves	17-8
	Maximizing the Speed of Revolution	17-9
	Electrical Circuits	17-10
	Unusual Exponent	17-12
	Program: Taylor Series	17-14
	Program: Sierpinski Triangle	17-16

Chapter 18:	The MEM (Memory) Menu	18-2
Memory	Managing Memory	18-3
Management	Deleting Images from Memory	18-4
	Restoring the U.S.G.	18-5
	Locating a Memory Management Screen	18-6
Chapter 19:	The Flashlight	19-2
Communications	Subsequent Images to Send	19-3
Link	Transmitting Images	19-5
	Receiving Images	19-6
	Receiving in Memory	19-7
	Example	19-8
Appendix A:	End-user Functional and Instructions	A-2
Tables	Tables of System Variables	A-25
Appendix B:	Battery Information	B-2
Reference	Accuracy Information	B-2
Information	Error Correction	B-4
	In Case of Difficulty	B-9
	Two (2) year contractual warranty	B-10
Index		

Using this Guidebook Effectively

The structure of the TI-85 guidebook and the design of its pages can help you find the information you need quickly. Consistent presentation techniques are used throughout to make the guidebook easy to use.

Structure of the Guidebook

The guidebook contains sections that teach you how to use the calculator.

- **Getting Started** is a fast-paced introduction to several important features of the TI-85.
- **Chapters 1 and 2** describe general operation and lay the foundation for Chapters 3 to 16, which describe specific functional areas of the TI-85 and include short examples.
- **Chapter 17** contains application examples that incorporate features from different functional areas of the calculator. These examples can help you see how commands, functions, and instructions work together to accomplish meaningful tasks.
- **Chapter 18** describes memory management and **Chapter 19** describes the communications link.

Page-Design Conventions

When possible, units of information are presented on a single page or on two facing pages. Several page-design elements help you find information quickly.

- **Page headings:** The descriptive heading at the top of the page or two-page unit identifies the subject of the unit.
- **General text:** Just below the page heading, a short section of bold text provides general information about the subject covered in the unit.
- **Left-column subheadings:** Each subheading identifies a specific topic or task related to the page or unit subject.
- **Specific text:** The text to the right of a subheading presents detailed information about that specific topic or task. The information may be presented as paragraphs, numbered procedures, bulleted lists, or illustrations.
- **Page "footers":** The bottom of each page shows the chapter name, chapter number, and page number.

Information-Mapping

Conventions

Several conventions have been used to present information consistently and to improve reference to format.

- **Numbered procedures:** A procedure or sequence of steps in the guidebook is numbered; therefore, when you see numbered text, you know you must perform the steps sequentially.
- **"Bulleted" lists:** If several items have equal importance, or if you may choose one of several alternative actions, this guidebook precedes each item with a "bullet" (•) to highlight it like this list you are reading now.
- **Tables and charts:** Sets of related information are presented in tables or charts for quick reference.



Reference Aids

Several techniques have been used to help you look up specific information when you need it. These include:

- A chapter table of contents on the first page of each chapter, as well as the full table of contents at the front of the guidebook.
- A glossary at the end of this section, defining important terms used throughout the guidebook.
- An alphabetical table of commands in Appendix A, showing each command, its syntax, the key and means that access them, and suggested alternatives for each command.
- Tables of system variables and built-in constants in Appendix A.
- A table of error codes in Appendix B, showing the codes and their meanings, with problem-handling information.
- An alphabetical index at the back of the guidebook, listing tasks and topics you may need to look up.

Glossary

This glossary provides definitions for important terms that are used throughout this guidebook.

Command	A command is either an instruction or an expression used to calculate a result.
Equation Variable	An equation variable may contain an equation or an expression. An equation is two expressions that are equal or a variable equal to an expression.
Expression	An expression is a complete sequence of numbers, variables, functions, and their arguments that can be evaluated to a single result. An expression can include an = sign (a mathematical equation).
Function	A function, which may have arguments, returns a value and can be used in an expression.
Home Screen	The Home Screen is the primary screen of the TI-85, where expressions can be entered and evaluated and instructions can be entered and executed.
Instruction	An instruction, which may have arguments, initiates an action. Instructions are not valid in expressions.
List	A list is a set of values that the TI-85 can use for activation such as graphing a family of curves or evaluating a function at multiple values.
Matrix	A matrix is a two-dimensional array on which the TI-85 can perform operations.
Menu Items	Menu items are shown on the seventh and eighth lines of the display and are associated with the menu keys below them.
Menu Keys	Menu keys are the keys  to  below the display. They are used to select menu items.
Variable	A variable is the name given to a location in memory in which a value, an expression, a list, a matrix, a vector, or a string is stored.
Vector	A vector is a one-dimensional array on which the TI-85 can perform operations.

This section takes you through several examples to introduce you to some of the principal operating and graphing features of the TI-85. You can learn to use the TI-85 more quickly by completing these examples first. Operating details are provided in the remaining chapters of the guidebook.


Contents

The Menu Keys	2
The First Screen	3
Entering Expressions: Savings Account Example	4
Formulating and Solving an Interest Problem	6
Graphing on the TI-85	7
Factoring an Equation: Illumination Example	9
Solving an Equation with the SOLVER	10
Solving for a Variable	11
Advanced Solutions with the SOLVER	12
Changing the Viewing Window	13
Plotting a Solution on the SOLVER Graph	14
Defining Functions to Graph	15
Displaying the Graph	16
Plotting and Graphing Functions	17
Plotting a Maximum Graphically	18
Using the Plot Command	19
Zooming In on the Graph	20
Erasing a Plot Graphically	21
Other Features	22

The Menu Keys

The TI-85 uses display menus to give you access to more operations than you can access from the keyboard alone.

The Menu and Menu Keys



On the TI-85 keyboard, the menu keys are [F1], [F2], [F3], [F4], and [F5]. The 2nd functions of the menu keys are [M1], [M2], [M3], [M4], and [M5]. Menu items are shown on the bottom line of the display, above the five menu keys.

- Selecting Menu Items**
- To select a menu item from the eighth (bottom) line of the display, press the menu key below the item.
 - To select a menu item from the seventh (next-to-the-bottom) line of the display, press and release [2nd] and then press the menu key below the item.

In this guidebook, the menu items are indicated by () brackets. For example, press [F1] to select ZIN or press [2nd] [M5] to select .GRAPH.

The First Steps

Before beginning these sample problems, follow the steps on this page to ensure that the TI-85 is reset to its factory settings. (Resetting the TI-85 erases all previously entered data types.)

- 1 Press **ON** to turn the calculator on.
- 2 Press and release **2nd** and then press **MEM**. (Pressing **2nd** accesses the operation printed to the left above the next key that you press. MEM is the 2nd operation of **2nd**.)

The bottom line of the display shows the MEM (memory) menu.



Press the **MEM** menu key to select (RESET), the third item in the MEM menu.

The bottom line is relabelled with the RESET menu and the MEM menu moves up a line.



- 3 Press **ALL** to select ALL. The display shows the message Are you sure?


Press **YES** to select YES. The display shows the messages Mem cleared and Defaults set.

The display shows the message Defaults set. To adjust the display contrast, press and release **2nd** and then press **▲** (to make the display darker) or **▼** (to make the display lighter).

Press **ON** to clear the display.




4. Press **[F1]** to select **TRACE**. Press **[▶]** to trace along function **y1**, then press **[▶]** to move to function **y2**. Notice the 1 or 2 in the upper right of the display, which indicates which function you are tracing.



5. Press **[EXIT]** to leave **TRACE** and display the **GRAPH** menu.

Press **[F1]** to select **ZOOM**. Press **[F1]** to select **WIN**. Move the cursor over the apparent intersection in the first quadrant. Press **[ENTER]**.




6. Press **[EXIT]** to leave **ZIN** and display the **ZOOM** menu.

Press **[F1]** to select **ZSTD** to display the original graph.

7. To explore the apparent solution in the second quadrant, press **[F1]** to select **BOX**. Move the cursor to the upper right corner of the area you want to examine more closely. Press **[ENTER]**. Move the cursor to the lower left corner (the box defining the area is shown as you move the cursor). Press **[ENTER]**.
8. If necessary, repeat the procedure for **ZIN** or **BOX** to see if the two functions intersect in the second quadrant (they do not).

The coordinate values may vary depending on the cursor location.



Entering an Equation: Illumination Example

On the TI-85, you can explore problems in several different ways. For example, you can solve many problems either by using the SOLVER feature or graphically. The remaining pages in Getting Started present an illumination example to show how to enter equations and explore them both by using the SOLVER and by graphing.

The illumination on a surface is:

- Proportional to the intensity of the source.
- Inversely proportional to the square of the distance.
- Proportional to the sine of the angle between the source and the surface.

The formula for illumination of a point on a surface is shown on the right. A substitution from trigonometry allows us to define illumination in terms of INTEN (intensity), HEIGHT (height of the pole), and DIST (distance).

Appropriate units are ft-c (foot-candles) for illumination, CP (candlepower) for intensity, and ft (feet) for distances.

Assume: The height of a light on a pole in a parking lot is 50 ft and the intensity is 1000 CP. Determine the illumination on the surface 25 ft from the pole.

1. Press \square to select $\text{DIST} = \frac{\text{INTEN} \times \sin \theta}{\text{ILLUM}^2}$.

Press \square to select DIST .

On the TI-85, you can store an unevaluated expression as an equation variable. For example,

$$\text{DIST} = \frac{\text{BASE}^2 + \text{HEIGHT}^2}{\text{HEIGHT}}$$

2. Press \square and \square to get ALPHA lock type $\text{DIST} =$, and then press \square to enter the keyboard and \square ALPHA to get BASE . Press \square to get HEIGHT .



$$\text{ILLUM} = \frac{\text{INTEN} \times \sin \theta}{\text{DIST}^2}$$

$$\sin \theta = \frac{\text{HEIGHT}}{\text{DIST}}$$

$$\text{ILLUM} = \frac{\text{INTEN} \times \text{HEIGHT}}{\text{DIST}^3}$$

$$\text{DIST} = \sqrt{\text{BASE}^2 + \text{HEIGHT}^2}$$


Done

Entering an Equation in the SOLVER

With the SOLVER feature of the TI-83, you can solve an equation for any variable in the equation. In the SOLVER, you can observe the effect that changing the value of one variable has on another and apply "what if" scenarios. This page shows how to enter the Illumination equation in the SOLVER.

1. Press **2nd** **SOLVER** to display the SOLVER equation entry screen.

Press **2nd** **ILLUM=INTEN*HEIGHT/DIST**. Press **2nd** **HEIGHT** **2nd** **DIST**. Press **2nd** **DIST** to select **DIST** from the menu; the characters **DIST** are copied to the cursor location.




3. Press **4** **3** to complete the equation that defines illumination in terms of intensity and height:
ILLUM=INTEN*HEIGHT/DIST **3**

As you enter the equation beyond 17 characters, it scrolls. Ellipsis marks (...) indicate that not all of the equation is displayed on the line. You can use **→** and **←** to scroll the equation.



4. Press **2nd** **SOLV**. The SOLVER equation screen is displayed.

The equation is displayed on the top line. The variables are listed in the order in which they appear in the equation. The variables **HEIGHT** and **BASE**, which define the equation variable **DIST**, are shown. The cursor is positioned at the end of the equation. The variables **HEIGHT** and **BASE** are shown. The variables **HEIGHT** and **BASE** are shown. The variables **HEIGHT** and **BASE** are shown.



bound defines the interval in which the SOLVER searches for a solution. The default values are **-1E99** to **1E99**.

Additional Solutions with the SOLVER

You can continue to explore solutions to equations with the SOLVER. You can solve for any variable within the equation to explore "what if" questions.

If the desired illumination is exactly 0.2 ft-c, and the intensity is still 1000 CP, at what height on the pole should the light be placed?


1. To change the value of ILLUM to .2, press the **CLEAR** key to clear the value on the line quickly and then type .2. The square dots disappear to show that the solution is not current.

Changing the Viewing Rectangle

You can graphically examine equations entered in the SOLVER. The viewing rectangle defines the portion of the graphing coordinate plane that is shown in the display. The values of the RANGE variables determine the size of the viewing rectangle. You can display and edit the values of the RANGE variables.

1. Press **2ND** **WINDOW** to display the RANGE editor.

You display and edit the values of the RANGE variables on this screen. The values shown are the standard default values.



The RANGE variables define the viewing rectangle. **XMin**, **XMax**, **YMin**, and **YMax** define the boundaries of the display. **XScale** and **YScale** define the tick marks on the **x** and **y** axes.



2. Graph the illumination example using new values for the RANGE variables, as shown.

Use **↑** or **ENTER** to move the cursor to each value and then type over the existing values to enter the new value. To enter -1, press **2ND** **1** and then press **=**.



Finding ■ Solution from ■ SOLVER Graph

The graph plots the variable on which the cursor is placed as the independent variable on the x axis and left-rt as the dependent variable on the y axis. Solutions exist for the equation where the function intersects the x axis.

1. Press **2nd** **GRAPH**. The graph plots **HEIGHT** on the x axis and left-rt on the y axis. The cursor is positioned on the graph. The independent variable on the x axis is shown on the right.

Notice from the graph that this problem has at least two solutions; we found the solution for **HEIGHT** at the larger value, 63.458763246529.



2. To solve for the other value of **HEIGHT**, we must supply a new initial guess or alter the limit. You can select a new initial guess with the graph cursor.

Use **←** and **→** to position the cursor near where the function crosses the axis at the smaller value. As you move the cursor, the coordinate values are displayed.

3. Press **ENTER** to select **SOLVE**. The value of **HEIGHT** identified by the cursor is used as the new initial guess. The first estimator is displayed, giving the calculation. The solution screen is displayed again with another solution for **HEIGHT**, 3.2022212466712.

The illumination on the surface is .2 ft-c and the intensity is 1000 CP, if the height of the light source is either 3.2022212466712 ft or 63.458763246529 ft.

63.458763246529
HEIGHT
BASE = HEIGHT * Y



Defining Functions to Graph

On the TI-85, functions are graphed for x and y when x is the independent variable and $y=y(x)$. You can store unevaluated expressions with the \rightarrow symbol (ALPHA function of the \rightarrow key). This page shows how to solve the illumination problem for a graphic calculator.

Graph the illumination equation and find the height that provides the maximum illumination for a base of 25 feet and an intensity of 1000 CP.

1. Press **[F10]** to return to the Home screen.
2. Press **[F10]** **[F10]** **HEIGHT** **[F10]** **[F10]** to store the unevaluated expression $\frac{1}{1000} \sqrt{1000^2 - 25^2}$ in the **HEIGHT** variable.
3. Press **[F10]** **[F10]** **INTEN** **[F10]** **[F10]** to store the value of the expression $\frac{1}{1000} \sqrt{1000^2 - 25^2}$ in the **INTEN** variable.
4. Press **[F10]** **[F10]** **COMPR** **[F10]** **[F10]** to store the value of the expression $\frac{1}{1000} \sqrt{1000^2 - 25^2}$ in the **COMPR** variable.
5. Press **[F10]** **[F10]** **ILLUM** **[F10]** **[F10]** to store the value of the expression $\frac{1}{1000} \sqrt{1000^2 - 25^2}$ in the **ILLUM** variable.
6. Press **[F10]** **[F10]** **ILLUM** **[F10]** **[F10]** to move the cursor to the beginning of the expression quickly. Press **[F10]** **[F10]** **[F10]** **[F10]** **[F10]** six times to delete **ILLUM**.

DATE: 1990-09-01
TIME: 10:00
PAGE: 1

NAME	NUMBER	DATE	TIME	TYPE	REMARKS

1010 INTERMEDIATE DIET

Displaying the Graph

After you have created and selected the function to graph and entered the appropriate viewing rectangle, you can display the graph.

1. Press **2nd** **[F5]** to select **GRAPH** to graph

(The **Y=** indicator appears on the screen.)

The display now shows the **Y=** indicator, the function, and the viewing rectangle.

Because **HEIGHT** is replaced by **x**, the current value of **x** is shown next to the point is plotted. The graph of the function for $0 \leq x \leq 100$ is plotted.



2. The graph shows that there is likely one maximum value of **ILLUM** for a height between 0 and 100.

Press **▶** to move the cursor to the graph's cursor just to the right of the center of the curve. The top shows the coordinates of the **x** and **y** of the point. Coordinate values for that point appear: **x,y**.



3. Using the arrow (movement) keys **◀**, **▶**, **▲**, and **▼** to move the cursor until it is positioned at the expected maximum of the function. As you move the cursor, the **x** and **y** display coordinate values are updated continually with the cursor position.



The free-moving cursor shows maximum illumination of 10.258064516 CD for heights from 14.28571429 to 35.71428571.

25.428571429000, with an accuracy of one display point, which means accuracy is ± 0.0000000001 , and accuracy is 0.02258064516, calculated and shown on right.

$$\text{Accuracy}_x = \frac{x_{\text{Max}} - x_{\text{Min}}}{128}$$

$$\text{Accuracy}_y = \frac{(y_{\text{Max}} - y_{\text{Min}})}{62}$$

Using the TRACE feature of the TI-85, you can move the cursor along a function, showing the x and y display coordinate values of the cursor location on the function.


1. Press **[F4]** to select (TRACE). The TRACE cursor appears near the middle of the display on the function.

The coordinate values of the cursor location, $x, y1(x)$, are displayed on the bottom line of the display. No menu items are shown. The y value shown is the calculated value of the function at the displayed value of x. That is, if $y1=fx$, then the value of y shown is fx .

2. Use **[▶]** and **[◀]** to move along the function until you have traced to the largest y value.

The maximum illumination is .6157776262 CP if the height is 17.46031746 ft.

This value of y is the function value fx at the x display coordinate value. It is different from the value found with the free-moving cursor, which is based on the RANGE setting.



Finding ■ Maximum Graphically

With the operations on the GRAPH MATH menu, you can analyze a displayed graph to determine where minimum and maximum values, inflection points, and intercepts occur.

1. Press **2ND** to display the GRAPH menu. Press **W** to display additional items on the GRAPH menu.

2. Press **F1** to select (MATH). Press **W** to display additional items on the GRAPH MATH menu.

3. Press **5** to select (MAX). The TRACE cursor appears near the middle of the display on the function at the point $(x, y1(x))$.



4. Press **ENTER**. The calculated maximum is displayed in the cursor coordinates at the bottom of the display, .61584028714 at an x value of 17.677668581.

This value of y, which is the mathematically calculated maximum, is larger than the value found with the TRACE cursor. This calculated maximum is the most accurate of the three graphical solutions we have tried.



Graphing the Derivative

The maxima and minima of a continuous differentiable function, if they exist, occur where the first derivative is equal to 0. On the TI-85, you can graph the derivative of a function.

1. Press **GRAPH**. Press **F1** to display the $y(x)$ editor.

Press **ENTER** to move to $y2$.



2. The calculus functions are grouped on the **CALC** menu. Press **2ND** **[CALC]** to display the calculus menu on the bottom line.

3. Press **F7**. The function name for the exact first derivative, **der1**, is copied to the cursor location.




4. Press **2ND** **[M2]** to copy y from the menu on the seventh line to the cursor location, then type 1 to enter the name of the first equation, $y1$. Press **ENTER**.

5. On the TI-85, you can evaluate the calculus functions with respect to any variable, but to be meaningful in graphing, the variable of differentiation or integration must be x .

Press **2ND** **[XMM]** or **2ND** **[M1]** to copy x to the cursor location. Press **ENTER**.

der1(y1,x) is the exact derivative, evaluated at the current value of x . When this equation is graphed, the derivative is calculated for each value of x on the graph.



Zooming In on the Graph

You can magnify the viewing rectangle around a specific cursor location by selecting the Zoom In instruction from the ZOOM menu.

1. Press **(2ND)** **(F6)** **(M5)** to select (GRAPH and graph both functions. The busy indicator displays while the graph is plotted.

The viewing rectangle is the same as you defined in the **2ND** **(F2)** **(ZOOM)** menu. **Figure 1** shows the graph plotted on the graph of the different rate hypothesis to assist in identifying the **X** axis.



2. Press **(F5)** to select (ZOOM).
3. To zoom in, press **(F5)** to select (ZIN) from the menu.

The cursor appears at the middle of the display.



4. Use the cursor-movement keys to position the cursor near where the derivative function intersects to cross the **X** axis. Press **(ENTER)**. The position of the cursor becomes the center of the next zoom rectangle. The busy indicator displays while the graphs are plotted.



The new viewing rectangle has been adjusted in both the **X** and **Y** directions by factors of 4, which are the default values for the zoom factors.

The coordinate values may vary depending on the cursor location.

Finding a Root Graphically

The TI-85 can find the root (zero) of a graphed function and can calculate the value of the function for any value of x . Find the x value where the root of the derivative function $\text{der1}(y1,x)$ occurs and use it to calculate the maximum of the function.

1. Press **ON** **2ND** **GRAPH** to display the GRAPH menu on the bottom line of the display. Press **WE** to display and freeze the graph. Press **2** to select **Y1** to display the GRAPH **Y1**ATH display screen.



2. Press **1** to select **ROOT**. The TRACE cursor appears on the **y1** function in the **y1** column of the display. The **y1** function is "above" the display.

3. Press **2** to move the cursor to the derivative function, **y2**, as indicated by the 2 in the upper right corner of the display. You can use **←** and **→** to move the cursor to a point near the root.

4. Press **ENTER**. The trace indicator displays **y1=1.76778655E1** at the bottom of the display. The cursor is positioned at the function of the display **y1=1.76778655E1** at the **x** value of **17.6778655**.

5. Press **2ND** **WE** **2ND** **WE** to select **(EVAL)**. Press **WE** **2ND** **WE** to enter the solution to **ROOT** as the value for **x**. The results cursor is displayed on the **y1** function at the specified **x**.

On page 15, **PMAX** found a function maximum of **y=61584028714** at **x=17.6778655E1**. Corresponding to that **max**, **ROOT** supplied the root of the derivative at **x=17.67786553**, which evaluated to a **max** of **y1=61584028714**.



Other Features

This Getting Started section introduced you to operating the calculator, the function graphing features, and one equation-solving feature. The remainder of this guidebook describes these features in more detail and also covers the other capabilities of the TI-85.

Other Capabilities of the TI-85

- Store, graph, and analyze up to 99 functions in function graphing (Chapter 4), up to 99 polar equations in polar graphing (Chapter 5), up to 99 parametric equations in parametric graphing (Chapter 6), and a system of up to nine first-order differential equations (Chapter 7).
- Use **DRAW** and **Shade** features to emphasize or analyze on function, polar, parametric, and differential equation graphs (Chapter 4).
- Solve an equation for any variable, solve a system of up to 30 simultaneous linear equations, and find the real and complex roots of up to a 30th order polynomial equation (Chapter 14).
- Enter and store any number of matrices and vectors with dimension up to 255. Has standard matrix operations, including elementary row operations, and standard vector operations (Chapter 13).
- Perform one-variable and two-variable statistical analyses. Enter and store any number of datapoints. Seven regression models are available: linear, logarithmic, exponential, power, and second-, third-, and fourth-order polynomial models. You can analyze data graphically with histograms, scatter plots, and line drawings and plot regression equation graphs (Chapter 15).
- Enter programs that include extensive control and input/output instructions. Enter and store any number of programs (Chapter 16).
- Share variables and programs with another TI-85. Print graphs and programs, enter programs, and store data on a disk through an IBM[®]-compatible or Macintosh[®] computer (Chapter 19).
- The TI-85 has 32K of RAM.

This chapter describes the TI-85 and provides general information about its operation.

Chapter Contents	
Turning the TI-85 On and Off	1-2
Setting the Display Contrast	1-3
The 2nd and ALPHA Keys	1-4
The Display	1-6
The Equation Operating System	1-8
Equation List Editing	1-10
Expression and Functions	1-12
Last Answer	1-13
Last Entry	1-14
Example: Convergence of a Series	1-15
The TI-85 Memory	1-16
Using the Memory	1-17
Selecting the Memory	1-18
Memory and the TI-85	1-20
The CLT/ACC	1-22
The CUSTOM Menu	1-23
Setting Modes	1-24
Input Conventions	1-29

Turning the TI-85 On and Off

To turn the TI-85 on, press the **2** key. To turn it off, press and release **[2/]** and then press **[OFF]**. After about five minutes without any activity, the APD™ Automatic Power Down feature turns the TI-85 off automatically.

Turning the Calculator On



Press **[2]** to turn the TI-85 on.

- If you pressed **[2/]** **[OFF]** to turn the calculator off, the display shows the Home screen as it was when you last used it.
- If the APD feature turned the calculator off, the TI-85, including the display, cursor, and any error conditions, will be exactly as you left it.

Turning the Calculator Off

Press and release **[2/]** and then press **[OFF]** to turn the TI-85 off.

- Any error condition is cleared.
- All settings and memory contents are retained in memory by the Constant Memory™ feature.

The APD™ Automatic Power Down Feature

To prolong the life of the batteries, the APD feature turns the TI-85 off automatically after about five minutes without any activity. When you press **[2]**, the TI-85 will be exactly as you left it.

- The display, cursor, and any error conditions are exactly as you left them.
- All settings and memory contents are retained in memory by the Constant Memory feature.

Batteries

The TI-85 uses four AAA alkaline batteries and has a user-replaceable back-up lithium battery. You can change the batteries (Appendix B) without losing any information in memory.

Setting the Display Contrast

The brightness and contrast of the display depend on room lighting, battery freshness, viewing angle, and adjustment of the display contrast. The contrast setting is retained in memory when the TI-85 is turned off.

Adjusting the Display Contrast

You can adjust the display contrast to suit your viewing angle and lighting conditions at any time. As you change the contrast setting, the display contrast changes, and a number in the upper right corner indicates the current contrast setting between 0 (lightest) and 9 (darkest).

To adjust the contrast:

1. Press and release the **[AD]** key.
2. Use one of two keys:
 - To increase the contrast, press and hold **[A]**.
 - To decrease the contrast, press and hold **[V]**.

Note: If you adjust the contrast setting to zero, the display may become completely blank. If this happens, press and release **[ON]** and then press and hold **[A]** until the display reappears.

When to Replace Batteries

When the batteries are low, the display begins to dim (especially during calculations), and you must adjust the contrast to a higher setting. If you find it necessary to set the contrast to a setting of 8 or 9, you should replace the four AAA batteries soon.

Note: To replace batteries without losing information stored in memory, follow the directions on page B-2.

The 2nd and ALPHA Keys

Most keys on the TI-85 access more than one operation. The additional operations are printed above the keys. To access them, press **2nd** or **ALPHA** before you press the key.

Tl-85 Keys

2nd operation → √ K ← ALPHA operation
 ↓ ↙
 r² Primary operation

2nd Operations

To access a 2ND operation, first press and release [2d] and then press the appropriate key.

When you press [2d], the cursor changes to □ to indicate that the next keystroke is a 2nd operation.

To cancel 2nd, press [2d] again.

In this guidebook, 2nd operations are shown in brackets and preceded by [2d]; for example, [2d] |√|.

ALPHA Characters

To access the letter or character printed to the right above a key, first press [ALPH] or [2d] alpha and then press the appropriate key.

- To make the next keystroke an uppercase alphabetic character, press [ALPH]. The cursor changes to A. To cancel ALPHA, press [ALPH] until the normal cursor appears.
- To make the next keystroke a lowercase alphabetic character, press and release [2d], and then press alpha. The cursor changes to a. To cancel alpha, press [ALPH] until the normal cursor appears.

Alpha-Lock

ALPHA-lock (uppercase) and alpha-lock (lowercase) make each subsequent keystroke an alphabetic character. You do not need to press **ALPHA** or **alpha** before every character to enter display text or the names of variables, functions, or instructions.

Action	Keystrokes
Set uppercase ALPHA-lock	ALPHA ALPHA
Set lowercase alpha-lock	2nd alpha ALPHA or 2nd alpha 2nd alpha or ALPHA 2nd alpha
Cancel ALPHA-lock	ALPHA
Cancel alpha-lock	2nd alpha or ALPHA ALPHA
Change from uppercase ALPHA-lock to lowercase alpha-lock	2nd alpha
Change from lowercase alpha-lock to uppercase ALPHA-lock	ALPHA


Note: **SD** and name prompts automatically set the keyboard in ALPHA-lock. **2nd** does not take the keyboard out of ALPHA-lock or alpha-lock.

The Display

The TI-85 displays text, graphs, and menus. Graphs are described in Chapter 4. Menus are described on pages 1-16 to 1-19.

The Home Screen

The Home screen is the primary screen of the TI-85, where you enter expressions to be evaluated and see the results.



Expression
Result

If text is displayed, the screen can have up to eight lines of 31 characters per line. If all text lines of the display are filled, text "scrolls" off the top of the display.

The MODE settings control the way expressions are interpreted and results are displayed (pages 1-24 to 1-27).

Displaying Expressions

On the Home screen and in the program editor (Chapter 16), if an expression is longer than one line, it wraps to the beginning of the next line.

Displaying Results

When an expression is evaluated on the Home screen, the result is displayed on the right side of the next line. If a result is too long to display in its entirety, ellipsis marks (...) are shown at the left or right. Use \rightarrow and \leftarrow to scroll the result. If the result is a matrix with more rows than the screen can display, use \uparrow and \downarrow to scroll the result vertically. For example:






Expression
Result





Returning to the Home Screen

To return to the Home screen from any other screen, press 2nd [QUIT].

Display Cursors

In most cases, the appearance of the cursor indicates what will happen when you press the next key.

Cursor	Appearance	Meaning
Entry cursor	Solid flashing rectangle	The next keystroke  entered at the cursor; it types over any character.
INS (insert) cursor	Flashing underline	The next keystroke is inserted at the cursor.
2nd cursor	Flashing 	The next keystroke is a 2nd operation.
ALPHA cursor	Flashing A	The next keystroke is an uppercase alphabetic character.
alpha cursor	Flashing 	The next keystroke is a lowercase alphabetic character.
"full" cursor Chessboard	rectangle	You have entered the maximum characters in a name, or memory is full

If you press ,  (alpha), or  during an insertion, the underline cursor changes to an underlined A, a, or  cursor.

Busy Indicator

When the TI-85 is calculating or graphing, a moving vertical bar shows in the upper right of the display as a busy indicator. (When you pause a graph or a program, the busy indicator is a dotted bar.)

The Equation Operating System

With the TI-85's Equation Operating System (EOS™), you enter numbers and functions in a simple, straightforward sequence. EOS evaluates expressions according to the standard priorities of mathematical functions and uses parentheses for grouping.

Order of Evaluation

A function returns a value. EOS evaluates functions in an expression in this order:

- Functions that are entered after the argument, such as x^2 , x^{-1} , $1/x$, $\%$, $\sqrt{}$, and conversions.
- Powers and roots, such as $2\sqrt{5}$ or $5\sqrt[3]{32}$.
- Implied multiplication where the second argument is a number, variable name, constant, list, matrix, or vector or begins with an open parenthesis, such as $4A$, $A\ B$, $(A+B)4$, or $4(A+B)$.
- Single-argument functions that precede the argument, such as negation, $\sqrt{}$, \sin , or \ln .
- Implied multiplication where the second argument is a multiargument function or a single-argument function that precedes the argument, such as $2\ \text{gcd}(144,64)$ or $A\ \sin\ 2$.
- Permutations nPr and combinations nCr .
- Multiplication and division.
- Addition and subtraction. An $=$ in an expression, rather than an equation, is evaluated as $-$. For example, $A+B=C+1$ is evaluated as $A+B-(C+1)$.
- Relational functions, such as $>$ or \leq .
- Boolean operator **and**.
- Boolean operators **or** and **xor**.

Within a priority group, EOS evaluates functions from left to right. However, two or more single-argument functions that precede the same argument are evaluated from right to left. For example, $\sin(\text{fPart}\ \ln\ 8)$ is evaluated as $\sin(\text{fPart}(\ln\ 8))$.

Calculations within a pair of parentheses are evaluated first. Multiargument functions, such as $\text{gcd}(144,64)$ or $\text{der1}(\sin\ \text{ANG}, \text{ANG}, x)$, are evaluated as they are encountered.

Implied Multiplication

The TI-85 recognizes implied multiplication. For example, it understands 2π , $4 \sin 45$, $5(1+2)$, and $(2*5)7$ as implied multiplication. Except between two numbers, a space indicates implied multiplication, as in $A B$ or $B 3$.

Variable names can be more than one character; the TI-85 recognizes AB and $b2$ as variable names. Variable names cannot start with a number; $3AB$ and $3b2$ are interpreted as implied multiplication ($3*AB$ and $3*b2$).

Parentheses

All calculations inside a pair of parentheses are completed first. For example, in the expression $4(1+2)$, EOS first evaluates the portion of the expression inside the parentheses $1+2$, and then multiplies the result by 4.

You can omit any right (close) parentheses at the end of an expression. All "open" parenthetical elements are closed automatically at the end of an expression and preceding the \rightarrow (store) or display conversion instructions.

Note: If the name of a list, matrix, or vector is followed by an open parenthesis, it does not indicate implied multiplication. It is used to access specific elements in the list, matrix, or vector.

Negation

To enter a negative number, use the negation function. Press $(-)$ and then enter the number. On the TI-85, negation is in the fourth group in the EOS hierarchy. Functions in the first group, such as squaring, are evaluated before negation. For example, the result of $-X^2$ is a negative number; the result of -9^2 is -81 . Use parentheses to square a negative number: $(-9)^2$.

Note: Use the $(-)$ key for subtraction and the (\pm) key for negation. If you press (\pm) to enter a negative number, as in $9 (\pm) 7$, it is an error. If you press $9 (\pm) 7$ or $(\text{ALPHA}) A (\pm) (\text{ALPHA}) B$, it is interpreted as implied multiplication ($9*-7$ or $A*-B$).

Entering and Editing

The arrow keys in the upper right of the keyboard control the movement of the cursor. In normal entry, a keystroke types over the character or characters at the position of the cursor. The **DEL** and **INS** keys delete or insert characters.

The Cursor-Movement Keys

← and **→** move the cursor within an expression. The cursor stops when it reaches the beginning or end of the expression except in the program editor.

⏮ **←** or **⏭** **→** moves the cursor to the beginning or end of the expression.

⏶ and **⏷** move the cursor between lines in the current expression on the Home screen. **⏶** on the top line of an expression on the Home screen moves the cursor to the beginning of the expression. **⏷** on the bottom line moves the cursor to the end.

If you press and hold a cursor-movement key, the cursor movement repeats until you release the key.

The Edit Keys

Key	Action
INS	Inserts characters at the underline cursor.
DEL	Deletes the character at the cursor.
ENTER	Executes the expression or instruction.
CLR	<ul style="list-style-type: none">On a line with text on the Home screen, clears (blanks out) that line.In an editor, clears (blanks out) the expression number where the cursor is located. It does not delete a page.On a blank line on the Home screen, clears everything on the Home screen.

To end insertion, press **ESC**, **DEL**, or a cursor-movement key **←**, **→**, or **⏶**, or **⏷** except in the program editor (IS PR).

You can press and hold **DEL** to delete a long sequence of characters.

Entering a Name

You can enter the names of functions, instructions, variables, and constants in one of several ways:

- Type the characters of the name.
- Press the key or select from a menu to copy the name to the cursor location.
- Select the name from the CATALOG.

If you type the name, you must enter each character, including a space (the alpha character above \square) preceding the name and the space or open parenthesis after the name, if required. If you select the name from the keyboard or a menu, all required characters are copied.

The TI-85 ignores uppercase and lowercase when it interprets names of functions and instructions (but not the names of variables and constants). For example, to calculate a log, you can press \square , type the letters l o g (followed by a space), or type the letters L O G (followed by a space).

type the letters L O G (followed by a space).

Character Entry

The TI-85 treats an expression as individual characters, regardless of whether a name was entered by typing each character or by copying the name from a key, menu, or selection screen. Names copied from a key, menu, or selection screen are copied as if the individual letters were typed. You can type over any character in the name. For example, if you press \square , the characters sin followed by a space are displayed. If you then press \square \square \square \square G N, the function is changed to siGN.

Expressions and Instructions

On the TI-85, you can enter expressions, which return a value. In most places where a value is required. You enter instructions, which initiate an action, on the Home screen or in the program editor (Chapter 16).

Expressions

An expression is a complete sequence of numbers, variables, functions, and their arguments that evaluate to a single result. On the TI-85, you enter an expression in the same order that it normally is written. For example, $n \times \text{radius}^2$ is an expression.

Expressions can be used as commands on the Home screen to calculate a result. Expressions may be used in instructions to enter a value. In editors, expressions may be used to enter a value.

Instructions

An instruction is a command that initiates an action. For example, **CIOrw** is an instruction that clears any drawn elements from a graph. Instructions cannot be used in expressions.

Entering an Expression

To create an expression, you enter numbers, variables, and functions from the keyboard and from display menus. An expression is completed when you press **ENTER**, regardless of the cursor location. The entire expression is evaluated according to EOS (page 1-8), and the result is displayed.

Example of Entering an Expression

Calculate $3.76 \div (-7.9 \div \sqrt{5}) + 2 \log 45$.

3.76	÷	(-)	7.9	÷	
2nd	√	5	÷	2	LOG
45					
ENTER					
					2.64257525233

Entering More than One Command on a Line

To enter more than one instruction or expression on a line, separate them with a colon. For example, $5 \rightarrow A:2 \rightarrow B:A/B$ **ENTER** displays 2.5. All the commands are stored together in Last Entry (page 1-14).

Interrupting a Calculation

While the busy indicator is displayed, indicating that a calculation or a graph is in progress, you can press **STOP** to stop the calculation. (There may be a delay.) Except in graphing, the break ERROR screen is shown.

- To go to where the interrupt occurred, select **GOTO**.
- To return to the Home screen, select **QUIT**.

Last Answer

When an expression is evaluated successfully from the Home screen or from a program, the TI-85 stores the result to a special variable, **Ans** (Last Answer). When you turn the TI-85 off, the value in **Ans** is retained in memory.

Using Last Answer in an Expression

You can use the variable **Ans** in most places where its data type is valid. Press $\boxed{\text{ANS}}$ and the variable name **Ans** is copied to the cursor location. When the expression is evaluated, the TI-85 uses the value of **Ans** in the calculation.

Calculate the volume of a cube 1.5 feet on each side, and then calculate the volume in cubic inches.

1.5×3	1.5^3	
1.5		3.375
$12 \times 3 \times \boxed{\text{ANS}}$	12^3 Ans	
ENTER		5832

Continuing an Expression

You can use the value **Ans** as the first entry in the next expression, without entering the value again. On the blank line on the Home screen, enter the function $\pi r^2 h$; the TI-85 types the variable name **Ans** followed by the function:

Calculate the area of a circle of radius 5 inches. Then calculate the volume of a cylinder of height 3 inches and radius 5 inches.

$\pi r^2 h$	$\pi 5^2$	
$\boxed{\text{ANS}}$		78.5398163397
$\times 3$	Ans^2	
ENTER		235.619449019

Storing Results

To store a result, store **Ans** to a variable before you evaluate another expression.

$\boxed{\text{VOLUME}}$	$\text{Ans} \rightarrow \text{VOLUME}$	
ENTER		235.619449019

Last Entry

When you press **2ND** **ENTER** on the Home screen to evaluate an expression or execute an instruction, the expression or instruction is stored in a special storage area called Last Entry, which you can recall. When you turn the TI-85 off, Last Entry is retained in memory.

Using Last Entry

To recall Last Entry and edit it, press **2ND** **ENTER** (ENTRY). The cursor is positioned at the end of the entry. Because the TI-85 updates the Last Entry storage area only when **2ND** **ENTER** is pressed, you can recall the previous entry even if you have begun entering the next expression. However, when you recall Last Entry, it replaces what you have typed.

5 2ND 7	5+7	
2ND ENTER		12
2ND ENTER	5+7	

Entries Containing More than One Command

If the previous entry contained more than one command separated with a colon (page 1-12), all the commands are recalled. You can recall all commands, edit any command, and then execute all commands.

Using the equation $A = \pi r^2$, find by trial and error the radius of a circle that covers 200 square inches. Use **R** as your first guess.

8 2ND STOP R ALPHA (Z) 1		
2ND 1 ALPHA R (Z)	R \rightarrow R PR	
ENTER		201.06192983
2ND ENTER	R \rightarrow R PR R ²	
2ND 7 (INS) .95	7.95 \rightarrow R PR R ²	
ENTER		

Continue until the result is as accurate as you want.

Reexecuting the Previous Entry

Press **2ND** **ENTER** on a blank line on the Home screen to execute Last Entry; the entry does not display again.

0 2ND N	0 \rightarrow N	
ENTER		11
N \rightarrow N + 1 2ND N 2ND		
1 N ALPHA (Z) 1	N \rightarrow 1 \rightarrow N N ² 1	
ENTER		0
2ND ENTER		3
2ND ENTER		8

Example: Convergence of a Series

Show that when $A < 1$, the series A^n converges to $A/(1-A)$ as N increases. You can use the TI-85 functions `sum` and `seq` (Chapter 3) to calculate a series.

Procedure

Calculate the series A^N for $A = 1/2$ at $N = 1, 5$, and 100 . `sum` returns the sum of all elements in a list, `seq` generates a list; the form for `seq` is:

```
seq(expression, variable, name, begin, end, increment)
```

Enter all expressions and instructions on the same command line so that you can recall, edit, and execute them. Store 1 in the variable NTH (for the n th element) and 1/2 to the variable A.

Remember that function names are not case-sensitive, but variable names are. The keyboard remains in ALPHA-lock after [STC], even when you press **ON**.

```
1 → NTH N:1/2
1 → 2 → A:
SEQ(A,N)
N → N:1/2
1 → NTH
1 → 1/2
LIST(SUM) LI
ST
ENTER
```

Recall Last Entry. Change NTH to 5 and evaluate. Repeat for NTH=100.

```


MC [ENTRY]
1,NTH,1)→A:seq(A^N,N
,1,NTH,1)→LIST:sum LIST
5→NTH:1/2→A:seq(A^N,N
,1,NTH,1)→LIST:sum LIST
96875
FAIR
[ENTRY] [DE] 1
[INS] 00
100→NTH:1/2→A:seq(A^N
,N,1,NTH,1)→LIST:sum
LIST
INTER

```

The TI-85 Menu

To leave the keyboard uncluttered, the TI-85 uses display menus to access many additional operations. The five keys immediately below the display are used to select items from menus. Specific menus are described in the appropriate chapters.

The Menu Keys



On the TI-85 keyboard, the menu keys are **F1**, **F2**, **F3**, **F4**, and **F5**. The 2nd operations of the menu keys are (M1), (M2), (M3), (M4), and (M5). Menu items are shown above the five menu keys.

The Menu Items

Menu items can display on the bottom two lines (seventh and eighth lines) of the display. If any text is displayed on a line where a menu is to be displayed, the text in the display scrolls up a line.

The appearance of a menu item generally helps to identify what the menu item is.

- The names of functions, which return a value and are valid within an expression, generally begin with a lowercase letter; for example, **rPart** or **Imag**.
- The names of instructions, which initiate an action from a command line, generally begin with a capital letter; for example, **Shade** or **CIDrw**.
- Menu items that access a lower-level menu or that perform immediate actions, generally are in all uppercase letters; for example, **NUM** or **ZOUT**.

Displaying Menus

If you select a menu item that displays another menu, the first menu may move to the seventh line; the new menu displays on the eighth line.

Displaying a Menu

Many of the 2nd operations, such as MATRX, VECTR, CPLX, MATH, and LIST, access menus of characters or names of variables, functions, and instructions to copy to the cursor location. When you press one of these keys, the eighth line of the display shows the menu items. For example, $\boxed{\text{CPLX}}$ labels the menu keys with complex number functions:

conj real imag abs angle

The menu items may access lower-level menus. For example, if you press $\boxed{\text{MATH}}$, the menu keys are labelled with the names of menus, each of which accesses a menu of math functions:

NUM PROB ANGLE HYP MISC

Displaying Additional Items in a Menu

A menu may have up to fifteen menu items, but only five are displayed at one time. ► at the right of the menu items indicates that there are more items in the menu. Press $\boxed{\text{MORE}}$ to label the menu keys with the next group of menu items. If you are on the final group, $\boxed{\text{MORE}}$ displays the first group. For example, on the MATH NUM menu:

 MORE

round iPart fPart int abs sign min max mod

 MORE

In this guidebook, all items in a menu usually are shown at once, stacked vertically; for example:

round iPart fPart int MORE
sign min max MORE

Selecting from Menus

You can select an item from the menu on the eighth line or from the menu on the seventh line.

Selecting an Item from the Menu on the Eighth Line

To select a menu item from the eighth line, press the corresponding menu key, **[M]**, ... **[F]**

- If the item is a character or a name, it is copied to the cursor location, typing over existing characters (except in insert mode). If not all characters in a name can display, the name is truncated in the menu item, but the full name is copied to the cursor location. The menus do not change.
- If the item is an editing operation, such as **INS** (insert row), the display changes as soon as you select the operation. The menus do not change.
- If the item is an action, such as **SOLVE**, the action occurs immediately. The menus change if appropriate.
- If the item accesses another menu, the menu keys are labelled immediately with the new menu.

In this guidebook, menu items shown enclosed by brackets (for example, **[HYP]**) indicate that you are to select that menu item.

The Menu on the Seventh Line


If you select a menu item that accesses another menu, the menu from the eighth line may move to the seventh line, and the name of the selected menu is highlighted.

For example, selecting **NUM** from the **MATH** menu on the Home screen moves the **MATH** menu to the seventh line and displays the **MATH NUM** menu items in the eighth line. On the seventh line, **NUM** is highlighted.



Accessing Menus from an Editor

An exception occurs if you are in a full-screen editor, such as the program or matrix editor. In this case, the editor menu remains on the seventh line for convenience.



Selecting an Item from the Menu on the Seventh Line

If a menu is displayed on the seventh line, you can select an item from it in one of the following ways:

- Press **[2nd]** and then press the menu key, (M1), . . . , (M6), that corresponds to the item that you want. For example **[2nd]** (M2) on the screen above would copy **y** to the cursor location.
- Press **[↓]**, which causes the menu on the seventh line to "move down" to the eighth line. Then press the menu key (F1), . . . , (F6) that corresponds to the item that you want. For example **[↓]** **[F4]** on the screen above would delete function **y1**.

"Exiting" a Menu

When you press **[↑]**:


- If a menu is displayed on the seventh line, that menu "moves down" to the eighth line. The display does not change.
- If a menu is displayed only on the eighth line, you are returned to the Home screen.

Moving around the TI-85

In addition to changes in the menu lines, the display may change when you press a key or select from a menu.

Moving to a Full-Screen Editor

Many of the keys on the TI-85 access applications with full-screen editors where you enter expressions as you do on the Home screen. The full-screen editors are:


CONS EDIT	POLY	GRAPH $y(x)=$
LIST EDIT	SOLVER	GRAPH $r(q)=$
MATRIX 	SIMULT	GRAPH $E(t)=$
VECTR EDIT	MATH INTER	GRAPH $O'(t)=$
STAT EDIT	STAT FCST	GRAPH RANGE
PRGM EDIT		GRAPH ZOOM ZFACT

When you select one of these:

- You "leave" the Home screen or the application in which you are working, and the appropriate editor displays.
- Any existing menu lines are cleared. The editor menu, if any, displays on the eighth line.




Working on a Full-Screen Editor

When you are working on a full-screen editor and press a key that displays a menu:

- The editor remains unchanged.
- The editor menu moves to the seventh line (if it is not already there), and the selected menu displays on the eighth line. You still can access editing operations (such as **INS**) or instructions (such as **SOLVE**) with the  key.

Leaving an Editor

To leave an editor:

- Press  (**QUIT**) to return to the Home screen.
- Press  one or more times to return to the previous menu, display, or the Home screen.
- Press the appropriate keys to move to another application, such as  (**SOLVER**).

Pull-Down Screens The VARS and CATALOG selection screens temporarily replace the current display.

- The current display is replaced, but you have not "left" the application in which you are working.
- The VARS or CATALOG menu is displayed.

When you press **EXIT** or make a selection, the current display and menus are shown again.

The Prompt Line Sometimes you will be prompted for a value or variable name on the prompt line, the line above the menu(s).



Clearing a Prompt Press **CLEAR** to clear anything on the prompt line. Press **CLEAR** on a blank prompt line to clear the prompt and return the cursor to the editor or graph.

Correcting an Error on the Prompt Line When an error occurs on the prompt line, ERR nn is displayed at the right of the line. It is not necessary to clear the error message to edit the entry. To clear the error and the entry, press **CLEAR**.

Returning to the Home Screen To return to the Home screen from any other screen, press **2nd** **QUIT**.


You also can press **EXIT** one or more times until the Home screen is displayed.

The CATALOG

You can use the **CATALOG** to copy the name of an instruction or a function to the cursor location in an expression that you are editing. These include the functions and instructions from the keyboard and from **ROMAN**.

The CATALOG Selection Screen

When you press **[2nd]** **[CATALOG]**, the **CATALOG** screen temporarily replaces the screen on which you are working.



The names of functions and instructions are displayed in alphabetical order. Names that do not begin with an alphabetic character (such as + or >Bin) follow Z. An arrow at the left of the name indicates the selection cursor. To move around the list:

- Press a letter to move quickly to names beginning with that letter. (The keyboard is set in ALPHA-lock.) Uppercase and lowercase names are intermixed.
- Press **[A]** to move quickly to the names beginning with special characters at the end of the list.
- Use **(PAGE)←** and **(PAGE)→** to move to the next page of names.
- Use **↓** and **↑** to move down and up the list.

Copying a Name to an Expression

Press **[ENTER]** to select the name to copy. The **CATALOG** selection screen disappears and the name is copied to the cursor location.

Leaving the CATALOG

To leave the **CATALOG** without making a selection:

- Press **[EXIT]** or **[CLEAR]** to return to the application in which you are working.
- Press **[2nd]** **[QUIT]** to return to the Home Screen.


The CUSTOM Menu

The CUSTOM menu has fifteen items. You can copy the names of up to fifteen functions or instructions from the CATALOG to the CUSTOM menu. This provides easy access to those you use most frequently.

Entering the Name of a Function or Instruction in the CUSTOM Menu

The names of functions and instructions are copied from the CATALOG to the CUSTOM menu.

1. Display the CATALOG selection screen. Move the cursor to the name you want to copy to the CUSTOM menu.
2. Select (CUSTOM). The menu keys are labelled with the first five items of the CUSTOM menu (which may be blank). To display the other menu items, press \square .



3. When the menu item to which you want to copy the name is displayed, press that menu key. The name is copied to the CUSTOM menu, replacing any name that might be there. The CUSTOM menu remains.

Blanking out a CUSTOM Menu Entry

To blank out (clear) a menu item in the CUSTOM menu:

1. Press \square (CATALOG).
2. Select (BLANK). The menu keys are labelled with the first five items of the CUSTOM menu. Press \square to move around the menu.
3. When the menu item that you want to clear is displayed, press that menu key. The item is cleared. The CUSTOM menu remains.

Using a CUSTOM Menu Entry in an Expression

To copy a function or instruction from the CUSTOM menu to the expression you are entering or editing, press \square and select the appropriate menu key.

Setting Modes

Modes control how numbers and graphs are displayed and interpreted. MODE settings are retained by the Constant Memory™ feature when the TI-85 is turned off. All numbers, including elements of matrices, vectors, and lists, are displayed according to the current MODE settings.

Checking MODE Settings

Press **MODE** to display the MODE settings. The current settings are highlighted. The specific MODE settings are described on the following pages.

Setting	Meaning
Normal Sci Eng	Numeric display format
Float 012345678901	Number of decimal places
Radian Degree	Unit of angle measure
Rect C PolarC	Complex number display format
Func Pol Param DfEq	Type of graphing
Dec Bin Oct Hex	Number base
Rect V CylV SphereV	Vector display format
dxDer1 dxNDer	Type of differentiation

Changing MODE Settings

1. Use **↑** or **↓** to move the cursor to the line of the setting that you want to change. The setting that the cursor is on flashes.
2. Use **→** or **←** to move the cursor to the setting that you want.
3. Press **ENTER**.

Leaving the MODE Selection Screen

When the MODE settings are as you want them, leave the MODE selection screen in one of the following ways:

- Press the appropriate keys to go to an application.
- Press **2nd** [QUIT], **EXIT**, or **2nd** [CLEAR] to return to the Home screen.

Normal, Scientific, or Engineering Notation Display Format

Notation formats affect only how a numeric result is displayed on the Home screen. Numeric results can display with up to 12 digits and a three-digit exponent. You can enter a number in any format.

Normal display format is the way in which we usually express numbers, with digits to the left and right of the decimal, as in 12345.67.

Sci (scientific) notation expresses numbers in two parts. The significant digits display with one digit to the left of the decimal. The appropriate power of 10 displays to the right of e , as in 1.234567e4.


Eng (engineering) notation is similar to scientific notation. However, the number may have one, two, or three digits before the decimal, and the power-of-10 exponent is a multiple of three, as in 12.34567e3.

Note: If you select normal display format, but the result cannot display in 12 digits or the absolute value is less than .001, the TI-86 changes to scientific notation for that result only.

Floating or Fixed Decimal Display Setting

Decimal settings affect only how a result is displayed on the Home screen. They apply to all three notation display formats. You can enter a number in any format.

Float (floating) decimal setting displays up to 12 digits, plus the sign and decimal.

The **fixed decimal** setting displays the selected number of digits (0 to 11) to the right of the decimal. Place the cursor on the number of decimal digits you want and press .

Radian or Degree Angle Setting

Angle settings control how the TI-85 interprets angle arguments in trig functions, polar/rectangular complex polar numbers, and 2-element and 3-element cylindrical or spherical vectors.

Radian setting interprets the arguments as radians. Results display in radians.

Degree setting interprets the arguments as degrees. Results display in degrees.

Rectangular or Polar

Complex Number Display Format

Complex number format affects only how a complex result is displayed. You can enter a complex number in either format.

RectC (rectangular complex) number format displays the result in the format (real,imag).

PolarC (polar complex) number format displays the result in the format (magnitude \angle angle).

Function, Polar, Parametric, or Differential Equation Graphing MODE

Func (function) graphing plots functions where y is expressed in terms of x (Chapter 4).

PoI (polar) graphing plots functions where r is expressed in terms of θ (Chapter 5).

Param (parametric) graphing plots relations where x and y are each expressed in terms of t (Chapter 6).

DiffEq (differential equation) graphing plots differential equations (Chapter 7).

**Decimal, Binary,
Octal, or
Hexadecimal
Number Base**

Number base format controls how an entered number is interpreted, unless another base is specified (Chapter 10), and how results are displayed. Nondecimal modes are valid only on the Home screen and in programs. Nondecimal modes are not valid for some functions.

In **Dec** (decimal) number base, numbers are interpreted and displayed as decimal (base 10).

In **Bin** (binary) number base, numbers are interpreted as binary (base 2). Results display with the **b** suffix.

In **Oct** (octal) number base, numbers are interpreted as octal (base 8). Results display with the **o** suffix.

In **Hex** (hexadecimal) number base, numbers are interpreted as hexadecimal (base 16). Results display with the **h** suffix.

**Vector Coordinate
Display Format**

Vector coordinate format affects only how a 2-element or 3-element vector result is displayed. You can enter a vector in any format. Both cylindrical and spherical vector formats display 2-element vectors in polar format.

RectV (rectangular vector) coordinate format displays results in the format $[x\ y]$ for 2-element or $[x\ y\ z]$ for 3-element vectors.

CylV (cylindrical vector) coordinate format displays results in the format $[r\angle\theta]$ for 2-element or $[r\angle\theta\ z]$ for 3-element vectors.

SphereV (spherical vector) coordinate format displays results in the format $[r\angle\theta]$ for 2-element or $[r\angle\theta\angle\phi]$ for 3-element vectors.

For example, if the MODE is **CylV** and **Radian**, $(1,2,3)$ returns $[2.2360679775\angle 69.110714871779\ 3]$

Differentiation Type	<p>Differentiation is used in the instruction <code>TanLn</code>, function <code>arc</code>, and interactive graphing activities <code>dy/dx</code>, <code>dr/db</code>, <code>dy/dt</code>, <code>dx/dt</code>, <code>ARC</code>, <code>TANLN</code>, and <code>INFLC</code>. You can select the type of differentiation to use.</p> <p><code>dxDer1</code> (exact differentiation) uses <code>der1</code> (Chapter 3) to differentiate exactly and calculate the value for each function in an expression. It is more accurate than <code>dxNDer</code>, but more restrictive, in that only certain functions are valid in the expression.</p> <p><code>dxNDer</code> (numeric differentiation) uses <code>nDer</code> to differentiate numerically and calculate the value for an expression. It is less accurate than <code>dxDer1</code>, but less restrictive in the functions that are valid in the expression. The variable <code>δ</code> applies (Chapter 3).</p>
Setting Modes from ■ Command Line	<p>To set a MODE on the Home screen or in a program, enter the name of the MODE as an instruction. For example, <code>Func</code> or <code>Float</code>. The form for fixed decimal setting is <code>Fix n</code>. You can select the name in the program editor from an interactive selection screen (Chapter 16).</p>

Error Conditions

The TI-85 detects any errors at the time it evaluates an expression, executes an instruction, plots a graph, or stores a value. Calculations stop and an error message with a menu displays immediately. Error codes and conditions are described in detail in Appendix B.

Diagnosing an Error

If the TI-85 detects an error, it displays the ERROR screen. An example is shown below.



The error message on the top line indicates a two-digit error number and the type of error. The menu keys are labelled with appropriate actions.

- If you select (GOTO), the cursor is at the location where the error was detected.

Note: If the error was detected in the contents of an equation variable, this option creates the appropriate assignment statement on the Home screen (page 23). Enter the correction and press ENTER. Edits created from program commands must be corrected in the program.

- If you select (QUIT) or press (2nd) (QUIT), (EXIT), or (CLEAR), you return to the Home screen.

Correcting an Error

1. Note the number and type of the error.
2. Select (GOTO), if that option is available, and look at the expression, especially at the location of the cursor, for syntax errors.
3. If the error in the expression is not readily apparent, turn to Appendix B and read the information about the error message.
4. Correct the expression.

Chapter 2: Entering and Using Data

This chapter describes the types of data used by the TI-85 and how to enter and use them. More detailed descriptions of the data types and particular operations relating to them are in the appropriate chapters.

Chapter Contents	Data Types	2-2
	Entering and Using Numbers	2-3
	Variables	2-4
	Storing Values to Variables	2-5
	Using Variable Values	2-6
	The VARS (Variables) Menu	2-7
	Accessing Variable Names	2-8
	Equation Variables	2-9
	Recalling Variable Contents	2-10
	Variable Examples	2-11
	Constants, Programs, Graphs, and Pictures	2-12

Data Types

On the TI-85, you can enter and use several types of data, including real and complex numbers, matrices, vectors, and lists; strings; equations; constants; graph databases; pictures; and programs. User-assigned variable names reference them in memory.

Data Types	Data Type	Entry/Display Format
	Numbers	7.135E1
	Real or complex	71.35
		(-2,0)
		(-2,0)
	Matrices	$\begin{bmatrix} 1 & 2 & 3 & 4 \end{bmatrix}$
	Real or complex	$\begin{bmatrix} 1 & 2 \\ 3 & 4 \end{bmatrix}$
	Vectors	$\{1,2,3\}$
	Real or complex	$\{1\ 2\ 3\}$
	Lists	$\{1,2,3,4\}$
	Real or complex	$\{1\ 2\ 3\ 4\}$
	Strings	'HELLO'
	Characters	HELLO
	Equations	AREA= π *RADIUS ²
	Expressions	Done
	Constants	Ng
	Real or complex	6.022136736E23

Notes about Data Types

Any of these data types can be stored to and recalled from memory with a user-assigned variable name.

The MODE settings may control the entry and/or display format of a particular type of data (pages 1-24 to 1-27).

You can enter numbers, matrices, vectors, lists, and strings in an expression directly, or you can enter the name of a variable or constant to refer to values in memory.

You also can use editors to define or edit matrices, vectors, lists, equations, and constants.

Other Named Items

Programs are defined and edited using an editor (Chapter 16). Graph databases and pictures are stored and recalled using specific instructions (Chapter 4).

Entering and Using Numbers

Numbers on the TI-85 can be real or complex. You can enter a number in normal or scientific notation or in decimal, binary, octal, or hexadecimal base (Chapter 10). The MODE settings may control the entry and/or display format.

Real Numbers

Real numbers are displayed using the notation format, decimal setting, and number base setting specified by the MODE settings. You can enter a real number in any of these formats, with up to 14 digits and a three-digit decimal exponent.

Entering a Number in Scientific or

Use the \boxed{EE} key to enter the exponent (power of 10) in scientific or engineering notation.

Engineering Notation

1. If the number is negative, press $\boxed{(-)}$, and then type the portion of the number that precedes the exponent.
2. Press \boxed{EE} . E in the expression indicates the exponent.
3. If the exponent is negative, press $\boxed{(-)}$, and then type the exponent, which can be up to three decimal digits.

For example, $(1.2) \div (-3.1)$ returns $(-.2,3)$ and $(1.2)^3$ returns $(1.24844050964,2.72789228048)$ in Radian MODE.

Variables

Values can be stored to and recalled from memory with variable names. A variable is a name that refers to a location in memory where the value is stored. In an expression, the variable name represents the value.

Variable Names

A variable can represent a number, a matrix, a vector, a list, a string, an equation, a program, a graph database, or a picture.

Variable names in the TI-85 can be up to eight characters long. They must begin with a letter (including Greek and international letters, and special characters Ç, ç, Ñ, and Ñ). You can use letters, numbers, hex numbers, Greek letters, international characters, and special characters Ç, ç, Ñ, and Ñ in variable names. The symbols ² and ' are used in the names of system variables, such as Σx^2 and $Q'1$.

The following are not valid as variable names:

- Names of constants
- Names of functions
- Names of instructions

Note: All variable and data type names are case-sensitive; the names **AREA** and **area** refer to different variables. The names of functions and instructions are not case-sensitive; the function names **SIN** and **sin** both refer to the same function and are not valid as variable names.

System Variables

In addition to user-assigned variable names, there are some system variables that are used by the TI-85. Most of these variables are related to specific applications and are described in the appropriate chapters. These names are case-sensitive; the variable names **xMin** and **XMIN** refer to different variables.

You can use system variables in expressions. You can store to some, but not all of them. Restrictions on the use of system variables are described in Appendix A.

Storing Values to Variables

Values and strings are stored to variables using the **STO>** key. You can enter the value as an expression, it is evaluated when you press **ENTER**, and the result is stored in the variable. For information about storing unevaluated expressions in variables, see page 2-8.

Storing a Value to a Variable with STO>

1. On a blank line on the Home screen or in the program editor, enter the value to store. This value can be a real or complex number, matrix, vector, list, or string, or an expression that evaluates to one of these types.

2. Press the **STO>** key. The instruction \rightarrow is copied to the cursor location.

3. Enter the name of the variable to which to store the value.

Note: After you press **STO>**, the TI-86 keyboard is set in ALPHA-lock (uppercase alphabetical entry). To enter digits in the name, press **ALPHA** to cancel ALPHA-lock. To enter lowercase letters, press **2nd** [alpha].

4. Press **ENTER** to complete the instruction. If you entered an expression, it is evaluated before the value is stored to the variable.

Example

Add 10 to 25 and store the result in the variable **TEMP**. Then divide 75 by the result (**TEMP**).

Procedure	Keystrokes	Display
Enter expression	10 + 25	10+25
Store value in TEMP	STO> TEMP	10+25 \rightarrow TEMP 35
Begin expression	75 ÷	75/
Set ALPHA-lock	ALPHA ALPHA	75/
Divide by TEMP	TEMP	75/TEMP
Evaluate expression	ENTER	75/TEMP 2.14285714286

Using Variable Values

Once you have stored a value to a variable, you can use the variable name to recall the value. Simply enter the name of the variable in an expression.

Using a Variable in an Expression

Generally, you can use a variable as any element in an expression where its data type is valid. When the expression is evaluated, the current value of that variable is used. There are three ways to enter the name of a variable in an expression:

- Type the characters of the name. Variable names are case-sensitive.
- Use a VARS selection screen to copy the variable name to the cursor location (pages 2-7 and 2-8).
- Use the LIST NAME, MATRX NAME, VECTR NAME, CONS USER, or CONS BLTIN menu to copy the name of a matrix, vector, or constant to the cursor location.

Note: If not all characters in a name can display in the menu item, the name is truncated in the menu, but the entire name is copied to the cursor location.

Displaying the Value of a Variable

You can display variable contents in three ways.

- Enter the variable name on a blank line on the Home screen. Press **ENTER**. The value is displayed in the current display format.
- Use the RCL (recall) feature (page 2-10) to display the unevaluated contents of the variable on a blank line on the Home screen. If the contents are an expression or equation, you can press **ENTER** to evaluate the expression.
- View the contents in an editor (for lists, see Chapter 12; for matrices and vectors, see Chapter 13).

Copying a Variable

To copy the contents of any variable to another variable, use the **F5** key. For example, **VAR1**→**VAR2** copies **VAR1** to **VAR2**.

Deleting a Variable

Variables are deleted from memory through the memory management menu (Chapter 18).

The VARS (Variables) Menu

[VAR] (VARS) accesses the names of variables for use in expressions. Variables are classified by the contents stored to the variable name. Press **[VAR]** to move around the menu.

The VARS Menu

When you press **[VAR]** (VARS), the menu keys are labelled with the first five items of the variables menu.

ALL	REAL	CPLX	LIST	VECTR
MATRX	STRNG	EQU	CONS	
GDB	PIC	STAT	RANGE	

When you select an item from the **VARS** menu, the **VARIABLES** selection screen is displayed.


Item	Accesses
ALL	Names of all variables and named items.
REAL	Names of real number variables.
CPLX	Names of complex number variables.
LIST	Names of list variables.
VECTR	Names of vector variables.
MATRX	Names of matrix variables.
STRNG	Names of string variables.
EQU	Names of equation variables, including current y_n , m , x_n , y_n , and Q_n equations.
CONS	Names of user-defined constants.
PRGM	Names of programs.
GDB	Names of graph databases.
PIC	Names of picture images.
STAT	Names of statistics variables.
RANGE	Names of RANGE variables.

Accessing Variable Names

You can copy the name of a variable from the VARIABLES selection screen to the cursor location in an expression.

Copying a Variable Name to an Expression

1. Press **[2nd]** [VARS] to display the VARS menu. The VARIABLES screen temporarily replaces the screen on which you are working.
2. Select the data type. (ALL displays variable names of all data types.)



3. The names are displayed in alphabetical order (uppercase, then lowercase, then special characters). An arrow at the left indicates the selection cursor. The data type is shown at the right. (Constants and some system variables with no current value do not show a type.) To move around the list:
 - Press a letter to move quickly to names beginning with that letter. (The keyboard is set in ALPHA-lock; press **[2nd]** [alpha] to change to alpha-lock.)
 - Use **(PAGE)←** and **(PAGE)→** to move to the next page of names.
 - Use **(V)↓** and **(A)↑** to move down and up the list.
4. Press **[ENTER]** to select the name the cursor is on. The VARIABLES selection screen disappears and the name is copied to the cursor location.

Leaving the VARIABLES Screen

To leave this screen without making a selection:

- Press **[2nd]** or **[CLEAR]** to return to the application in which you are working.
- Press **[2nd]** [QUIT] to display the Home Screen.

Equation Variables

You can store an unevaluated expression or a series of characters from the Home screen or a program to the equation data type. You can recall the unevaluated expression or characters to the cursor location at a later time.

Equations

An equation is a variable data type that contains an unevaluated expression or series of characters. In addition to user-defined equation variables, several editors store to equation variables; for example, the graphing equations ($y1$, $y2$, $r1$, etc.), the SOLVER eqn , and the STAT $RegEq$. The expression in an equation variable can include an equal sign; therefore, it can be a mathematical equation. For example, an equation data type may contain $A+B$, $A=B+C$, or $CIDw$.

If an equation variable contains an instruction—for example, $CIDw$ —you can recall the contents to the cursor location and then execute the instruction, but you cannot enter the name of the equation variable on a line by itself as a command to execute.

Storing an Expression to an Equation Variable

The assignment instruction, entered with the $\boxed{A\rightarrow B}$ key, stores an unevaluated expression to an equation variable. (The store instruction, entered with the $\boxed{STO\rightarrow}$ key, evaluates the expression when the instruction is executed and stores the value.)

The form for a completed assignment instruction is:
 $variable=expression$

When the assignment instruction is executed, the expression is not evaluated. The TI-85 stores the unevaluated expression to the variable.

For example, $EQ1=A+B-7$ stores the expression $A+B-7$ in the variable $EQ1$ and $EQ2=A+B+C$ stores $A+B+C$ in the variable $EQ2$.

Errors

Expressions stored using an assignment instruction are not evaluated. Therefore, any errors in the expression are not detected when the assignment is performed.

When an error, such as a syntax error, is encountered within an equation or equation variable and you select (GOTO), the Home screen is displayed with the appropriate assignment instruction for you to edit.

Recalling Variable Contents

The RCL (recall) feature copies the contents of a variable to the cursor location. It is useful for equation variables that have had expressions stored to them with assignment instructions and to display the **RECALL** of variables before evaluation.

Recalling the Contents of a Variable

1. Press **(2nd)** (RCL). The cursor is positioned after Rcl on the prompt line and the keyboard is set in ALPHA-lock.
2. Enter the name of the variable by typing it or by selecting it from a menu (but not the VARS selection screen).
3. Press **(ENTER)**. The contents of the variable are inserted at the cursor location, whether the calculator is in insert mode or not.
 - If the contents were stored with the **(RPN)** **(=)** key, the contents are recalled exactly as stored.
 - If the contents were stored with **(STO)**, the contents are a value. The elements of the value are recalled **according** to the current modes, but in an entry format. For example, the keystrokes **(2nd)** **(=)** **(STO)** **A** **(RCL)** **A** **(ENTER)** recalls the characters 3.14 if the MODE is Fix 2.

After you use RCL to copy the contents of a variable to the cursor location, you can edit the characters in the display.

You cannot recall a program, graph database, or picture onto the Home screen.

Clearing Recall

If there are characters in the prompt following Rcl, **(CLR)** clears (blanks out) the prompt entry.

If the prompt entry is blank, **(CLR)** cancels RCL and returns the cursor to the Home screen or the editor.

Recalling a Program

You can recall the contents of another program to the cursor location in the program editor. This copies (inserts) all of the commands, which you then can edit (Chapter 16). You cannot recall a program onto the Home screen.


Variable Examples

The following examples show the relationship between how information is stored to a variable, how it is retrieved, and the result. These examples use Fix 2 display MODE.

Procedure	Keystrokes	Result	
Store instruction	20 ÷ 3 [F2] A [ENTER]	20 ÷ 3 → A in memory, A contains 23	23.00
Assignment instruction	A ← B [F2] 7 [ENTER]	B = 7 in memory, B contains 7	Done
Assignment instruction	A ← C [F2] 4 [ENTER]	C = 4 + A in memory, C contains 4 + A	Done
Use value of contents of A (23)	3 ÷ [F2] A [ENTER]	3/A	.13
Recall contents of A (23) into expression according to MODE settings	3 ÷ [F2] [RCL] A [ENTER]	3/A	13
Use value of contents of B (7)	3 ÷ [F2] B [ENTER]	3/B	.43
Recall contents of B (7) into expression	3 ÷ [F2] [RCL] B [ENTER]	3/7	.43
Use value of contents of C (4+23)	3 ÷ [F2] [ALPHA] C [ENTER]	3/C	.11
Recall contents of C (4+23) into expression	3 ÷ [F2] [RCL] C [ENTER]	3/4+A	23.75

Constants, Programs, Graphs, Pictures

You can store named items (constants, programs, graph databases, and pictures) and recall them from memory by name.

Constants	<p>The TI-85 has several built-in constants. In addition, you can create user-defined constants (Chapter 8).</p> <p>You create and edit user-defined constants only through the CONSTANT editor. Constant names are case-sensitive; CONST1 and const1 refer to different constants. They can be used in expressions.</p>
Programs	<p>A program is a series of commands that can be executed. Programs are described in Chapter 16.</p> <p>You store and recall programs by name in the program editor. Program names are not valid in expressions. The names are case-sensitive; PROG1 and prog1 refer to different programs.</p>
Graph Databases	<p>A graph database is all of the elements that define a particular graph. The graph can be recreated from these elements (Chapter 4).</p> <p>You can store and recall a graph database by name. Graph database names are not valid in expressions. The names are case-sensitive; GRAPH1 and graph1 refer to different graphs.</p>
Pictures	<p>A picture is  an image of the current graph display at a particular time (Chapter 4).</p> <p>You can store and recall a picture by name. Picture names are not valid in expressions. The names are case-sensitive; PIC1 and pic1 refer to different pictures.</p>
Storing to Named Items	<p>You cannot store to a variable name if that name is currently used for a named item, such as a constant, program, graph database, or picture. This prevents one of these data types from being overwritten. Before you can use the name as a variable, you must delete the named item through the memory management menu (Chapter 18).</p>

Chapter 3: Math, Calculus, and Test Operations

This chapter describes the math, calculus, and relational functions and instructions that are available on the TI-85 from the keyboard, MATH menu, CALC menu, and TEST menu.

Chapter Contents	Keyboard Math Functions	3-3
	The MATH Menu	3-3
	The NUM (Number) Menu	3-4
	The PROB (Probability) Menu	3-6
	The ANGLE Menu	3-7
	The HYP (Hyperbolic) Menu	3-8
	The MISC (Miscellaneous) Menu	3-9
	The INTER (Interpolation) Feature	3-11
	The CALC (Calculus) Menu	3-12
	The TOLER (Tolerance) Settings	3-17
	The TEST (Relational) Menu	3-18

Keyboard Math Functions

The most commonly used math functions are on the keyboard. The placement of the arguments of each function is described in Appendix A. These examples assume that the default MODE settings are in effect.

Functions	Example	Keystrokes	Display
$+$, $-$, \times , \div	$75 \div 12 \times 2$	75 \div 12 \times 2 ENTER	$75 \div 12 \times 2$ 51
Powers	$6^2 + 2^5$	6 x^y 2 $+$ 2 x^y 5 ENTER	$6^2 + 2^5$ 86
\sqrt{x}	$\sqrt{16}$	$\sqrt{\square}$ 16 ENTER	$\sqrt{16}$ 4
x^{-1}	$1/4$	4 1/x ENTER	4^{-1} 25
Negation	$-2 + 5$	+/- 2 $+$ 5 ENTER	$-2 + 5$ 3
\sin , \cos , \tan , \sin^{-1} , \cos^{-1} , \tan^{-1}	$\sin \pi$	\sin π (pi) ENTER	$\sin \pi$ 0
\log , \ln	$\ln 1$	\ln 1 ENTER	$\ln 1$ 0
10^x , e^x	e^0	2nd (e) 0 ENTER	e^0 1

Notes about Keyboard Math Functions

Arguments may be real or complex values. These functions are valid also for lists. They return a list of results calculated on an element-by-element basis. If two lists are used in the same expression, they must be the same length.

\sin^{-1} , \cos^{-1} , and \tan^{-1} are the inverse trig functions, arcsin, arccos, and arctan.

x^{-1} , the multiplicative inverse, is the equivalent of the reciprocal, $1/x$.

PI π is stored as a constant in the TI-85. Press 2nd (pi) and the symbol π is copied to the cursor location; the number 3.1415926535898 is used internally in calculations.

The MATH Menu

The MATH menu accesses additional mathematical functions and features that are not on the keyboard. Press 2ND to move around the menu.

The MATH Menu

When you press 2ND [MATH], the menu keys are labelled with the MATH menu.


	PROB	ANGLE	HYP	MISC
NUM	Menu of number functions (page 3-4).			
INTER	Interpolation editor (page 3-11).			
NUM	round sign	IPart ^{1/2} min	IPart ^{1/2} max	int abs
PROB	Menu of probability functions (page 3-6).			
ANGLE	Menu of angle functions (page 3-7).			
HYP	Menu of hyperbolic functions (page 3-8).			
MISC	Menu of miscellaneous mathematical functions and instructions (page 3-9).			
INTER	Interpolation editor (page 3-11).			

The NUM (Number) Menu

The MATH NUM menu displays number functions. When you select an item from the menu, the name is copied to the cursor location. Press **→** to move around the menu. These examples assume that the default MODE settings are in effect.

The MATH NUM Menu

When you select (NUM) from the MATH menu, the menu keys are labelled with the first five items of the number menu.

round sign	iPart min	iPart max	Int mod	
---------------	--------------	--------------	------------	---

The functions that are valid for lists return a list of results calculated on an element-by-element basis.

The round Function

round returns a number or numbers rounded to a specified number of decimal places or digits. The first argument is the real or complex number, list, matrix, or vector to round. The second argument (optional) is the number of decimal places (0 to 11) to round to. If there is no second argument, the number is rounded to twelve digits. The parentheses are required.

round(value, #decimals) or **round(value)**

The iPart Function

iPart (integer part) returns the integer part or parts of a real or complex number, or of each element of a list, matrix, or vector.

For example, **iPart -23.45** returns **-23**.

The fPart Function

fPart (fractional part) returns the fractional part or parts of a real or complex number, or of each element of a list, matrix, or vector.

For example, **fPart -23.45** returns **-.45**.

The Int Function

Int (greatest integer) returns the largest integer less than or equal to a real number, each element of a complex number, or each element of a list, matrix, or vector. The result is the same as **iPart** for nonnegative numbers and negative integers, but one integer less than **iPart** for negative noninteger numbers.

For example, **Int -23.45** returns **-24**.

The NUM (Number) Menu (Continued)

The abs Function	abs (absolute value) returns the absolute value of a real number or the magnitude (modulus), $\sqrt{(\text{real})^2 + (\text{imag})^2}$, of a complex number or of each element of a list, matrix, or vector. For example, abs -23.45 returns 23.45 .
The sign Function	sign returns 1 for a positive real number, 0 for 0, or -1 for a negative real number or for each element of a real list. For example, sign -23.45 returns -1 .
The min Function	min (minimum value) returns the smaller of two real or complex numbers or the smallest element in a real or complex list. If two lists are compared, the result is a list of the smaller of each pair of elements. If the argument is complex, the comparison is based on magnitude (modulus). The parentheses are required. min(list), min(value, value), or min(list, list) For example, min(3,-5) returns -5 , min({1,3,-5}) returns -5 , and min({1,2,3},{3,2,1}) returns {1 2 1} .
The max Function	max (maximum value) returns the largest element in a real or complex list or the larger of two real or complex numbers. If two lists are compared, the result is a list of the larger of each pair of elements. If the argument is complex, the comparison is based on magnitude (modulus). The parentheses are required. max(list), max(value, value), or max(list, list)
The mod Function	mod (modulus) returns the modulo value of the first (real) argument with respect to the second (real) argument (the modulus). mod(value, modulus) For example, mod(23.45,10) returns 3.45 .

The (Probability) Menu

The MATH PROB menu displays probability functions. When you select an item from the menu, the name is copied to the cursor location. These examples assume that the default MODE settings are in effect.

The MATH PROB Menu

When you select (PROB) from the MATH menu, the menu keys are labelled with the probability menu.

nPr **nCr** **rand**

The Factorial Function

! (factorial) returns the factorial of a positive integer between 0 and 449.

For example, **6!** returns 720.

The nPr Function

nPr (number of permutations) returns the number of permutations of *n* items taken *r* at a time. The arguments must be nonnegative integers.

Items **nPr** number

For example, **5 nPr 2** returns 20.

The nCr Function

nCr (number of combinations) returns the number of combinations of *n* items taken *r* at a time. The arguments must be nonnegative integers.

Items **nCr** number

For example, **5 nCr 2** returns 10.

The rand Function

rand (random number) generates and returns a random number greater than 0 and less than 1. To control a random number sequence, first store an integer seed value in **rand**; for example, **0→rand**. If you store **■** to **rand**, the TI-85 uses the factory-set seed value. When you reset the TI-85, **rand** is set to the factory seed.

For example, **0→rand:rand*3** always returns 2.83079220748.

The ANGLE Menu

The **MATH ANGLE** menu displays angle indicators and instructions. When you select an item from the menu, the name is copied to the cursor location.

The MATH ANGLE Menu	When you select ANGLE from the MATH menu, the menu keys are labelled with the angle menu. <div>• DMS</div>
The ' Function	' (degree) lets you designate the real number argument as degree, regardless of the current angle MODE setting. The argument may be a real list. angle '
The ° Function	° (radian) lets you designate the real number argument as radian, regardless of the current angle MODE setting. The argument may be a real list. angle °
The ' Notation	The ' (minute) entry notation is used to enter numbers in DMS format. Degrees ($\leq 999,999$), minutes (< 60), and seconds (< 60 , may have decimal places) must be entered as numbers, not as variable names or expressions. degrees 'minutes' seconds ' For example, enter 54'32'30' for 54 degrees, 32 minutes, 30 seconds. The MODE setting must be Degree for the TI-85 to interpret this entry as degrees, minutes, and seconds (in Radian MODE , enter 54'32'30"').
The ►DMS Instruction	►DMS (display as degree/minute/second) displays the (real) result in degree, minute, second format. The MODE setting must be Degree for the TI-85 to interpret the result as degrees, minutes, and seconds. It is valid only at the end of a command. result ►DMS

The HYP (Hyperbolic) Menu

The MATH HYP menu displays hyperbolic functions. When you select an item from the menu, the name is copied to the cursor location. Press **2ND** to move around the menu.

The MATH HYP Menu When you select HYP from the MATH menu, the menu keys are labelled with the first five items of the hyperbolic menu.

sinh **cosh** **tanh** **sinh⁻¹** **cosh⁻¹**
tanh⁻¹

The sinh, cosh, and tanh Functions **sinh**, **cosh**, and **tanh** are the hyperbolic functions. The arguments may be real or complex numbers.

sinh value

These functions are valid for lists. They return a list of results calculated on an element-by-element basis.

The sinh⁻¹, cosh⁻¹, and tanh⁻¹ Functions **sinh⁻¹**, **cosh⁻¹**, and **tanh⁻¹** are the hyperbolic arcsin, hyperbolic arccos, and hyperbolic arctan, respectively. The arguments may be real or complex numbers.

sinh⁻¹ value

These functions are valid for lists, returning a list of results calculated on an element-by-element basis.

The MISC (Miscellaneous) Menu

The MATH MISC menu displays miscellaneous mathematical functions. When you select an item from the menu, the name is copied to the cursor location. Press **ESC** to move around the menu. These examples assume that the default MODE settings are in effect.

The MATH MISC Menu

When you select (MISC) from the MATH menu, the menu keys are labelled with the first five items of the mathematical menu.

sum prod seq lcm gcd
 >Frac % pEval ' eval

The sum Function

sum (summation) returns the sum of the elements of a real or complex list.

sum list

For example, **sum {1,2,4,8}** returns 15.

The prod Function

prod (product) returns the product of the elements of a real or complex list.

prod list

For example, **prod {1,2,4,8}** returns 64.

The seq Function

seq (sequence) returns a real list, in which each element is the value of the expression, evaluated at increments for the specified variable from the beginning value to the ending value. The increment can be negative. **seq** is not valid in the expression.

seq(expression, variable_name, begin, end, increment)

For example, **seq(N², N, 1, 11, 3)** returns {1 16 49 100}.

Sums and Products of Numeric Sequences

You can combine **sum** or **prod** with **seq** to obtain:

$$\sum_{x=\text{lower}}^{\text{upper}} \text{expression}(x) \qquad \prod_{x=\text{lower}}^{\text{upper}} \text{expression}(x)$$

For example, to evaluate $\sum 2^{j-1}$ from $j=1$ to 4, enter **sum seq(2*(j-1), j, 1, 4, 1)**, which returns 15.

The lcm Function

lcm (least common multiple) returns the least common multiple of two nonnegative integers.

lcm(value, value)

The MISC (Miscellaneous) Menu (Continued)

The gcd Function	<p>gcd (greatest common divisor) returns the greatest common divisor of two nonnegative integers.</p> <p>gcd(value ,value)</p>
The ►Frac Instruction	<p>►Frac (display as fraction) displays a result as the rational equivalent. The argument can be a real or complex number, list, matrix, or vector. If it cannot be simplified, the decimal equivalent is returned. ►Frac is valid only at the end of a command.</p> <p>result ►Frac</p> <p>For example, $1/3+2/7$ ►Frac returns $13/21$</p>
The % Function	<p>% (percent) returns the percent (divides the argument by 100) of a real number.</p> <p>value %</p> <p>For example, $5\%*200$ returns 10.</p>
The pEval Function	<p>pEval (polynomial evaluation) returns the value of a polynomial for a given x. The first argument is a real or complex list of the coefficients. The second argument is the real or complex value of x.</p> <p>pEval(list ,value)</p> <p>For example, pEval({2,2,3},5) returns 63, the value of $2x^2+2x+3$ at $x=5$.</p>
The $\sqrt[n]{}$ Function	<p>$\sqrt[n]{}$ (root) returns the real or complex root of a real or complex number.</p> <p>nth_rootⁿ√value</p> <p>For example, $5\sqrt[5]{32}$ returns 2, the fifth root of 32.</p>
The eval Function	<p>eval (evaluation) returns a list of the values of any selected functions in the current graphing MODE for the specified real value of the independent variable. eval is not valid in a graphing function.</p> <p>eval value</p>

The INTER (Interpolation) Feature

The TI-85 can interpolate or extrapolate a value linearly, given two known pairs and the x or y value of the unknown. Selecting **INTER** from the **MATH** menu displays a full-screen editor for entering values and displaying interpolated results.

The MATH INTER Editor

Select **INTER** from the **MATH** menu to display the **INTERPOLATE** editor.



Interpolating a Value

1. Enter real values (which can be expressions) for **(x1,y1)**, the first known pair.
2. Enter values for **(x2,y2)**, the second known pair.
3. Enter a value for either the x or the y value of the unknown.
4. Move the cursor to the value for which you want to solve (x or y) and select **SOLVE**.

The result is interpolated or extrapolated and displayed; the variables x and y are not changed. A square dot in the first column indicates the interpolated value. You can store individual values with the **STO** key.

For example, press **2** **5** **→** to enter (3,5), then press **4** **4** **→** to enter (4,4). To extrapolate the y value at x=1, press **1** **→** and select **SOLVE**. The result is **y=7**.

Further Solutions

After solving for a value, you can continue to enter values and interpolate from this display.

Using the Interpolation Function from a Command Line

You can use the interpolate feature from the Home screen or from a program to find a y value:

Inter(x1 ,y1 ,x2 ,y2 ,x)

To interpolate for x, enter **Inter(y1 ,x1 ,y2 ,x2 ,y)**

The CALC (Calculus) Menu

The CALC menu displays calculus functions. Press **2nd** **[CALC]** to move around the menu. When you select an item from the menu, the name is copied to the cursor location.

The CALC Menu

When you press **2nd** **[CALC]**, the menu keys are labelled with the calculus menu.

evalF	nDer	der1	der2	mint
fMin	fMax	int1		

The calculus functions return values with respect to any non-system variable, to system variables **eqn** and **exp**, and to graphing variables such as **x**, **t**, and **θ**.

The result is calculated using the current values of all variables. **MODE** must be **Dec**.

The calculus functions are valid in graphing equations.

The evalF Function

evalF (evaluate a function) returns the value of an expression with respect to the named variable.

evalF requires three arguments: an expression, the name of a variable, and a value to use for evaluation.

evalF(expression, variable_name, value)

For example, **evalF(A^3,A,5)** returns 125.

evalF is not valid in the expression agreement.

The nDer Function

nDer (numerical derivative) returns an approximate numerical derivative of an expression with respect to the named variable.

nDer requires two arguments: an expression and a variable name. An optional third argument gives a value to use for the variable; otherwise the current value is used. The variable value can be a real number, a complex number, or a real or complex list.

nDer(expression, variable_name, value)

The numerical derivative value is the slope of the secant line through the points (value- δ , f(value- δ)) and (value+ δ , f(value+ δ)). This is an approximation of the numerical derivative. As δ gets smaller, the approximation usually gets more accurate.

For example, **nDer**(A³,A,5) returns 75.0001 if $\delta=.01$, but returns 75 if $\delta=.0001$.

der1 and **der2** (page 3-14) can be used in the expression argument. **nDer** can be used once in the expression argument. A good approximation for the fourth derivative at the current value of x can be obtained by **nDer**(**nDer**(**der2**(x⁴,x),x),x). The accuracy is controlled by the variable δ (page 3-17, for step size). Because of the method, **nDer** can return a derivative value at a nondifferentiable point.

The `der1` and `der2` Functions

The TI-85 uses the rules of differentiation to calculate the first and second derivatives exactly to 14 digits.

`der1` (first derivative) returns the value of f' , `der2` (second derivative) returns the value of f'' with respect to the specified variable.

`der1` and `der2` require two arguments: an expression and a variable name. An optional third argument gives a value to use for the variable; otherwise the current value is used. The variable value can be a real number, a complex number, or a real or complex list.

`der1(expression, variable_name, value)`

For example, `der1(AB^3,AB,5)` returns 75 and `der2(AB^3,AB,5)` returns 30.

`der1` and `der2` are valid for the single-argument functions: `sin`, `cos`, `tan`, `sin-1`, `cos-1`, `tan-1`, the hyperbolic functions, `log`, `ln`, `10^x`, `e^x`, x^y , `sqrt`, `abs`, and negation. The two-argument functions `+`, `-`, `*`, `/`, and `^` are valid in the expression argument, but other multi-argument functions requiring parentheses are not. `evalF`, `der1`, `der2`, `fMin`, `fMax`, `arc`, `nDer`, and `seq` are not valid in the expression argument. Matrices, vectors, and strings are not valid in the expression argument.

The fnInt Function

fnInt (function integral) returns the numerical integral.

fnInt requires four arguments: an expression, the name of the variable with respect to which to calculate the integral, and the lower and upper limits.

fnInt(expression, variable_name, lower, upper)

For example, **fnInt**(A^2 , A , 0, 1) returns .333333333333.

fnInt and **arc** are not valid in the expression argument. The accuracy is controlled by the variable **tol** (page 3-17). A value is stored to **fnIntErr** that is indicative of possible solution error.

Example

Use **nDer** and **fnInt** to demonstrate that:

$$D_x \left[\int_0^x f(A) \, dA \right] = f(A)$$

1. On the Home screen, enter and evaluate the expression $f(A)=A^2$ at $A=3$: $3 \rightarrow A:A^2$, which returns 9.
2. Press **(2nd)** **(CALC)** to display the CALC menu and then enter and evaluate:
 $nDer(fnInt(A^2, A, 0, x), x, 3)$, which returns 9.00003333332 at $\delta=.01$. You can change **5** to increase the accuracy of the solution.

The CALC (Calculus) Menu (Continued)

The fMin and fMax Functions

fMin (function minimum) and **fMax** (function maximum) return the value at which the minimum or maximum value of an expression occurs, between specified lower and upper endpoints.

fMin and **fMax** require four arguments: an expression, the name of the variable with respect to which to calculate the minimum or maximum, and the lower and upper endpoints.

fMin(expression, variable_name, lower, upper)

For example, **fMin**(sin A,A,- π , π) returns -the π value where the minimum occurs.

lower must be less than upper . **fMin** and **fMax** are not valid in the expression argument. The accuracy is controlled by the variable **tol** (page 3-17). If there is no finite minimum or maximum in the interval, usually (depending on the expression argument) an error occurs.

The arc Function

arc returns the length along a curve between two points on the **screen**.

arc requires four arguments: an expression to define the curve, the name of the independent variable, and the two values of the variable

arc(expression, variable_name, value1, value2)

For example, **arc**(A²,A,0,1) returns 1.47894285752.

evalF, **arc** and **fnInt** are not valid in the expression argument.


evalF, **der1**, **der2**, **fMin**, **fMax**, **nDer**, and **seq** are not valid in the expression argument in **dxDer1** MODE . The accuracy is controlled by the variable **tol** in **dxNDer** or **dxDer1** MODE and by δ in **dxNDer** MODE (page 3-17).

The TOLER (Tolerance) Settings

The accuracy of the computations of certain functions is controlled by the variables δ and tol . The value may have an effect on calculating and plotting speed. The values of the variables can be viewed and edited on the TOLERANCE screen.

The TOLERANCE SCREEN

When you press $\boxed{\text{2nd}} \boxed{\text{[TOLER]}}$, the TOLERANCE editor is displayed. The values shown are the default settings.



Editing a Value

1. Enter a positive real value (which can be an expression), but not zero:
 - Type the new value. The original value is cleared automatically when you begin typing.
 - Use $\boxed{\text{right arrow}}$ or $\boxed{\text{left arrow}}$ to position the cursor and then make the changes.
2. Press $\boxed{\text{ENTER}}$, $\boxed{\text{V}}$, or $\boxed{\text{A}}$. If you entered an expression, it is evaluated. The new value is stored.

The δ Variable

The variable δ defines the step size in calculating the functions arc (in dxNder MODE) and nDer , and in the GRAPH MATH operations dy/dx , d1/dt , dy/dt , dx/dt , INFLC , TANLN , and ARC in dxNder MODE (Chapter 4). δ must be a positive value.

The tol Variable

The variable tol defines the tolerances in calculating the functions fInt , fMin , fMax , and arc , and the GRAPH MATH operations $\text{f}(x)$, fMin , fMax , and ARC (Chapter 4). tol must be a positive value.

Setting δ or tol from the Home Screen or a Program

You can store a value to δ or tol on the Home screen or in a program using the store instruction. When you press $\boxed{\text{2nd}} \boxed{\text{[TOLER]}}$ in the program editor, the menu keys are labelled δ and tol for convenience.

The TEST (Relational) Menu

The TEST menu displays relational operations that compare two values and return 1 or 0. Press **TEST** to move around the menu. When you select from the menu, the name is copied to the cursor location.

The TEST Menu

When you press **TEST**, the menu keys are labelled with the first five items of the relational menu.

= **<** **>** **≤** **≥**
≠

The **=** (equals relational function) distinguishes it from the **=** (assignment) character on the keyboard.

The Relational Functions

The relational functions are valid for two lists of the same length. They return a list of results calculated on an element-by-element basis.

The = Function

= (equals) returns 1 if the arguments are equal, 0 if not equal. The arguments can be real or complex numbers, matrices, vectors, or lists, or strings.

For example $\{1,2,3\}=\{3,2,1\}$ returns $\{0\ 1\ 0\}$.

The <, >, ≤, and ≥ Functions

< (less than), **>** (greater than), **≤** (less than or equal), and **≥** (greater than or equal) return 1 if the test is true and 0 if the test is false. Both arguments must be real values or lists (which can be expressions).

The ≠ Function

≠ (not equal) returns 1 if the arguments are not equal, 0 if equal. The arguments can be real or complex numbers, matrices, vectors, or lists, or strings.

Using Tests in Expressions and Instructions

Only the Boolean operators are below relational functions in the EOS evaluation hierarchy.

- The expression $2+2=2+3$ evaluates to 0. EOS first performs the addition and then compares 4 to 5.
- The expression $2+(2=2)+3$ evaluates to 6. EOS first performs the test because it is in parentheses and then adds 2, 1, and 3.

Relational functions can be used to control program flow (Chapter 16).

This chapter describes function graphing on the TI-85 in detail. It also lays the foundation for using the other graphing modes of the TI-85.

Chapter Contents	
Defining a Graph	4-2
Graphing Modes	4-3
The GRAPH Menu and Display	4-4
Setting the Graph Format	4-6
Defining Functions in the Y00 List	4-8
Solving Graph Problems	4-11
Defining the Viewing Rectangle	4-12
Displaying a Graph	4-14
Exploring a Graph with the Free-Moving Cursor	4-16
Exploring a Graph with the TRACE Feature	4-17
Exploring a Graph with the ZOOM Features	4-18
Using ZOOM Box	4-19
Zooming from Out	4-20
Setting ZOOM Factors	4-21
Other ZOOM Features	4-22
The User-Defined ZOOM	4-23
The GRAPH MATH Menu	4-24
Setting the Options for MATH Operations	4-25
Using the MATH Operations	4-26
Using EVAL to Analyze a Graph	4-29
The DRAW Menu	4-30
Drawing on a Graph	4-31
Standard Axes on a Graph	4-32
Drawing Lines	4-34
Drawing Vertical Lines and Tangent Lines	4-35
Drawing Circles	4-36
Drawing Functions and Inverses	4-37
Using PEN to Draw on a Graph	4-38
Drawing Pictures	4-39
Storing and Recalling Graph Databases	4-40
Storing and Recalling Graph Pictures	4-41
GRAPH Menu Items in the Program Editor	4-42
GRAPH Menu Chart	4-43
Example: Using Lists in Graphing	4-46

Defining a Graph

To define a graph, select the graphing mode, set the graph format, enter and select functions to be graphed, and define the viewing rectangle. Once a graph is defined, it can be displayed and explored.

Steps in Defining a Graph

There are five basic steps to defining a graph. You may not need to do all of the steps each time you define a graph. The procedures are described in detail on the following pages.

1. Set the **MODE** to **Func** graphing.
2. Set the graph **FORMT**.
3. Enter or edit expressions to define a function or functions in the $y(x)$ list.
4. Select the function or functions in the $y(x)$ list to graph.
5. Set values for the **RANGE** variables to define the viewing rectangle.

Once a graph has been defined, you can display it and use several tools of the TI-85 to explore the behavior of the function or functions. Those tools are described later in this chapter.

Graph Databases

You can store the elements that define the current graph in a graph database that has a user-defined name. At a later time, you can recall that database as the current graph (page 4-10).

Graph Pictures

You can store a picture of the current display in a graph picture that has a user-defined name. At a later time, you can superimpose the picture on the current graph (page 4-11).

Graphing Modes

The TI-85 has four graphing modes: function graphing, polar graphing, parametric graphing, and differential equation graphing.

The Graphing MODE Each of the four graphing modes (function, polar, parametric, and differential equations) is independent of the others. Each MODE has a current graph, defined by its elements:

- The functions
- The graph FORMT
- The RANGE variables

Changes made to a graph element apply to that element in the current graphing MODE only. For example, changes to the RANGE variables in Func graphing do not affect the RANGE variables in Pol graphing.

Note: ZOOM factors, MODE settings, and tolerances are global.

Checking and Changing the Graphing MODE To display or change the current MODE settings, press **2nd** [MODE]. The graphing modes are:

- **Func** (function graphing)
- **Pol** (polar graphing)
- **Param** (parametric graphing)
- **DNEq** (differential equation graphing)

To graph functions, you must be in Func MODE. The number base setting must be Dec. The Radian/Degree and dxDer1/dxNDer settings affect how some $y(x)$ functions are interpreted.


Setting the Graphing MODE from a Program You can set the graphing mode in a program through an interactive selection screen (Chapter 16) or by selecting the name from the CATALOG.

The GRAPH Menu and Display

GRAPH displays the GRAPH menu. It also displays the most recent graph, if no changes affecting the graph have been **STORED**.

The GRAPH Menu

When you press **GRAPH**, the menu keys are labelled with the first five items of the graph menu. Press **EXIT** to move around the menu.

y(x)= MATH EVAL	RANGE DRAW STPIC	ZOOM FORMT RCPIC	TRACE STGDB	GRAPH RCGDB
Item	Accesses			
y(x)=	The y(x) editor (page 4-8).			
RANGE	The RANGE editor (page 4-12).			
ZOOM	Operations  change the viewing rectangle (page 4-18).			
TRACE	Displays graph to trace functions (page 4-17).			
GRAPH	Displays graph with GRAPH menu (page 4-14).			
MATH	Menu of operations to explore a graph mathematically (page 4-24).			
DRAW	Operations to draw on graph (page 4-30).			
FORMT	Graph format selection screen (page 4-8).			
STGDB	Stores current graph database (page 4-40).			
RCGDB	Recalls stored graph database (page 4-40).			
EVAL	Displays graph and accesses an operation to evaluate functions (page 4-29).			
STPIC	Stores current graph picture (page 4-41).			
RCPIC	Recalls stored graph picture (page 4-41).			

Displaying the GRAPH Menu

If you have selected an item, such as **TRACE**, that does not display menus, press **EXIT** to display the **GRAPH** menu.

The "Smart Graph" Feature

The "Smart Graph" feature automatically keeps track of whether any element of a graph has been changed and replots only if you have done one or more of the following:

- Changed a function or the value of a variable that is used in a selected function.
- Selected or unselected a function.
- Changed a MODE setting for graphing MODE, Radian/Degree, or calculus MODE.
- Changed the value of a RANGE variable.
- Changed a graph FORMT setting other than an axis label or coordinate.
- Cleared drawings.

The GRAPH Screen

When you press , "Smart Graph" controls what is displayed on the screen.

- If you have changed one or more of the above, "Smart Graph" does not display a graph. The display is not changed; the menu keys are labelled with the GRAPH menu. You can continue to make changes to the graph elements. "Smart Graph" will plot the new graph when you select (GRAPH), (TRACE), (EVAL), (STGDB), or a ZOOM, DRAW, MATH, or PIC operation.
- If you have not changed any of the above since the graph was displayed previously, "Smart Graph" displays the graph immediately, and the menu keys are labelled with the GRAPH menu.

Setting the Graph Format

The graph format determines how a graph appears on the display. The FORMT settings for function graphing apply only to Func MODE.

Checking FORMT Settings

To display the FORMT selection screen, select <FORMT> from the GRAPH menu. The GRAPH menu remains on the bottom line. The current settings are highlighted. The FORMT settings are described on the following page.

Setting	Meaning
RectGC PolarGC	Type of cursor coordinate display.
CoordOn CoordOff	Whether to display the cursor coordinates.
DrawLine DrawDot	Whether to connect plotted points.
SeqG SimulG	How to plot selected functions.
GridOff GridOn	Whether to display a graph grid.
AxesOn AxesOff	Whether to display the axes.
LabelOff LabelOn	Whether to display the axes labels.

Changing FORMT Settings

To change any of the settings:

1. Move the cursor to the line of the setting you want to change. The setting the cursor is on flashes.
2. Move the cursor to the setting you want. Press **ENTER**.

Leaving the FORMT Selection Screen

- To continue defining the graph, select $y(x)=$ or <RANGE> from the GRAPH menu.
- To display the graph, select <GRAPH>, <TRACE>, <EVAL>, <STGE>, or a ZOOM, DRAW, MATH, or PIC operation.
- To display the Home screen, press **2nd** [QUIT], **END**, or **CLEAR**.


Rectangular or Polar Graphing Coordinate Display	RectGC (rectangular) displays the cursor coordinate in terms of the rectangular coordinates x and y . PolarGC displays the cursor coordinate in terms of the polar coordinates r and θ .
Cursor Coordinate On or Off	CoordOn (coordinate on) displays the cursor coordinate above the menu(s). CoordOff (coordinate off) does not display the cursor coordinate.
DrawLine or DrawDot Graph Display	DrawLine draws a line between the points calculated for the functions in the $y(x)$ list. DrawDot plots only the calculated points for the functions.
Sequential or Simultaneous Graphing	SeqG (sequential graphing) evaluates and plots one function completely before the next function is evaluated and plotted. SimulG (simultaneous graphing) evaluates and plots all functions for a single value of x before the next value of x is evaluated and plotted.
Grid Off or Grid On	GridOff does not display grid points. GridOn displays grid points. Grid points correspond to the axis tick marks.
Axes On or Axes Off Display	AxesOn displays the axes. AxesOff does not display the axes. It overrides the Axis Label setting.
Axis Label Off or Axis Label On	LabelOff does not label the axes. LabelOn labels the axes with the variables (x and y for Func, Pol, and Param MODE; the labels vary in DfEq MODE).

Defining Functions in the y(x) List

Functions to be graphed are entered on the y(x) editor. Up to 99 functions can be stored in the current graph or in each database, limited only by available memory. One or more of these functions can be graphed at a time.

Displaying the Functions in the y(x) List

To display the y(x) editor, select **y(x)** from the GRAPH menu. If no functions are defined, **y1=** is displayed. In the example below, the **y1** and **y2** functions are defined.



Adding a Function to the y(x) List

Use **↓** or **ENTER** to move the cursor to the line after the final defined function. The next function name is displayed automatically. Enter the expression to define the function.

Note: To move quickly from the first function to the final function in the list, press **↓**.

Inserting a Function in the y(x) List

You can insert a function in the y(x) list only where there are gaps in the number sequence. For example, if only **y1** and **y4** are defined, you can insert **y3**.

1. Move the cursor to the function below which you want to insert.
2. Select **INS** from the y(x) editor menu. The name of the immediately previous function is inserted.
3. Enter the expression to define the function.

Deleting a Function from the y(x) List

1. Move the cursor to the function in the y(x) list.
2. Select **DEL** from the y(x) editor menu. The function, including the name, is deleted.

Entering an Expression to Define a New Function

- The independent variable must be x . You may select x from the $y(x)$ editor menu, press VAR , or press 2ND [alpha] X .
- If the value of $y(x)$ is not real or is undefined for a specified x , no point is plotted for that x ; it is not an error.
- You may use functions, variables, constants, matrix elements, vector elements, list elements, or lists (page 4-15) in the expression.
- You may use entire matrices or vectors in the expression, but the expression must evaluate to a real number at each point to be plotted.
- You may use complex values in the expression, but the expression must evaluate to a real number at each point to be plotted.
- You may use equation variables in the expression. For example, you may use one function in the $y(x)$ list to define another, such as $y2=3y1$. You may select y from the $y(x)$ editor menu and then type the number of the function.
- You may recall equation variables into the expression (page 4-10).

The expression is stored as an equation variable as you enter it. If an expression is longer than one line, it scrolls. 2ND \leftarrow and 2ND \rightarrow move the cursor to the beginning and end of the expression.

When you complete the expression, press ENTER to move to the beginning of the next $y(x)$ function.

Note: If you press a key that displays a menu, the $y(x)$ editor menu moves to the seventh line (if it is not already there), and the selected menu is displayed on the eighth line.

Defining Functions in the $y(x)$ List (Continued)

Editing an Existing Function in the $y(x)$ List

1. Move the cursor to the function in the $y(x)$ list. $\boxed{\text{2nd}} \boxed{\text{F7}}$ and $\boxed{\text{2nd}} \boxed{\text{F5}}$ move the cursor to the end or beginning of the expression quickly.
2. Edit the function in one of the following ways:
 - Position the cursor and make the changes.
 - Press $\boxed{\text{DEL}}$ to clear (blank out) the expression and then enter a new expression.

Recalling an Equation Variable into a Function

You can copy an expression in an equation variable, including another $y(x)$ function, into a function.

1. Press $\boxed{\text{2nd}} \boxed{\text{F1}}$ (VARS). The cursor is positioned after **RCL** on the prompt line. The keyboard is set in ALPHA-lock.
2. Enter the name of the variable. Press $\boxed{\text{2nd}} \boxed{\text{F1}}$. The contents of the variable are inserted at the cursor location in the function, whether the calculator is in insert mode or not.

You can edit the characters you have recalled.

Leaving the $y(x)$ Editor

- To continue defining the graph, select **FORMAT** or **RANGE** from the **GRAPH** menu.
- To display the graph, select **GRAPH**, **TRACE**, **EVAL**, **STGDB**, or **ZOOM**, **DRAW**, **MATH**, or **PIC** operation.
- To display the Home screen, press $\boxed{\text{2nd}} \boxed{\text{QUIT}}$ or **EXIT**.

Entering a $y(x)$ Function from the Home Screen or a Program

You can enter a function in the $y(x)$ list on the Home screen or in the program editor regardless of the current graphing MODE. Use an assignment instruction to store an expression to a function name:

$y_n = \text{expression}$


Selecting Functions

Only functions that are selected are graphed. Any number of functions may be selected at one time. You select and unselect ("turn on" and "turn off") functions for graphing on the $y(x)$ editor.

Turning a Function "On" or "Off"

The equal sign on a selected function is highlighted. To change the selection status of a function:

1. If the $y(x)$ editor is not displayed, select $y(x)$ from the GRAPH menu to display the functions. In the example below, only the $y1$ function is selected.



Defining the Viewing Rectangle

The RANGE variables determine the boundaries and other attributes of the viewing rectangle. The RANGE variables associated with function graphing are retained if another type of graphing is used or if the calculator is off.

The RANGE Variables

The viewing rectangle of the TI-85 is the portion of the coordinate plane defined by the RANGE variables xMin, xMax, yMin, and yMax.



Checking the Viewing Rectangle

To display the values of the current RANGE variables, select (RANGE) from the GRAPH menu. The values shown below are the standard defaults.



Leaving the RANGE Editor

- To continue defining the graph, select (Y(X)=) from the GRAPH menu.
- To display the graph, select (GRAPH), (TRACE), (EVAL), (STOGB), or a ZOOM, DRAW, MATH, or PIC operation.
- To display the Home screen, press (2nd) [QUIT] or (EXIT).

Editing the RANGE Variables 1. Use \leftarrow , \rightarrow , or ENTER to move to the variable.

2. Enter a real value (which can be an expression) in one of the following ways:

- Type a new value. The original value is cleared automatically when you begin typing.
- Use \leftarrow or \rightarrow to position the cursor and then make the change.

3. Press ENTER , 0 , or 1 . If you entered an expression, it is evaluated. The new value is stored.

Note: x_{Min} must be less than x_{Max} , and y_{Min} must be less than y_{Max} . To turn the tick marks off, set x_{Scl} or y_{Scl} to zero.

Setting a RANGE Variable from the Home Screen or a Program

You can store a value to a RANGE variable for the current graphing mode on the Home screen or in the program editor, using the store instruction.

Δx and Δy

The variables Δx and Δy define the distance between the centre of two adjoining points on a graph (graphing accuracy).

$$\Delta x = \frac{(x_{\text{Max}} - x_{\text{Min}})}{128} \qquad \Delta y = \frac{(y_{\text{Max}} - y_{\text{Min}})}{62}$$

Δx and Δy are not on the RANGE screen; they are accessible through the VARS RANGE screen. You can store values to Δx and Δy on the Home screen or in the program editor. When the value is stored, a new value for x_{Max} or y_{Max} is calculated and stored.

Note: Δx and Δy are calculated from x_{Min} , x_{Max} , y_{Min} , and y_{Max} at the time a graph is plotted.

Displaying ■ Graph

Once you have set the MODE, set the graph format, entered and selected functions, and defined the viewing rectangle in order to define a graph, you can display the graph with or without the menu.

Displaying a New Graph

Press **2ND** **GRAPH** to display the GRAPH menu, if necessary. To display the graph, select **GRAPH**. The graph is displayed with the GRAPH menu on line eight. Press **GRAPH** to see the graph with no menus.

The TI-86 graphs all selected functions.

- Functions with undefined values graph without causing an error. For example, an error occurs if you evaluate $1/x$ at $x=0$, but no error occurs when you graph $y1=1/x$ for $-10 \leq x \leq 10$.
- The current graph FORMAT settings apply, and the current values of the RANGE variables define the viewing rectangle.
- As a graph is plotted, the TI-86 updates the variables x and y with the coordinate values of the function.
- As a graph is plotted, the busy indicator in the upper right of the display is on. No menu is displayed until the graph is complete.
- To pause graphing temporarily as a graph is being plotted, press **2ND** **ENTER**. The busy indicator changes to a dotted line. To resume graphing, press **2ND** **ENTER** again. To discontinue graphing after pausing, press **ON**.
- To stop graphing as a graph is being plotted, press **ON** until the graphing stops. Select **GRAPH** to start over.

Note: Smart Graph plots the current graph, if necessary, when you select **TRACE**, **EVAL**, **STGBB**, or **2ND** **ZOOM**, **DRAW**, **MATH**, or **PIC** operation.

Graphing from the Home Screen and Programs

You can display and explore a graph from a program (pages 4-42 and 4-43). You can access graphing commands on the Home screen from the CATALOG.

Displaying More of a Graph


To see parts of the graph that may be "hidden" by the cursor, coordinate values, or menus:

- Press **ENTR** (except during TRACE). The cursor and coordinate values disappear, but the menu(s), if any, remain.
- Select (GRAPH) from the GRAPH menu or press **GRAPH**. The cursor and coordinate values disappear, but the menu(s) remain.
- Press **CLEAR**. The cursor, coordinate values, lower and upper indicators, and menu(s) disappear. TRACE, ZOOM, or MATH operations are cancelled. To display the menu(s) after you press **CLEAR**, press **ENTR** or **GRAPH**.

When you press a cursor-movement key, the cursor moves from its current position and the coordinate values display.

Graphing a Family of Curves

If you enter a list as an element in an expression, the TI-85 plots the function for each value in the list, graphing a family of curves. (In **SimultG**, it graphs all functions for the first element, then for the second element, and so on.) For example, entering $(1,2,3)\sin x$ as a function in the $y(x)$ editor graphs three functions: $1 \sin x$, $2 \sin x$, and $3 \sin x$.



Exploring ■ Graph with the Free-Moving Cursor

While a graph is displayed, the free-moving cursor can be moved anywhere on the graph to identify the coordinate of any location on the graph.

The Free-Moving Cursor

You can use \leftarrow , \rightarrow , \uparrow , and \downarrow to move the cursor around the graph. When you first display the graph, no cursor is visible. As soon as you press a cursor movement key, the cursor moves from the centre of the viewing rectangle.

- In RectGC FORMT, moving the cursor updates the variables x and y . In PolarGC FORMT, the variables r and θ are updated also.
- If the FORMT is CoordOn, the coordinate values of the cursor location are displayed on the lowest available line just above the menu line (if any), as you move the cursor around the graph. Coordinate values generally are displayed with 11 digits in normal floating-decimal format. The numeric display MODE settings do not affect coordinate display.

Note: The free-moving cursor moves from point to point on the display. If you move the cursor to a point that appears to be "on" the function, it may be near, but not necessarily on, the function; therefore, the coordinate value displayed at the bottom of the screen is not necessarily a point on the function. To move the cursor along a function, use the TRACE feature.

Graphing Accuracy

The screen coordinate values approximate actual math coordinates accurate to within the width/height of a point, Δx and Δy (page 4-13).

As the values of $xMax$ and $xMin$ (and $yMax$ and $yMin$) move closer together (after a ZOOM command, for example), Δx and Δy become smaller; the graphing accuracy of the calculator increases, and the display coordinate values more closely approximate the math coordinates.

Exploring a Graph with the TRACE Feature

The TRACE feature moves the cursor from one plotted point to the next along a function. When you select TRACE from the GRAPH menu, Smart Graph displays the current graph, if necessary. The cursor coordinate may be displayed at the bottom of the screen. No menus are displayed during TRACE.

Beginning a TRACE	Select TRACE to begin a TRACE. If the graph is not displayed, the TI-85 displays it. The TRACE cursor is on the first selected function in the $y(x)$ list at the middle x value on the display. The number of the function shows in the upper right of the display.
Moving along a Function	Use \leftarrow or \rightarrow to move the cursor along the function. Each press moves the cursor from one plotted point $(x, y=f(x))$ to the next and updates the variables x and y .
Panning Left or Right	If you TRACE a function to the left or right edge of the display, the viewing rectangle automatically pans to the left or right. The RANGE variables $xMin$ and $xMax$ are updated accordingly.
Tracing a Function above or below the Display	If you trace a function above or below the viewing rectangle, the cursor disappears, but the coordinate is displayed (if CoordOn) and the variables x and y are updated.
QuickZoom	While tracing, you can press ZOOM to adjust the viewing rectangle so that the cursor location is the centre of the new viewing rectangle, even if the cursor is above or below the display.
Moving from Function to Function	To trace another function starting at the same x value, use \uparrow or \downarrow to move the cursor to that function. The function number in the upper right corner changes. The order is based on the order of the functions in the $y(x)$ list, not the appearance of the functions as graphed on the display.
Tracing a Family of Curves	If a selected function graphs a family of curves (page 4-15), \uparrow moves the cursor to each curve in the list before moving to the next $y(x)$ function. \downarrow moves in the reverse or F6 ON .
Cursor Coordinate Display	You must select CoordOn on the FORMAT screen to display the coordinate values x and y for RectGC (r and θ for PolarGC). The y value is calculated from the x value; that is, $y=f(x)$. If the function is nonreal or undefined at an x value, the y value is blank.
Leaving TRACE	To leave TRACE and display the GRAPH menu, press EXIT or GRAPH .

Exploring ■ Graph with the ZOOM Features

Selecting **ZOOM** accesses operations to adjust the viewing rectangle. **BOX**, **ZIN**, **ZOUT**, **ZOOMX**, **ZOOMY**, and **ZINT** prompt you to move the cursor to define a new viewing rectangle. **ZSTD**, **ZPREV**, **ZFIT**, **ZSQR**, **ZTRIG**, **ZRCL**, and **ZDECM** plot the new graph immediately.

The GRAPH ZOOM Menu

When you select **ZOOM** from the **GRAPH** menu, the menu keys are labelled with the first five items of the menu. Press **2nd** to move around the menu.

BOX	ZIN	ZOUT	ZSTD	ZPREV
ZFIT	ZSQR	ZTRIG	ZDECM	ZRCL
ZFACT	ZOOMX	ZOOMY	ZINT	ZSTO

Item	Action
BOX	Draws box to define viewing rectangle (page 4-19).
ZIN	Magnifies graph (page 4-20).
ZOUT	Displays more of graph (page 4-20).
ZSTD	Sets default RANGE variables (page 4-22).
ZPREV	Sets RANGE variables to values prior to executing previous ZOOM operation (page 4-22).
ZFIT	Sets yMin and yMax to include minimum and maximum y values for xMin to xMax (page 4-22).
ZSQR	Sets proportional points on axes (page 4-22).
ZTRIG	Sets built-in trig RANGE variables (page 4-22).
ZDECM	Sets size of points to .1 (page 4-22).
ZRCL	Sets user-defined RANGE variables (page 4-23).
ZFACT	Displays ZOOM FACTORS editor (page 4-21).
ZOOMX	Displays more of graph using xFact only (page 4-20).
ZOOMY	Displays more of graph using yFact only (page 4-20).
ZINT	Sets integer values on axes (page 4-22).
ZSTO	Sets user-defined RANGE variables to current values (page 4-23).

When a **ZOOM** operation is executed, the **TI-85** updates the values of the **RANGE** variables and displays the graph in the new viewing rectangle.

Using ZOOM Box

ZOOM Box uses the cursor to select diagonal corners of a rectangle. The TI-85 then plots the selected functions again, using that rectangle (box) to define the new viewing rectangle.

Defining the ZOOM Box

1. Select **BOX** from the **GRAPH ZOOM** menu. The menu disappears.
Notice the special cursor at the centre of the display. It indicates that you are using a ZOOM operation.
2. Move the cursor to any corner of the box you want to define. Press **ENTER**. The cursor changes to a small square.
3. Move the cursor to the diagonal corner of the box you want to define. As you move the cursor, the boundaries of the box change on the display.
Note: You can cancel the ZOOM BOX procedure any time before you press **ENTER** in one of the following ways:
 - To display the **GRAPH** menu, press **OUT** or **ON**.
 - Press **CLR** to leave ZOOM, but not display the **GRAPH** menu.
 - To return to the Home screen, press **2nd** **QUIT**.
 - To select another screen or menu, press the appropriate keys.
4. When the box is defined as you want it, press **ENTER**.

The TI-85 updates the **RANGE** variables and plots the selected functions in the new viewing rectangle defined by the box.

Zooming In or Out

ZIN (zoom in) magnifies the graph. ZOUT (zoom out) displays more of the graph. ZOOMX and ZOOMEY display more of the graph horizontally or vertically. Changes are centred around the cursor location. The xFact and yFact settings determine the extent of the magnification.

Zooming In on a Graph

1. After checking or changing the ZOOM factors (page 4-21), select ZIN from the GRAPH ZOOM menu. Notice the special cursor. It indicates that you are using a ZOOM operation.
 2. Move the cursor to the point you want as the centre of the new viewing rectangle. Press **ENTER**.
The TI-85 adjusts the viewing rectangle by xFact and yFact, updates the RANGE variables, and plots the selected functions again, centred around the cursor location.
- You can zoom in on the graph again:

- To zoom in at the same point, press **ENTER**.
- To zoom in at a new point, move the cursor to the new point and press **ENTER**.

You can press **2ND** **ENTER** to zoom in on a graph repeatedly. ZIN is not cancelled until you press a key other than **ENTER** or a cursor-movement key.

Using ZOUT

The procedure for ZOUT is the same as for ZIN.

ZOOMX and ZOOMEY

The procedure to zoom out on a graph using only xFact or only yFact is the same as for ZIN.

- ZOOMX adjusts the horizontal axis of the viewing rectangle by xFact, updates the RANGE variables, and plots the selected functions again, centred around the cursor location. yMin and yMax are not changed.
- ZOOMEY adjusts the vertical axis of the viewing rectangle by yFact, updates the RANGE variables, and plots the selected functions again, centred around the cursor location. xMin and xMax are not changed.

Setting ZOOM Factors


ZOOM factors determine the extent of the change for the viewing rectangle created by ZIN, ZOUT, ZOOMX, or ZOOMY on a graph. You can review or edit the ZOOM factors.

ZOOM Factors

ZOOM factors are positive numbers (not necessarily integers) greater than or equal to 1. They define the magnification or reduction factor used to zoom in or out around a point (page 4-20). ZOOM factors are global; they apply to all graphing modes. **xFact** is the variable name for the horizontal factor; **yFact** is the variable name for the vertical factor.

Checking xFact and yFact

Select (ZFACT) from the GRAPH ZOOM menu to display the ZOOM FACTORS screen (values shown are defaults).



Editing xFact and yFact

1. Enter a real value (which can be an expression) in one of the following ways:
 - Type a new value. The original value is cleared automatically when you begin typing.
 - Use \rightarrow or \leftarrow to position the cursor and then make the changes.
2. Press ENTER , Y , or ↓ . If you entered an expression, it is evaluated. The new value is stored.

Setting ZOOM Factors from the Home Screen or a Program

You can store a value to **xFact** or **yFact** on the Home screen or in the program editor. Select the variable name from the VARS ALL screen or type it from the keyboard.
value \rightarrow xFact or value \rightarrow yFact

Other ZOOM Features

The TI-85 has a variety of additional ZOOM features for exploring a graph. Some reset the RANGE variables to predefined values and some use factors to adjust the RANGE variables. All except ZINT plot the selected functions as soon as the menu selection is made.

Previous	ZPREV (zoom previous) returns to the viewing rectangle displayed prior to the previous ZOOM.	
Standard	ZSTD (zoom standard) changes the RANGE variables to the standard default values:	
	xMin=-10 xMax=10 xScl=1	yMin=-10 yMax=10 yScl=1
Fit	ZFIT (zoom to fit) recalculates yMin and yMax to include the minimum and maximum y values of the selected functions between the current xMin and xMax. xMin and xMax are not changed. (The busy indicator displays as the new viewing rectangle is calculated.)	
Square	ZSQR (zoom square) redefines the viewing rectangle based on the current RANGE variables. The RANGE variables are adjusted in only the x direction or y direction. The midpoint of the current graph (not the axis) becomes the midpoint of the new graph. ZSQR makes the graph of a circle look like a circle.	
Trig	ZTRIG (zoom trig) changes the RANGE variables to values appropriate for trig functions ($\Delta x = \pi/24$). The trig RANGE variables in Radian MODE are:	
	xMin=-8.24668071567 xMax=8.24668071567 xScl=1.5707963267949 ($\pi/2$)	yMin=-4 yMax=4 yScl=1
Decimal	ZDECM (zoom decimal) changes the RANGE variables to values that set Δx and $\Delta y = .1$.	
	xMin=-6.3 xMax=6.3 xScl=1	yMin=-3.1 yMax=3.1 yScl=1
Integer	ZINT (zoom integer) plots the selected functions, redefining the viewing rectangle so that $\Delta x=1$, $\Delta y=1$, the mid-point of each point is an integer, xScl=10, and yScl=10. Move the cursor to the point you want as the centre of the new viewing rectangle. Press ENTER .	

The User-Defined ZOOM

ZSTO stores the values of the current RANGE variables to user-defined ZOOM RANGE variables. ZRCL changes the viewing rectangle to the values stored with ZSTO.

User-Defined ZOOM RANGE Variables

In Func MODE there are six ZOOM RANGE variables that are user-defined: `zxMin`, `zxMax`, `zxSci`, `zyMin`, `zyMax`, and `zySci`. These variables are global; they apply to all graphing modes. Changing the value of `zxMin`, for example, in Func MODE also changes it in Param MODE.

Setting ZOOM RANGE Variables

To store the current viewing rectangle, select (ZSTO) (zoom store) from the GRAPH ZOOM menu. The values of the current RANGE variables are stored in the user-defined ZOOM RANGE variables.

The user-defined ZOOM RANGE variables contain the standard default values until you edit them the first time.

Setting a User-Defined ZOOM RANGE Variable from the Home Screen or a Program

You can store a value to a user-defined ZOOM RANGE variable, such as `zxMin`, from the Home screen or in a program. Select the variable name from the VARS RANGE screen or type it from the keyboard.

value→zoom_range

Recalling the User-Defined Viewing Rectangle

When you select (ZRCL) from the GRAPH ZOOM menu, ZRCL (zoom recall) updates the RANGE variables to the values of the user-defined ZOOM RANGE variables. The selected functions are plotted as soon as the menu selection is made.

The GRAPH MATH Menu

The GRAPH MATH operations analyze the graph that is displayed. The current graph is displayed when the GRAPH MATH operation is selected.

The GRAPH MATH Menu

When you select MATH from the GRAPH menu, the menu keys are labelled with the first five items of the menu. Press \rightarrow to move around the menu.

LOWER FMIN DIST	UPPER FMAX ARC	ROOT INFLC TANLN	dy/dx YICPT	f(x) ISECT
Item	Item			
LOWER	Defines lower bound of interval (page 4-25).			
UPPER	Defines upper bound of interval (page 4-25).			
ROOT	Finds root of a function in interval (page 4-26).			
dy/dx	Finds derivative (slope) of a function at a point (page 4-26).			
f(x)	Approximates definite integral of a function in interval (page 4-26).			
FMIN	Finds minimum of a function in interval (page 4-27).			
FMAX	Finds maximum of a function in interval (page 4-27).			
INFLC	Finds inflection point of a function in interval (page 4-27).			
YICPT	Finds y-intercept of a function (page 4-26).			
ISECT	Finds intersection of two functions in interval (page 4-27).			
DIST	Finds distance between two points on the display (page 4-28).			
ARC	Finds distance along a function between two points on a function (page 4-28).			
TANLN	Draws tangent line at a point (page 4-28).			

Setting an Interval for MATH Operations

The MATH operations **ROOT**, **H(x)**, **ISECT**, **FMIN**, **FMAX**, and **INFLC** analyze a function between two values of x , identified by the variables **lower** and **upper**.

lower and upper

On a graph, the values of **lower** and **upper** are always between **xMin** and **xMax**. **lower** changes to **xMin** and **upper** changes to **xMax** if

- You execute a **ZOOM** operation.
- You change **xMin** or **xMax** in the **RANGE** editor or from a command line.

First define the viewing rectangle, and then set **lower** and **upper** from the **GRAPH MATH** menu or from a command line.

Setting an Interval from a Graph

You can select the interval in which to analyze the graph. If you do not explicitly define the interval, **lower** is set to **xMin** and **upper** is set to **xMax**.

1. Select **MATH** from the **GRAPH** menu. The **GRAPH MATH** menu is displayed.
2. Select **LOWER** from the **GRAPH MATH** menu. The selection cursor is displayed on the current graph.
3. Position the cursor on the x value for the lower endpoint of the interval. Press **→**. A right-arrow indicator at the top of the display shows the lower endpoint and the x -coordinate value is stored in the variable **lower**. (When **lower**=**xMin**, the indicator is a single point.)
4. Set **upper** in the same way.

Setting an Interval from the Home Screen or a Program

To use an exact value for **lower** or **upper**, store a value to the variable from the Home screen before you press **→**. In a program, store a value to **lower** or **upper** to define the interval.

Using the MATH Operations

The GRAPH MATH operations provide a number of mathematical graph-analysis features to use directly on a graph. When you select any of these operations from the menu, the graph is displayed without menus, and the cursor is in TRACE mode. Restrictions are the same as for the CALC functions.

- The ROOT Operation** ROOT uses the SOLVER (page 14-7) to find a root of a function. Set values for **lower** and **upper**, if desired. Select (ROOT), ms Δ or ∇ to move the TRACE cursor to the desired function. Use \rightarrow or \leftarrow to move to a point between **lower** and **upper** to serve as an initial guess. Press ENTER . The result cursor is displayed at the solution point; the cursor coordinate value is the result, and x is stored in **Ans**.
- The dy/dx Operation** dy/dx (derivative) finds the derivative (slope) of a function at a point. The accuracy is affected by the differentiation MODE (Chapter 1) and the variable δ (Chapter 3). Select dy/dx. Use Δ or ∇ to move the TRACE cursor to the desired function. Use \rightarrow and \leftarrow to move to the desired point. Press ENTER . The result dy/dx= is displayed and stored in **Ans**.
- The $\int f(x)$ Operation** $\int f(x)$ (numerical integral) finds the numerical integral of a function between **lower** and **upper**. The accuracy is affected by the variable tol (Chapter 3). Select $\int f(x)$. Use Δ or ∇ to move the TRACE cursor to the desired function. Use \rightarrow or \leftarrow to move to the desired value for **lower**. Press ENTER . Repeat for **upper** (must be on the display). The result $\int f(x)=$ is displayed and stored in **Ans**. A value indicative of possible solution error is stored in **fnIntErr**.
- The YICPT Operation** YICPT (y intercept) calculates the value of y when $x=0$ for a function. Select YICPT. Use Δ or ∇ to move the TRACE cursor to the desired function. Press ENTER . The result cursor is displayed at the solution point; the cursor coordinate value is the result, and y is stored in **Ans**.

The FMIN and FMAX Operations

FMIN (function minimum) and FMAX (function maximum) find the minimum or maximum value of a function. The accuracy is affected by the variable **tol** (Chapter 3).

Set values for **lower** and **upper**, if desired. Select FMIN or FMAX, use **▲** or **▼** to move the TRACE cursor to the desired function. Press **ENTER**. The result cursor is displayed at the solution point, the cursor coordinate value is the result, and **x** is stored in **Ans**.

The ISECT Operation

ISECT (intersection) uses the SOLVER (page 14-7) to find an intersection of two functions.

Set values for **lower** and **upper**, if desired. Select ISECT. Use **▲** or **▼** to move the TRACE cursor to the desired first function. Press **ENTER**. The cursor automatically moves to the next function in the list. If necessary, use **▲** or **▼** to move to the desired function. Use **←** or **→** to move the cursor to a point near the intersection, between **lower** and **upper**, to serve as an initial guess. Press **ENTER**. The result cursor is displayed at the solution point; the cursor coordinate value is the result, and **x** is stored in **Ans**.

The INFLC Operation

INFLC (inflection) finds an inflection point for a function.

Set values for **lower** and **upper**, if desired. Select INFLC. Use **▲** or **▼** to move the TRACE cursor to the desired function. Press **ENTER**. The result cursor is displayed at the solution point, the cursor coordinate value is the result, and **x** is stored in **Ans**.

Using the MATH Operations (Continued)

The DIST Operation	<p>DIST (distance) finds the straight-line distance between two points on a function or functions.</p> <p>Select (DIST). Use \leftarrow or \rightarrow to move the TRACE cursor to the desired function. Use \uparrow or \downarrow to move the TRACE cursor to the first point (on the display). Press $\boxed{\text{ENTER}}$. The point is marked. Use \uparrow or \downarrow (if necessary) and \leftarrow or \rightarrow to move to the second point (on the display). A line displays as you move the cursor, but disappears if you TRACE off the display. Press $\boxed{\text{ENTER}}$. The result DIST= is displayed and stored in Ans.</p>
The ARC Operation	<p>ARC finds the distance along a function between two points on the function. The accuracy is affected by the variables tol and sometimes δ (Chapter 3) and the differentiation MODE (Chapter 1).</p> <p>Select (ARC). Use \uparrow or \downarrow to move the TRACE cursor to the desired function. Use \leftarrow or \rightarrow to move the TRACE cursor to the first point. Press $\boxed{\text{ENTER}}$. The point is marked. Use \leftarrow or \rightarrow to move to the second point (on the display). Press $\boxed{\text{ENTER}}$. The result ARC= is displayed and stored in Ans.</p>
The TANLN Operation	<p>TANLN (tangent line) draws a tangent line at a point on a function. The accuracy is affected by the differentiation MODE and the variable δ (Chapter 3).</p> <p>Select (TANLN). Use \uparrow or \downarrow to move the TRACE cursor to the desired function. Use \leftarrow and \rightarrow to move to the desired point. Press $\boxed{\text{ENTER}}$. The tangent line is drawn, and the result $dy/dx=$ is displayed and stored in Ans. (Select (CLDRW) from the DRAW menu to remove the line.)</p>
Results	<p>Coordinate value results are displayed for ROOT, YICPT, (SECT, FMAX, FMIN, and INFLC even if you have selected CoordOff on the FORMT screen. The coordinate values of the results cursor are stored in x and y.</p> <p>When a cursor-movement key is pressed, the result cursor disappears and the free-moving cursor appears near the location of the result.</p>

Using EVAL to Analyze ■ Graph

EVAL evaluates currently selected functions for a specified value of x . You can use **EVAL** directly on a graph. You also can use **eval** from the Home screen or a program.

Using **EVAL** on a Graph

1. Select (**EVAL**) from the **GRAPH** menu. The graph displays. The cursor is positioned after **Eval x=** on the prompt line.
2. Enter a real value for x between **xMin** and **xMax** (which can be an expression).

If there is a value entered for **Eval=**, **GRAPH** clears it. If there is no value for x , **GRAPH** cancels **EVAL**.

3. Press **ENTER**. The result cursor is on the first selected function in the list at the entered x and the coordinate values are displayed. (Coordinates are displayed even if you have selected **CoordOff** on the **FORMAT** screen.) Use **↑** or **↓** to move the cursor between functions at the entered x value.

When **→** or **←** is pressed, the free-moving cursor appears. It cannot necessarily move back to the **EVAL** x value.

Using the **eval** Function from the Home Screen or a Program

The **eval** (evaluate) function returns the value of any selected functions, evaluated at the specified x value. The only argument is the real x value at which to evaluate the functions (which can be an expression).

eval x_value

The results are returned as a list. If any of the functions are defined as a family of curves, each value is given in the list.

For example, if $y1=x^3$ and $y2=1/x$ and both are selected, then **eval** \blacksquare returns $\{125, .2\}$.

Note: **eval** cannot be used in a $y(x)$ expression.

The DRAW Menu

The **GRAPH DRAW** menu accesses operations that draw points, lines, circles, and shaded areas on a graph. You can draw directly on a graph using the cursor to identify coordinates or you can enter these instructions on the Home screen or in the program editor.

The GRAPH DRAW Menu

When you select **DRAW** from the **GRAPH** menu, the menu keys are labelled with the first five items of the menu. Press **2nd** to move around the menu.

Shade
PEN
TanLn

PTON
DrInV

VERT
PTOFF

CIRCL
PTCHG

DrawF
CLDRW

Item	Accesses
Shade	Instruction that shades part of the graph (Home screen or program only) (page 4-32).
LINE	Operation that draws a straight line (page 4-34).
VERT	Operation that draws a vertical line (page 4-35).
CIRCL	Operation that draws a circle (page 4-36).
DrawF	Instruction that draws a function (Home screen or program only) (page 4-37).
PEN	Operation that accesses a free-form drawing tool (interactive only) (page 4-38).
PTON	Operation that turns on a point (page 4-39).
PTOFF	Operation that turns off a point (page 4-39).
PTCHG	Operation that toggles a point on and off (page 4-39).
CLDRW	Operation that clears drawings (page 4-31).
TanLn	Instruction that draws a tangent line (Home screen or program only) (page 4-35).
DrInV	Instruction that draws the inverse function (Home screen or program only) (page 4-37).

The **DRAW** operations, except **DrInV**, can draw on **Func**, **Polar**, **Param**, and **DifEq** graphs. The coordinates for **DRAW** instructions are entered as the **x**-coordinate and **y**-coordinate values of the display.

Drawing on a Graph

The **DRAW** operations let you draw points, lines, circles, and shading on the current graph. These drawings are temporary.

The DRAW Operations

Access the **DRAW** operations through:

- The **GRAPH** menu to draw on a graph interactively.
- The **CATALOG** to enter **DRAW** instructions on the Home screen or in the program editor.
- The **GRAPH** menu in the program editor.

All points, lines, and shading drawn on a graph with **DRAW** operations are temporary. When the "Smart Graph" feature (page 4-5) plots a graph, all drawn points, lines, and shading are erased. A family of curves (page 4-15) cannot be drawn with **Shade**, **DrawF**, **DrawI**, or **TanLn**.

Before Drawing on a Graph

Because the **DRAW** operations draw on top of the graph of the currently selected functions, the following steps may be appropriate before drawing on a graph:

1. Change the **MODE** settings (page 4-3).
2. Change the graph **FORMT** (pages 4-6 and 4-7).
3. Enter or edit expressions to define functions in the **y(x)** list (pages 4-8 to 4-10).
4. Select or unselect functions in the **y(x)** list (page 4-11).
5. Edit **RANGE** variables (pages 4-12 and 4-13).

Clearing a Drawing from a Graph

To clear drawings from the currently displayed graph, select **CIDRW** from the **GRAPH DRAW** menu. The current graph is plotted and displayed with no drawn elements.

Clearing a Drawing from the Home Screen or a Program

The **CIDrw** (clear drawing) clears drawings from the current graph. It displays the message **Done**. The next time you display the graph, all drawn points, lines, circles, and shaded areas will be gone. **CIDrw** has no arguments.

Note: You can store drawings with **STPic** (page 4-11).

Shading Areas ■ ■ Graph

The **Shade** instruction shades the area on a graph that is below one specified function and above another. It also draws the two functions.

The Shading Parameters

The **Shade** instruction can have four arguments. Only the areas above the first argument is shaded; the second argument are optional. The first argument is the bottom boundary. The second argument is the top boundary.

The first argument defines the bottom boundary of the shaded area and the function to be drawn. The argument can be any of the following:

- An expression in terms of x . For example, x^2+1 shades the area above the curve $y=x^2+1$.
- A real value (which can be an expression). For example, 3 shades the area above the line $y=3$.
- An expression stored in an equation variable or a function in the $y(x)$ list and referenced by name. For example, if $y^2=x^2+5$, $y2$ shades the area above the curve $y=x^2+5$.

The second argument defines the top boundary of the shaded area and the function to be drawn. The argument can be any of the types described for the first argument.

The third argument (optional) defines the left boundary of the shaded area (the beginning x). It is a real value (which can be an expression). If the argument is not specified, the default is the current value of **lower** (or **xMin** if the **MODE** is not **Func**).

The fourth argument (optional) defines the right boundary of the shaded area (the ending x). It is a real value (which can be an expression). If the argument is not specified, the default is the current value of **upper** (or **xMax** if the **MODE** is not **Func**).

Drawing a Shaded Area on a Drawing


To shade an area on a graph, enter the instruction on a blank line on the Home screen or in the program editor.

1. Select **DRAW** from the **GRAPH** menu.
2. Select **Shade** from the **GRAPH DRAW** menu. **Shade** is copied to the cursor location. (If you select **Shade** while the graph is displayed, the Home screen is displayed.)
3. Enter the first argument. Press **[]**.
4. Enter the second argument.
 - If you do not want to enter the third or fourth arguments, go to step 6.
 - If you want to enter the third and fourth arguments, press **[]**, and then go to step 5.
5. Enter the optional arguments, separated by commas.
6. Press **[]** and **ENTER**.

When the instruction is executed, the shaded area and the two functions, as defined by the arguments, are drawn on the current graph:

Shade(lowerfunc,upperfunc,xbeg,xend)

For example, **Shade(x+1,x²-8x,-5.5)** displays:



Drawing Lines

While a graph is displayed, the LINE operation lets you define a line on the graph using the cursor. You also can enter an instruction on the Home screen or in the program editor to draw a line on a graph.

Drawing a Line from a Graph

1. Select **LINE** from the **GRAPH DRAW** menu. The current graph is displayed.
2. Position the cursor at the beginning point of the line you want to draw. Press **ENTER**.
3. Move the cursor to the end point of the line you want to draw. The line is displayed as you move the cursor. Press **ENTER**. The line is drawn on the graph between the two selected points.


Repeat steps 2 and 3 to continue to draw lines. To cancel **LINE** and display the menus, press **EXIT**.

Drawing a Line from the Home Screen or a Program

The **Line** instruction on the Home screen or in the program editor has four real value arguments (which can be expressions): the x value and y value of the beginning coordinate and the x value and y value of the ending coordinate.
Line(xbeg,ybeg,xend,yend)

When the instruction is executed, the line is drawn on the current graph.

For example, **Line(1,1,6,8)** displays:



Drawing Vertical Lines and Tangent Lines

While a graph is displayed, the VERT operation lets you define a vertical line on the graph using the cursor. You also can enter the instruction on the Home screen or in the program editor. Using the TanLn instruction, you can draw the tangent line of a function at a specified point.

Drawing a Vertical Line from a Graph

1. Select VERT from the GRAPH DRAW menu. The current graph is displayed.
2. Position the cursor where you want to draw the vertical line. A line is displayed as you move the cursor. Press **ENTER**. The line is drawn.

Repeat step 2 to continue to draw vertical lines. To cancel VERT and display the menus, press **ESC**.

Drawing a Vertical Line from the Home Screen or a Program

The VERT (vertical line) instruction on the Home screen or in the program editor requires one argument, the real x value at which to draw the vertical line (which can be an expression).

Vert x

Drawing a Tangent Line

TanLn (tangent line) draws a line tangent to a function at a specified point. When you select TanLn from the GRAPH DRAW menu, the instruction is copied to the Home screen. The TanLn instruction requires two arguments: an expression in terms of x and the real x value at which to draw the tangent line (which can be an expression). The expression is interpreted as being in Func MODE.

TanLn(expression,value)

For example, if $y1 = 2x^3 - 2x + 6$ is the only selected function, **TanLn(y1,3)** plots y1 and draws the tangent line:



Note: You can draw a tangent line interactively through the GRAPH MATH **MENU** (page 4-28).

Drawing Circles

While a graph is displayed, the CIRC operation lets you define a circle on the graph using the cursor. You also can enter an instruction on the Home screen or in the program editor to draw a circle on a graph.

Drawing a Circle from a Graph

1. Select (CIRC) from the GRAPH-DRAW menu. The current graph is displayed.
2. Position the cursor at the centre of the circle you want to draw. Press **ENTER**.
3. Move the cursor to a point on the circumference. Press **ENTER**. The circle is drawn on the graph.

Because this circle is drawn on the display and is independent of the RANGE values (unlike the CIRC instruction, see below), it appears as a circle.

Repeat steps 2 and 3 to continue to draw circles. To cancel CIRC and display the menus, press **ESC**.


Drawing a Circle from the Home Screen or a Program

The CIRC instruction on the Home screen or in the program editor requires three real arguments (which can be expressions): the x-coordinate and y-coordinate values of the centre, and the radius of the circle.

CIRC(x,y,radius)

When the instruction is executed, the circle is drawn on the current graph.

Note: When the CIRC instruction is used from the Home screen, the drawn circle may not look like a circle because it is drawn with respect to the current RANGE values. For example, in the standard viewing rectangle, **CIRC(0,0,5)** displays:



To make the drawn circle look like a circle, execute **ZSqr** first.

Drawing Functions and Inverses

The **DrawF** instruction draws a function on the current graph from the Home screen or in the program editor. The **DrInV** instruction draws an inverse of a function on the current graph from the Home screen or a program.

Drawing a Function: **DrawF** (draw function) draws a function on the current graph. When you select **DrawF** from the **GRAPH DRAW** menu, the instruction is copied to the Home screen. The **DrawF** instruction requires one argument, an expression in terms of x :

DrawF expression

For example, if $y1=2x^3-2x+6$ is the only selected function, **DrawF** $y1-5$ plots $y1$ and draws the function:



Drawing an Inverse of a Function

DrInV (draw inverse) draws the inverse of a function on the current graph. When you select **DrInV** from the **GRAPH DRAW** menu, the instruction is copied to the Home screen. You must be in **Func MODE**. The **DrInV** instruction requires one argument, an expression in terms of x :

DrInV expression

For example, if $y1=2x^3-2x+6$ is the only selected function, **DrInV** $y1$ plots $y1$ and draws its inverse:



Using PEN to Draw on a Graph

While a graph is displayed, the PEN feature lets you draw directly on the graph with the cursor.

Using the PEN

Overview

PEN can only draw directly on a graph. It is not an instruction.

1. Select **PEN:** from the **GRAPH DRAW** menu. The current graph is displayed.
2. Position the cursor where you want to begin drawing. Press **ENTER** to turn the pen on.
3. As you move the cursor, it draws on the graph, turning on each point that the cursor crosses.
4. Press **ENTER** to turn the pen off. Move the cursor to a new position where you want to begin drawing again.

Repeat steps 2, 3, and 4 to continue to draw on the graph with the pen. To cancel PEN and display the menus, press **ESC**.

Drawing Points

While a graph is displayed, the PT (point) operations let you turn on, turn off, or reverse a point on the graph using the cursor. You also can enter an instruction on the Home screen or in the program editor to execute these instructions.

Drawing a Point from a Graph

1. Select **PTON** from the **GRAPH DRAW** menu. The current graph is displayed.
2. Position the cursor at the location on the display where you want to draw the point. Press **ENTER**. The point is drawn.

Repeat step 2 to continue to draw points. To cancel **PTON** and display the menus, press **ESC**.

Drawing a Point from the Home Screen or a Program

The **PtOn** (point on) instruction on the Home screen or in the program editor requires two real arguments (which can be expressions): the x value of the coordinate and the y value of the coordinate.

PtOn(x,y)

When the instruction is executed, the point is drawn on the current graph.

The **PTOFF** and **PTCHG** Instructions

The procedure for using **PTOFF** (point off) to turn off (erase) a point is the same as for **PTON**.

The procedure for using **PTCHG** (point change) to toggle (reverse) a point on and off is the same as for **PTON**.

Storing and Recalling Graph Databases

A graph database is the elements that define a particular graph. The graph can be recreated from these elements. You can store these elements with a user-assigned name and recall it as the current graph at a later time. Graph databases do not include any drawn items.

Graph Databases

The elements of a graph database are:

- Graphing MODE, graph FORMAT settings, and RANGE variables.
- All functions in the $y(x)$ list, and whether they are selected.

Storing a Graph Database

1. Select **STGDB** (store graph database) from the **GRAPH** menu.
2. The cursor is positioned after **Name=** on the prompt line. The menu keys are labelled with the names of existing databases for the current graphing MODE in alphabetical order. You may type a name or select one from the menu.
3. Press **ENTER**. The elements of the current database are stored.

Recalling a Graph Database

Caution: When you recall a graph database, all existing $y(x)$ functions are replaced. You may want to store the current $y(x)$ functions to another database before recalling a stored database.

1. Select **RCGDB** (recall graph database) from the **GRAPH** menu.
2. Enter the name as above.
3. Press **ENTER**. The new database replaces the current graph database.
 - If you recall a graph database while a graph is displayed, the graphing mode of the recalled database must match the current graphing mode. The new graph is plotted.
 - If you recall a graph database from the Home screen or a program (page 4-43), the TI-85 changes graphing MODE automatically, if necessary. The new graph is not plotted.

Deleting a Graph Database

Graph databases are deleted from memory through the memory management menu (Chapter 18.)

Storing and Recalling Graph Pictures

You can store an image of the current display with a user-assigned name and superimpose that image onto a displayed graph at a later time from the Home screen or a program.

Storing a Graph Picture

A picture includes drawn elements, plotted functions, axes, and tick marks. The picture does not include menus, axis labels, lower and upper indicators, prompts, or cursor coordinates. Any parts of the display "hidden" by these are stored with the picture.

1. Select (STPIC) from the GRAPH menu. The current graph is displayed if necessary.
2. The cursor is positioned after Name= on the prompt line, and the menu keys are labelled with the names of existing pictures in alphabetical order. You may type a name or select one from the menu.
3. Press ENTER. The most recently displayed picture is stored.

Recalling a Graph Picture

1. Select (RCPIC) from the GRAPH menu. The current graph is displayed if necessary.
2. The cursor is positioned after Name= on the prompt line. Enter the name as above.
3. Press ENTER. The picture is superimposed on the current graph.

Note: Pictures are drawings. You cannot TRACE any curve on a picture.


Deleting a Graph Picture

Graph pictures are deleted from memory through the memory management menu (Chapter 18.)

GRAPH Menu Items in the Program Editor

You can access the graphing capabilities of the TI-85 in the program editor (Chapter 16). To enter graphing instructions, type the name, copy it from CATALOG, or select it from the GRAPH menu in the program editor.


The GRAPH Menu in the Program Editor

When you press  in the program editor, the menu keys are labelled with the PRGM GRAPH menu.

VARS	RANGE	ZOOM	Trace	DispG
MATH	DRAW	FORMAT	StGDB	ReGDB
eval	StPic	RePic		

The VARS Menu

When you select (VARS), the menu keys are labelled with the names of the graphing variables and some instructions.

y	x	x1	y1	t
z	0	Q	Q'	t
FnOn	FnOff	Axes		

The RANGE Menu


When you select (RANGE), the menu keys are labelled with the names of all the RANGE variables:


xMin	xMax	xScI	yMin	yMax
yScI	tMin	tMax	tStep	tMin
eMax	0Step	tPicI	dltToI	

The ZOOM

Instructions


When you select (ZOOM), the menu keys are labelled:

ZInt	ZIn	ZOut	ZStd	
ZFlt	ZSqr	ZTrg	ZDecm	ZFlt

When a ZOOM instruction is executed, the current graph is displayed. ZInt, ZIn, ZOut and ZSqr use the midpoint of the current graph as the new midpoint. If Pause (Chapter 16) is the next program command, the program halts as you examine the display. Execution resumes when you press .

The Trace Instruction

When you select (Trace), Trace is copied to the cursor location.

When the Trace instruction is executed, the current graph is displayed with cursor coordinate values, the TRACE cursor is on the midpoint of the first selected function, and the special program input busy signal is displayed. Use the cursor movement keys to move the cursor. Press  to resume program execution.

GRAPH Menu Items in the Program Editor (Continued)

The DispG

DispG

DispG displays a graph of currently selected functions during program execution. The graph has no cursor and no menu. In the program editor, press **GRAPH** and then select **DispG**. **DispG** is copied to the cursor location. You can use the **Pause** instruction (Chapter 16) to halt the program so you can examine the display. Execution resumes when you press **ENTER**.

The MATH Menu

When you select **MATH**, the menu keys are labelled with the **CALC** function that corresponds to the interactive **GRAPH MATH** operation.

fMin **fMax** **wrc** **MEM**

The DRAW

Instructions

When you select **DRAW** the menu keys are labelled:

Shade **Line** **Vert** **Circl** **DrawF**
PtOn **PtOff** **PtChg** **CiDrw** **TanLn**
DrInv

The **DRAW** instructions are described on pages 4-30 to 4-39.

FORMAT Settings

You can set graph **FORMAT** settings in a program through a TI-85 interactive selection screen (Chapter 16).

The eval Function


When you select **eval**, **eval** is copied to the cursor location. The **eval** function is described on page 4-29.


Graph Databases and Pictures

When you select a store or recall instruction, the name of the instruction is copied to the cursor location. Type the name of the database or picture or copy it from the **VARS GDB** or **VARS PIC** screen.

StGDB database_name **MEM** **RcGDB database_name**
StPic picture_name **and** **RcPic picture_name**

GRAPH Menu Chart





Example: Using Lists in Graphing

The TI-85 uses lists to graph a family of curves. The function is evaluated and plotted once for each element of the list. Plot the functions $2x-(0,2,4)$ and $(1,2,3) \sin(2x-(0,2,4))$.

Procedure

1. Press **2ND**, select $y(x)=$ and enter the functions:

$$y1=2x-(0,2,4)$$

$$y2=(1,2,3) \sin y1$$

Note: { and } are on the LIST menu.

2. Place the cursor anywhere on $y1$ and select (SELECT) to turn off the function so it will not graph.
3. Select (RANGE) from the GRAPH menu and set the RANGE variables:

$$xMin=-10$$

$$yMin=-3$$

$$xMax=10$$

$$yMax=3$$

$$xScl=1$$

$$yScl=1$$

4. Select (GRAPH) to graph the functions:

$$f^1(x)=\sin 2x$$

$$f^2(x)=2 \sin(2x-2)$$

$$f^3(x)=3 \sin(2x-4)$$

5. Press **CLEAR** to clear the menu from the display.



Chapter 5: Polar Graphing

This chapter describes how to graph polar equations on the TI-85. Polar graphs are completely independent of function, parametric, or differential equation graphs. Before doing polar graphing, you should be familiar with the graphing features in Chapter 4, Function Graphing.

Chapter Contents	Defining and Displaying a Polar Graph	5-2
	Exploring and Analyzing a Polar Graph	5-4
	Example: Graphing a Cardioid	5-6

Defining and Displaying a Polar Graph

Polar equations are defined in terms of the independent variable, θ . Up to 99 polar equations can be defined and graphed at one time, limited by available memory.

Steps in Defining a Polar Graph

The steps for defining a polar graph are the same as those for defining a function graph. Differences are noted below. Graph format, equations, and RANGE variables in Pol graphing are independent of the other graphing modes.

Setting the Graphing MODE

To graph polar equations, you must select **Pol** on the **MODE** screen.

The Pol GRAPH Menu

The **Pol GRAPH** menu is:

$r(\theta)=$	RANGE	FORM	TRACE	GRAPH
MATH	ORAW	FORMAT	STGDB	RECALL
EVAL	STPIC	RCPIC		

Setting the Graph Format

Select **(FORMAT)** to display the **FORMAT** screen. In Pol graphing, you may select **RectGC** or **PolarGC** graph coordinate display; **PolarGC** shows the cursor coordinates in terms of the variables that define the equations, r and θ .

DrawLine usually presents a more meaningful Pol graph.

Displaying Polar Equations

Select $r(\theta)=$ from the **GRAPH** menu to display the $r(\theta)$ editor, where you display and enter polar equations. You can enter up to 99 equations into 99 equations (one line of memory). $r1=2\sin(3\theta)$



Defining a Polar Equation

Enter or edit the polar equation(s).

- The independent variable in each equation must be θ . You may select θ from the menu.
- You can reference another equation; for example, $r2=r1+1$. You may select r from the menu, and then type the number of the equation.

Selecting a Polar Equation

Only the polar equations you select are graphed. The procedure for selecting equations in Pol graphing is the same as in Func graphing.

Defining the Viewing Rectangle

Select **RANGE** to display and change the **RANGE** variables. The values shown below are the standard defaults in **Radian MODE**.

Setting	Meaning
$\theta\text{Min}=0$	Smallest θ value to evaluate
$\theta\text{Max}=6.28318530718$	Largest θ value to evaluate (2π)
$\theta\text{Step}=.13089969389957$	Increment between θ values ($\pi/24$)
$x\text{Min}=-10$	Smallest x value to display
$x\text{Max}=10$	Largest x value to display
$x\text{Scl}=1$	Spacing between x tick marks
$y\text{Min}=-10$	Smallest y value to display
$y\text{Max}=10$	Largest y value to display
$y\text{Scl}=1$	Spacing between y tick marks

Displaying the Graph

Select **GRAPH**, **TRACE**, **EVAL**, **STGE**, or a **ZOOM**, **DRAW**, **MATH**, or **PIC** operation to plot the selected polar equations. The TI-85 evaluates r for each value of θ (from θMin to θMax in intervals of θStep) and then plots each point. As the graph is plotted, the variables θ , r , x , and y are updated.

Graph Databases and Pictures

Storing or recalling a graph database or graph picture in Pol graphing works as it does in Func graphing.

Exploring and Analyzing a Polar Graph

As in Function graphing, several tools are available for exploring a Polar graph: using the free-moving cursor, tracing an equation, zooming, and drawing.

The Free-Moving Cursor

The free-moving cursor works in **Pol** graphing just as it does in **Func** graphing. The variables x and y are updated if r and θ also are updated in **PolarGC FORMT**. If **FORMT** is **CoordOn**:

- In **PolarGC FORMT**, the cursor coordinate values for r and θ are displayed.
- In **RectGC FORMT**, the cursor coordinate values for x and y are displayed.

The TRACE Feature

The **TRACE** feature lets you move the cursor along polar equations. When you begin a trace, the **TRACE** cursor is on the first selected equation at θ Min. Use \rightarrow or \leftarrow to move the cursor along an equation, increasing θ by θ Step with each keystroke. Use \uparrow or \downarrow to move between equations. The variables r , θ , x , and y are updated. If **FORMT** is **CoordOn**:

- In **PolarGC FORMT**, the cursor coordinate values for r and θ are displayed.
- In **RectGC FORMT**, the cursor coordinate values for x , y , and θ are displayed.

If you have graphed a family of curves, \downarrow or \uparrow moves through each curve before moving to the next θ function.

If the cursor moves off the display, the coordinate values at the bottom of the display continue to change appropriately.

In **Pol** graphing, automatic panning does not occur if the cursor moves off the display to the left or right.

The **QuickZoom** feature is available in **Pol** graphing. If you **TRACE** an equation and then press \square , the viewing rectangle is adjusted so that the cursor location becomes the centre of the new viewing rectangle, even if you have traced off the display.

The ZOOM Features

The ZOOM features work in **Pol** graphing as they do in **Func** graphing, except ZFIT, which adjusts the viewing rectangle in both the x and the y directions. The **Pol** GRAPH ZOOM menu is:

BOX	ZIN	ZOUT	ZSTD	ZPREV
ZFIT	ZSQR	ZTRIG		ZRCL
ZFACT	ZOOMX	ZOOMY	ZINT	

Only the x and y RANGE variables are affected. The θ RANGE variables (θ Min, θ Max, and θ Step) are not affected, except by ZSTD and ZRCL.

Drawing on a Polar Graph

The DRAW instructions work in **Pol** graphing as they do in **Func** graphing. The **Pol** GRAPH DRAW menu is:

Shade		LINE	VERT	CIRCL	DrawF
PEN	PTON	PTOFF	PTCHG	PTCHG	CLDRW
TenLn					

Note: The coordinates for DRAW instructions in **Pol** graphing are the x-coordinate and y-coordinate values of the display, just as they are in **Func** graphing.

Evaluating Equations for a Given θ

The EVAL operation evaluates currently selected polar equations for a given value of θ directly on a graph.

The eval function in a program or from the Home screen, returns a list of r values.

The MATH Features

The MATH operations work in **Pol** graphing as they do in **Func** graphing. The **Pol** GRAPH MATH menu is:

DIST	dy/dx	d/d θ	ARC	TANLN
------	-------	--------------	-----	-------

The distances calculated by DIST and ARC are distances in the rectangular coordinate plane. dy/dx and d/d θ are independent of the RectGC or PolarGC FORMT.


TANLN at a point where the derivative is undefined will draw the line, but no result is displayed or stored in Ans.

Example: Graphing a Cardioid

The polar equation $r=a+b\cos\theta$ graphs a cardioid. Graph the equation for $a=3$ and $b=5$ and find the length of the arc that defines the cardioid.

Procedure

1. Press **[2nd]** **MODE**. Select **Pol** MODE. Choose the defaults for the other modes.
2. Press **[2nd]** **[F5]** and select **FORMD**. Select **PolarGC** to show cursor coordinates r and θ .
3. Select **0(0)=**. Enter the polar equation:
 $r1=3-5\cos\theta$
4. Select **ZOOM** from the **GRAPH** menu. Select **ZSTD** from the **GRAPH ZOOM** menu to graph the equation in the standard default viewing rectangle.
5. Select **TRACE** and trace the equation.



6. To calculate the arc length from $\theta=0$ to $\theta=2\pi$, press **[2nd]** **[F5]** **[MATH]** **(ARC)**. The cursor is on the function at $r=2$ and $\theta=0$.
7. Press **[ENTER]** to mark the beginning of the arc at $\theta=0$.
8. Press and hold **[ENTER]** until you have traced the curve back to the beginning, $\theta=2\pi$ (6.2831853072). Press **[ENTER]** to mark the end of the arc.

The busy indicator displays while the arc length is calculated. The result, **ARC=34.313587101**, is displayed at the bottom of the screen.

This chapter describes how to graph parametric equations on the TI-85. Parametric graphs are completely independent of function, polar, or differential equation graphs. Before doing parametric graphing, you should be familiar with the graphing features in Chapter 4, Function Graphing.

Chapter Contents

Defining and Displaying a Parametric Graph	6-2
Exploring and Analyzing a Parametric Graph	6-4
Example: Simulating Motion	6-6

Defining and Displaying a Parametric Graph

Parametric equations have an x component and a y component, each expressed in terms of the independent variable t . They often are used to graph equations over time. Up to 99 pairs of parametric equations can be defined and graphed at one time, limited by available memory.

Steps in Defining a Parametric Graph

The steps for defining a parametric graph are the same as those for defining a function graph. Differences are noted below. Graph formats, equations, and RANGE variables in Param graphing are independent of the other graphing modes.

Setting the Graphing Mode

To graph parametric equations, you must select **Param** on the **MODE** screen.

The Param GRAPH Menu

The Param GRAPH menu is:


E(t)=	RANGE	ZOOM	TRACE	{GRAPH
MATH	DRAW	FORMT	STGDB	RCGDB
EVAL	STPIC	RCPIC		

Setting the Graph Format

Select **FORMT** to display the **FORMT** screen. **DrawLine** usually presents a more meaningful Param graph.

Displaying the Components of Parametric Equations

Select **E(t)=** from the **GRAPH** menu to display the **E(t)** editor, where you display and enter parametric equations. You can enter up to 99 pairs of equations, each defined in terms of t . If no equations are defined, **x1=** and **y1=** are displayed.



```
x1=3 cos t
y1=3 sin t
x2=4+t sin t
y2=3 sin t

TRACE RANGE ZOOM TRACE GRAPH
t x1 y1 DEL SELECT
```

Press **NOI** to access **(INS)**, **(ALL+)** and **(ALL-)**.

Deleting Parametric Equations

To delete a parametric equation, place the cursor on either component and select **DEL**. Both components are deleted. To delete a parametric equation from the **MEM DEL** menu, delete the **x1** component.

Graph Databases and Pictures

Storing or recalling a graph database or graph picture in Param graphing works as it does in Func graphing.

Defining Components of Parametric Equations

Enter or edit both the **x** and **y** components in a pair to define a parametric equation.

- The independent variable in each component must be **t**. You may select **(t)** from the menu.
- You can reference a component of a parametric equation in the expression; for example, $x_2=3 \cdot x_1$. You may select **x1** or **y1** from the menu and then type the number of the equation.

Selecting Parametric Equations

Once the parametric equations you select are graphed. To select a parametric equation, you may place the cursor on either the **x** or **y** component and select **(SELECT)**; both components are selected.

Defining the Viewing Rectangle

Select **(RANGE)** to display and change the **RANGE** variables. The values shown below are the standard defaults in **Radian MODE**.

Setting	Meaning
tMin=0	Smallest t value to evaluate
tMax=6.28318530718	Largest t value to evaluate (2π)
tStep=.13089969389957	Increment between t values ($\pi/24$)
xMin=-10	Smallest x value to display
xMax=10	Largest x value to display
xScl=1	Spacing between x tick marks
yMin=-10	Smallest y value to display
yMax=10	Largest y value to display
yScl=1	Spacing between y tick marks

Displaying the Graph

Select **(GRAPH)**, **(TRACE)**, **(EVAL)**, **(STGDB)**, or a **ZOOM**, **DRAW**, **MATH** or **PIC** operation to plot the selected parametric equations. The TI-85 evaluates both the **x** and the **y** component for each value of **t** (from **tMin** to **tMax** in intervals of **tStep**) and then plots each point. As the graph is plotted, the variables **x**, **y**, and **t** are updated.

Exploring and Analyzing ■ Parametric Graph

As in Function graphing, several tools are available for exploring a Parametric graph: using the free-moving cursor, tracing an equation, zooming, and drawing.

The Free-Moving Cursor

The free-moving cursor works in Param graphing just as it does in Func graphing. The variables x and y are updated (r and θ also are updated in PolarGC FORMAT). If FORMAT is CoordOn:

- In PolarGC FORMAT, the cursor coordinate values for r and θ are displayed.
- In RectGC FORMAT, the cursor coordinate values for x and y are displayed.

The TRACE Feature

The TRACE feature lets you move the cursor along parametric equations. When you begin a trace, the TRACE cursor is on the first selected equation at tMin. Use \leftarrow or \rightarrow to move the cursor along an equation, one tStep at a time. Use \uparrow or \downarrow to move between equations. The variables x , and y and t are updated. (r and θ are also updated in Polar GC FORMAT). If FORMAT is CoordOn:

- In PolarGC FORMAT, the cursor coordinate values for r , θ and t are displayed.
- In RectGC FORMAT, the cursor coordinate values for x , y , and t are displayed.

If you have graphed a family of curves, \uparrow or \downarrow moves through each curve before moving to the next E(t) function.

If the cursor moves off the display, the coordinate values at the bottom of the display continue to change appropriately.

In Param graphing, automatic panning does not occur if the cursor moves off the display to the left or right.

The QuickZoom feature is available in Param graphing. If you TRACE an equation and then press $\boxed{\text{ZOOM}}$, the viewing rectangle is adjusted so that the cursor location becomes the centre of the new viewing rectangle, even if you have traced off the display.

The ZOOM Features

The ZOOM features work in **Param** graphing as they do in **Func** graphing, except ZFIT, which adjusts the viewing rectangle in both the x and the y directions. The **Param** GRAPH ZOOM menu is:

BOX	ZIN	ZOUT	ZSTD	ZPREV
ZFIT	ZSQF	ZTRIG	ZDECM	ZACL
ZFACT	ZOOMX	ZOOMY	ZINT	ZSTO

Only the x (xMin, xMax, and xScl) and y (yMin, yMax, and yScl) RANGE variables are affected. The t RANGE variables (tMin, tMax, and tStep) are not affected, except for (ZSTD) and (ZACL).

Drawing on a Parametric Graph

The DRAW instructions work in **Param** graphing as they do in **Func** graphing. The coordinates for DRAW instructions are the x-coordinate, y-coordinate, and time (t) of the object. The **Param** GRAPH DRAW menu is:

Shade	LINE	VERT	CIRCL	ARC
PEN	PTON	PTOFF	PTCHG	PTDEL
TANLN				

Evaluating Equations for a Given t

EVAL evaluates currently selected parametric equations for a given value of t. It is used directly on the graph.

In a program or from the Home screen, the eval function returns a list of x and y values in the form {x1(t) y1(t) x2(t) y2(t) ...}.

The MATH Features

The MATH operations work in **Param** graphing as they do in **Func** graphing. The **Param** GRAPH MATH menu is:

DIST	dy/dx	dy/dt	dx/dt	ARC
TANLN				

The distances calculated by DIST and ARC are distances in the rectangular coordinate plane.

TANLN at a point where the derivative is undefined will draw the line, but no result is displayed and no result is stored in Ans.

Example: Simulating Motion

Graph the parametric equation that describes the position over time of a ball that has been kicked.

Problem

Graph the position of a ball kicked at an angle of 52° with an initial velocity of 40 feet per second. (Ignore air resistance.) What is the maximum height and when is it reached? How far away and when does the ball strike the ground?

If v_0 is the initial velocity and θ is the angle, then the horizontal component of the position of the ball as a function of time is described by

$$x(t) = t v_0 \cos \theta$$

The vertical component of the position of the ball as a function of time is described by

$$y(t) = -16t^2 + t v_0 \sin \theta$$

Procedure

1. Press $\left[\frac{\square}{\text{MODE}}\right]$ **MODE**. Select **Param** and **Degree** **MODE**.
2. Press $\left[\frac{\square}{\text{FORMAT}}\right]$. Select **FORMAT**. Select **DrawLine** and **RectGC**.
3. Select $\left[\frac{\square}{\text{EQ}}\right]$ from the **GRAPH** menu. Enter the expressions to define the parametric equation in terms of t .
 $xt1=40t \cos 52$
 $yt1=40t \sin 52-16t^2$
3. Select **RANGE**. Set the **RANGE** variables.

$tMin=0$	$xMin=-5$	$yMin=-5$
$tMax=2.5$	$xMax=50$	$yMax=20$
$tStep=.02$	$xScl=5$	$yScl=5$
4. Select **TRACE** to graph the position of the ball as a function of time and to explore the graph. The values for x , y , and t are displayed at the bottom of the screen. These values change as you trace the graph.

Move the cursor along the path of the ball to investigate these values.

Chapter 7: Differential Equation Graphing

This chapter describes how to solve numerically and graph differential equations on the TI-85. DfEq graphs are completely independent of function, polar, or parametric graphs. Before doing DfEq graphing, you should be familiar with the graphing features in Chapter 4, Function Graphing.

Chapter Contents	Defining a DfEq Graph	7-2
	Displaying and Exploring a DfEq Graph	7-5
	Example: Transforming a Differential Equation	7-7
	Example: Solving a Differential Equation	7-8
	Example: Linear Harmonic Oscillator	7-9

Defining a DifEq Graph

DifEq graphing can graph a system of up to nine first-order differential equations.

Steps In Defining a Graph

The steps for defining a differential equation graph are similar to those for defining a function graph, but also include setting initial conditions and selecting the axes. To graph any differential equation above first order, transform it to an equivalent system of first-order differential equations. Each equation in the system requires an initial condition.

Setting the Graphing Mode

To graph a differential equation, you must select **DifEq** on the **MODE** screen.

The DifEq GRAPH

The DifEq GRAPH menu is:


Q'1=	RANGE	INITC	AXES	GRAPH
FORMAT	DRAW	ZOOM	TRACE	EVAL
STGDB	RCGDB	STPIC	RCPIC	

Setting the Graph Format

Select **FORMAT** to display and change the **FORMAT** options: coordinate, axes, grid, and label display.

Displaying the Equations

Select **Q'(t)=** from the **GRAPH** menu to display the **Q'(t)** editor, where you display and enter differential equations. You can enter up to 9 equations. The independent variable in **DifEq** is **t**. If no equations are defined, **Q'1=** is displayed.



Displaying and Selecting the Axes-

You can specify the x and y axes (as t , Q , Q' , Q_{n-1} , or Q'_0) of the graph in order to see the planes of the solution. Note that if the axes are t and Q_n (or Q'_n) solution is plotted, regardless of which equations are selected. Select **AXES** from the **GRAPH** menu to display the **AXES** editor.



Defining the Viewing Rectangle

Select **RANGE** to display and change the **RANGE** variables. The values shown below are the standard defaults in **Radian MODE**. x and y settings correspond to the variables selected as the axes.

Setting	Meaning
tMin=0	Smallest t value to solve
tMax=6.28318530718	Largest t value to solve (2π)
tStep=.13089969389957	TRACE increment between t values ($\pi/24$)
tPlot=0	Point at which plotting usually begins
xMin=-10	Smallest x value to display
xMax=10	Largest x value to display
xScl=1	Spacing between x tick marks
yMin=-10	Smallest y value to display
yMax=10	Largest y value to display
yScl=1	Spacing between y tick marks
diffTol=.001	Tolerance to help select the step size for solving. diffTol must be > 0.

Displaying and Exploring a DfEq Graph

As in Func graphing, several tools are available for exploring a DfEq graph: using the free-moving cursor, tracing an equation, zooming, and drawing.

Displaying a Graph

Select (GRAPH), (TRACE), (EVAL), (STGDB), or a ZOOM, DRAW, or PIC operation to plot the selected differential equations. The TI-85 solves each equation from t_{Min} to t_{Max} . If t is not an axis, it plots each point beginning at t_{Plot} ; otherwise it begins at t_{Min} . As a graph is plotted, the variables x , y , t , and $Q1a$ are updated.

t_{Step} affects the TRACE resolution and appearance of the graph, but not the accuracy of the TRACE cursor. t_{Step} does not determine the step size for solving the algorithm. (Range-Kernel) t_{Step} is determined by the step size. If t_{Step} is not a constant, $t_{\text{Step}} = x_{\text{Max}} - x_{\text{Min}}$ (128 iterations plotting) time without increasing accuracy.

The Free-Moving Cursor

The free-moving cursor works in DfEq graphing as it does in Func graphing. The cursor coordinate values for x and y are displayed and the variables are updated.

The TRACE Feature

The TRACE feature lets you press \rightarrow to move the cursor along the equation one t_{Step} at a time. When you begin a TRACE, the TRACE cursor is on the first selected equation at or near t_{Plot} (or t_{Min} if t is an axis) and the coordinate values of x , y , and t are displayed at the bottom of the screen. \leftarrow returns the cursor to the beginning point on the same equation.

As you trace an equation, the values of x , y , and t are updated and displayed. x and y are calculated from t .

If the cursor moves off the screen, the coordinate values of x , y , and t displayed at the bottom of the screen continue to change appropriately.

Automatic panning does not occur in DfEq graphing if the cursor moves off the screen to the left or right.

The QuickZoom feature is available in DfEq graphing. If you TRACE an equation and then press \rightarrow , the viewing rectangle is adjusted so that the cursor location becomes the centre of the new viewing rectangle, even if you had traced off the screen.

The ZOOM Features

The ZOOM features work in DifEq graphing as they do in Func graphing, except ZFIT, which adjusts the viewing rectangle in both the x and y directions. The DifEq GRAPH ZOOM menu is:

BOX	ZIN	ZOUT	ZSTD	ZPREV
ZFIT	ZSQR	ZTRIG	ZDECM	ZRCL
ZFACT	ZOOMX	ZOOMY	ZINT	ZSTO

Only the x (xMinZ, xMax, and xScl) and y (yMin, yMax, and yScl) RANGE variables are affected. The t RANGE variables (tMin, tMax, and tplot) are not affected, except for ZSTD and ZRCL. You may want to change the t RANGE variables to ensure that sufficient points are plotted. ZSTD sets diffTol=.001 and t and Q as axes.

Drawing on a DifEq Graph

The DRAW instructions work in DifEq graphing as they do in Func graphing. The coordinates for DRAW instructions are the x-coordinate and y-coordinate values of the display. The DifEq GRAPH DRAW menu is:

Shade	LINE	VERT	CIRCL	DrawF
PEN	PTON	PTOFF	PTCHG	CLDRW
TanLn				

The Math Features

The Math features are not available in DifEq graphing.

Evaluating

Equations for a
Given t

EVAL evaluates currently selected differential equations for a given value of t, tMin to tMax. It can be used directly on the graph. In a program, eval returns a list of Q values.

Example: Transforming a Differential Equation

To use differential equations on the TI-85, you must transform the differential equation into a system of first-order differential equations. In general, an n th-order differential equation can be transformed to an equivalent system of n first-order differential equations.

Problem Convert $y^{(4)} - y = e^{-t}$ to an equivalent system of four first-order differential equations.

Procedure Define the variables:

Q1	=	y
Q2	=	y'
Q3	=	y''
...		
Q9	=	$y^{(4)}$

Therefore, by differentiation

Q'1	=	y'
Q'2	=	y''
Q'3	=	y'''
...		
Q'9	=	$y^{(4)}$

You can use the variable definitions above to convert the differential equation to a system of first-order equations (with no derivatives on the right-hand side of the system).

1. From the second chart, $Q'1=y'$ and from the first chart, $y=Q2$. Therefore, by substitution, $Q'1=Q2$.
2. Similarly, $Q'2=y''=Q3$ and $Q'3=y'''=Q4$.
3. From the original differential equation, $Q'4=y^{(4)} - e^{-t} + y = e^{-t} + Q1$. (In differential equations on the TI-85, t is the independent variable.)
4. Press $\boxed{\text{MODE}}$ and select **DifEq**.
5. Press $\boxed{\text{INPUT}}$ $\langle Y(t) \rangle$. Enter the equations.




(Continued
on next page)

Example: Solving a Differential Equation

Consider the differential equation $y'' - y = e^x$ entered on the previous page. Solve the initial value problem by setting the RANGE variables, entering initial conditions: $y(0)=3$, $y'(0)=-5.25$, $y''(0)=7.5$, $y'''(0)=-5.75$, and graphing the differential equation.

Procedure

1. Use (SELECT) to turn off Q'2, Q'3, and Q'4.
2. Select (RANGE). Set the RANGE variables to:

tMin=0	xMin=0	yMin=-4
tMax=10	xMax=10	yMax=4
tStep=.01	xSci=1	ySci=1
tPlot=0		diffTol=.001
3. Select (INITC). Enter the initial conditions.
Q11=3
Q12=-5.25
Q13=7.5
Q14=-5.75
4. Select (AXES). Set the axes to $x=t$ and $y=Q$.
5. Select (TRACE) to graph and to explore graphically the solution to the differential equation.
6. From analytical methods, we know that the solution to this differential equation is $y=(5-(1/4)x)e^{-x}-2\cos x$. Select DrawF from the (DRAW) menu. Or, the Home screen calculator: $\text{DrawF}((5-(1/4)x)e^{-x}-2\cos x$

7. Note that the graphic solution is not valid for $t > 8$. Change diffTol to .00001 and repeat step 6.

Example: Linear Harmonic Oscillator

Plot the solution to the linear harmonic oscillator second-order differential equation: $y'' + y = 0$ with initial conditions $y(0) = 0$ and $y'(0) = 5.0$.

Procedure

Transform this second-order differential equation to the equivalent system of first-order equations:

Let $Q1 = y$ and let $Q2 = y'$. By substitution, $Q'1 = Q2$ and $Q'2 = -Q1$

1. Press **[2d]** (MODE). Select **DIFEq** mode. Choose the defaults for the other modes.

2. Press **[F5]** and select **(Q'())**. Enter the expressions to define the equation in terms of t

$$Q'1 = Q2$$

$$Q'2 = -Q1$$

3. Use **(SELECT)** to unselect **Q'2**.

4. Use **(DELT)** to delete **Q'3** and **Q'4**.

5. Select **(RANGE)**. Set the values to:

$$tMin = 0$$

$$xMin = -10$$

$$yMin = -10$$

$$tMax = 2\pi$$

$$xMax = 10$$

$$yMax = 10$$

$$tStep = \pi/24$$

$$xSci = 2$$

$$ySci = 5$$

$$tPlot = 0$$

$$diffToI = .001$$

6. Select **(INITC)**. Enter the initial conditions

$$Q1 = 0$$

$$Q2 = 5$$


Note: All four initial conditions from the earlier problem remain if you have not deleted them through **MEM DELET**. The square dots next to **Q1** and **Q2** indicate that they are the initial conditions required.

7. Select **(AXES)**. Set the axes to $x = t$ and $y = Q$.

(Continued on following page.)

Example: Linear Harmonic Oscillator (Continued)

8. Select **TRACE** to graph the equation and begin tracing. The **TRACE** values are the numerical solutions to the differential equation.



9. Select **DrawF** from the **GRAPH DRAW** menu. Use it to overlay the function $5 \sin x$ and visually compare it to the solution of the differential equation.
DrawF 5 sin x
10. Select **AXES** from the **GRAPH** menu. Define $x=Q1$ and $y=Q2$.
11. Select **ZSQR** from the **GRAPH ZOOM** menu. This is the phase plane of the solution.
12. Select **RANGE** from the **GRAPH** menu. Set **tPlot**= π to begin the plot at π .
13. Select **GRAPH**. Notice that it plots only half of the equation in the phase plane.

Chapter 8: Constants and Conversions

This chapter describes how to use built-in constants, user-defined constants, and built-in conversions on the TI-85.


Chapter Contents	The CONS (Constants) Menu	8-2
	Using Constants	8-3
	Creating and Editing User-Defined Constants	8-4
	The CONV (Conversion) Menu	8-6
	Using Conversions	8-8

The CONS (Constants) Menu

The CONS menu accesses built-in and user-defined constants for use in expressions. You also can create and edit user-defined constants through the CONS menu.

The CONS Menu

When you press  (CONS), the menu keys are labelled with the constants menu.






BLTIN	EDIT	USER				
Item	Accesses					
BLTIN	Menu of names of the built-in constants.					
	Na	k	Cc	ec	Rc	
	Gc		Me	Mp	Mn	
	$\mu 0$	$\epsilon 0$	h	c	u	
EDIT	The constant editor, where you create or edit user-defined constants (page 8-4).					
USER	Menu of user-defined constants (page 8-8).					

and e

π and e , natural log, are stored as constants in the TI-85. π , 3.1415926635898, is accessible from the keyboard. e , 2.718281828459, is accessible from the keyboard as lowercase e .

Built-In Constants

The TI-85 has 16 built-in constants that you can select from the CONS BUILT IN menu or type from the keyboard and CHAR GREEK menu.

	Avogadro's number	6.0221367E23 mole ⁻¹
k	Boltzman's 	1.380658E-23 J/K
Cc	Coulomb constant	8.9875517873688E9 N m ² /C ²
ec	Electron charge	1.6021773E-19 C
Rc	Gas constant	8.31451 J/mole K
Gc	Gravitational constant	6.67259E-11 N m ² /kg ²
	Earth acceleration due to gravity	9.80665 m/sec ²
	Mass of an electron	9.1093897E-31 kg
Mp	Mass of an proton	1.6726231E-27 kg
Mn	Mass of an neutron	1.6749286E-27 kg
$\mu 0$	Permeability of a vacuum	1.2566370614359E-6 N/A ²
$\epsilon 0$	Permittivity of a vacuum	8.8541878176204E-12 F/m
h	Planck's constant	6.6260755E-34 J sec
c	Speed of light	299,792,458 m/sec
u	Atomic  unit	1.6605402E-27 g

Using Constants

The values for built-in constants cannot be changed, and the values for user-defined constants can be changed only in the CONSTANT editor. Otherwise, constants are used like variables in expressions.

Entering and Editing Constants

User-defined constants can be entered and edited only in the constant editor (see page 8-4). **[END]** and **[DEL]** are not used to store values to constants. Built-in constants cannot be edited.

Using a Constant in an Expression

To use a constant in an expression, you may:

- Type the name of the built-in or user-defined constant (case-sensitive).
- Select the name of a user-defined constant from the VARS CONS screen.
- Select the name from the CONS USER menu or the CONS BLTIN menu.

Example

Calculate the time in seconds for light to travel from the sun to Mercury, a distance of 57,924,000 km.

57924000	×	1000	:
OK	→	BLTIN	
OK	→	57924000x1000/c	
ENTER			193.213666503

Creating and Editing User-Defined Constants

On the TI-85 you can create real or complex user-defined constants. Use the CONSTANT editor to create a new user-defined constant, change the value of an existing user-defined constant, or delete a user-defined constant.

Defining a New User-Defined Constant

1. Press **[2d]** (CONS) to display the CONS menu.
2. Select **[EDIT]** to display the constant editor. The menu keys are labelled with the names of the existing user-defined constants in alphabetical order.



3. Type the name of the new constant. It must follow the rules for naming variables (Chapter 2). The keyboard is set in ALPHA-lock. You cannot move to the value until you have entered a name.
4. Press **[ENTER]**. The value is blank, and the menu keys are labelled:
PREV **NEXT** **DELET**
5. Enter the real or complex value of the new constant (which can be an expression). The new constant is created and the value stored.

Note: If you press a key that displays a menu, the constant editor menu moves to the seventh line (if it is not already there), and the selected menu is displayed on the eighth line.

Displaying an Existing User-Defined Constant

1. Select (EDIT) from the CONS menu. The menu keys are labelled with the names of the existing user-defined constants in alphabetical order.
2. Enter the name of the constant to change in one of two ways:
 - Select the name from the menu.
 - Type the name, up to eight characters (case-sensitive). The keyboard is set in ALPHA-lock.
3. Press **ENTER**. The value of the constant is displayed, and the menu keys are labelled:
PREV **NEXT** **DELET**
 - To display the previous constant (alphabetically) and value, select (PREV).
 - To display the next constant (alphabetically) and value, select (NEXT).

Editing an Existing User-Defined Constant

1. Display the constant as described above.
2. Enter the new real or complex value (which can be an expression).

Deleting a User-Defined Constant

You can delete a user-defined constant in one of two ways:

- Through the MEM-DELET menu (Chapter 18).
- Through the constant editor. Select (DELET) when the constant is displayed as described above. The constant is deleted immediately, and the next constant (alphabetically) is displayed.

The CONV (Conversions) Menu

The TI-85 has built-in conversion functions for the most commonly used conversions. The conversion functions, which are accessed from the CONV menu, convert between any two defined units within the same conversion type. Press **2nd** to move around the menu.

The CONV Menu

When you press **2nd** (CONV), the menu keys are labelled with the conversion types. When you select a type, the menu keys are labelled with the units for that type.

Item	Accesses
LNGLH	Menu of units of length. mm cm m in ft yd km mile nmile ft-yr mil Ang fmi rod fath (nmile=nautical mile, ft-yr=light year, Ang=Angstrom, fath=fathom)
AREA	Menu of units of area. ft ² m ² mi ² km ² mi² in ² cm ² yd ² ha mi² (ha=hectare)
VOL	Menu of units of volume. liter gal qt pt oz cm ³ in ³ fl ³ m ³ cup tsp tbsp ml galUK ozUK
TIME	Menu of units of time. sec mn hr day yr week ms us ns ns (ms=millisecond, us =microsecond, ns=nanosecond)
TEMP	Menu of units of temperature. °C °F °K °R

The CONV (Conversions) Menu (Continued)

Item	Accesses
MASS	Menu of units of mass. gm kg lb amu slug ton mton (ton=2000 lb, mton=metric ton, amu=atomic mass unit.)
FORCE	Menu of units of force. N dyne tonf kgf lbf (tonf=tons force, kgf= kg force, lbf=pounds force)
PRESS	Menu of units of pressure. atm bar N/m ² lb/in ² mmHg mmH ² inHg inH ₂ O
ENRGY	Menu of units of energy. J cal Btu ft-lb kw-hr eV erg l-atm (ft-lb=foot-pound, eV=electron-volt)
POWER	Menu of units of power. hp W ftlb/s cal/s Btu/m (W=watts, ftlb/s=foot-pound per second, Btu/m=Btu per minute)
SPEED	Menu des unités de vitesse. ft/s m/s mi/hr km/hr knot

Note: mmHg is copied to the cursor location as mmH₂O. (Btu/m is copied as Btu/min.)

Values of conversion factors generally use internationally defined values.

Using Conversions

The functions to convert between units on the TI-85 must be accessed from the CONV menu. Units are grouped by conversion types. You can convert between any pair of units within a conversion type.

Using a Conversion Function in an Expression

You cannot type the name of a conversion function in an expression or obtain it from the catalog. To enter the name of a conversion function in an expression, you must "build" the name of the function through the CONV menu. The name consists of three parts: the "from" unit, the conversion symbol, and the "to" unit.

1. Enter the real value to be converted (which can be an expression).
2. Press **[2nd]** (CONV) to display the conversion menu. The menu keys are labelled with the types.
3. Select the type of conversion. The menu keys are labelled with the units within that conversion type in alphabetical order.
4. Select the "from" unit. The name of the "from" unit and the conversion symbol \rightarrow are copied to the cursor location.
5. Select the "to" unit. The name of the "to" unit is copied to the value from unit \rightarrow to unit.

For example, $2 \text{ in} \rightarrow \text{mm}$ returns 50.8.

The "from" and "to" unit must both be from the same conversion type. You cannot, for example, convert ft to gal.

Once a conversion function has been entered, you can edit the alphabetic characters of the "from" unit and the "to" unit, but the special characters $^$, 2 , 3 , $^{\circ}$, $^{\circ}$, $^{\circ}$, $^{\circ}$, $^{\circ}$, $^{\circ}$, and $^{\circ}$ are accessible only through the CONV menu.

To convert values expressed as rates, you must use parentheses. For example, to convert 12 miles in 7 hours to meters per second, enter $(12/7) \text{ mi/hr} \rightarrow \text{m/s}$ or $12 \text{ miles} \rightarrow \text{m/7 hr} \rightarrow \text{sec}$, which returns .766354285714.

Chapter 9: Strings and Characters

This chapter describes strings and how to manipulate them. It also describes the miscellaneous characters, Greek letters, and accented international letters available through menus for use in display text and variable names.

Chapter Contents	Entering and Using Strings	9-2
	The STRING String Menu	9-4
	The CHAR Character Menu	9-6
	Accessing Miscellaneous and Greek Characters	9-7
	Accessing International Characters	9-8

Entering and Using Strings

On the TI-85, you can enter and use strings. Strings are used primarily in programming to display and enter characters. Strings are entered, stored, and displayed directly on a command line.

Strings

A string is a sequence of characters that is enclosed between quotation (") marks. Strings are not evaluated. To evaluate a string, it must first be converted to an equation using the **St→Eq** instruction (page 9-5).

Strings on the TI-85 have two primary applications.

- They define text for display in a program.
- They accept input from the keyboard in a program.

Entering a String

1. Press **[2d]** **[STNG]** to display the STNG menu.

sub	length	Eq→St	St→Eq
-----	--------	-------	-------
2. Select **(1)** to indicate the beginning of the string.
3. Enter the characters of the string. Press **[Alpha]** or **[2d]** (alpha, as appropriate).
4. Select **(2)** from the STNG menu to indicate the end of the string. This is not necessary at the end of a command or preceding the **[PRTN]** key.

The computed expression is

"stng"

For example, "Hello"

String Variables	On the TI-83, strings can be stored to and represented by variables.
Storing a String	To store a string, press STO following the string and then enter the name of the variable to which to store the string. The completed instruction is: "characters" →string_name For example, "Hello" →GREETING .
Displaying a String Variable	To display the contents of a string variable, enter the name of the string on a blank line on the Home screen and press ENTER .

The STRNG (String) Menu

The STRNG menu displays additional functions and instructions to manipulate strings. When you select from the STRNG menu, the character or the name of the function or instruction is copied to the cursor location.

The STRNG Menu

When you press **2nd** [STRNG], the menu keys are labelled with the string menu.

* sub lngth Eq>St St>Eq

The * character is used to enter strings (page 9-3).

Finding a Subset of a String

sub (subset) returns a string created from a subset of a string. **sub** has three arguments: a string or the name of a string variable, the beginning position (1, 2, 3, etc.) of the subset, and the number of characters (including blanks) in the subset. When the expression is evaluated, the subset of the string is returned as a string.

sub: string, begin, length)

For example, if **STRING** contains "The answer is 33", then **sub(STRING,16,2)** returns "33"

Finding the Length of a String

lngth (length) returns the number of characters of a string. The string can be a variable containing a string, or you can enter the string directly. When the expression is evaluated, the number of characters (including blanks) in the string is returned. The quotation marks are not included in the length.

lngth "string" or **lngth** string_name

For example, if **STRING** contains "The answer is 33", then **lngth STRING** returns 16.

Concatenating Strings

To concatenate strings, use the + function.

For example, "St"+"ring" returns "String".

Converting an Equation to a String

Eq>St (equation to string) is used primarily in programming to convert an equation to a string. It has two arguments: the name of the variable containing the equation and the name of the variable to which to store the string. When the instruction is executed, the equation in the equation variable is stored as a string in the string variable.

Eq>St{equation_name, string_name}

The **Disp** programming instruction displays the string in the string variable.

Converting a String to an Equation

St>Eq (string to equation) is used primarily in programming to convert a string entered using the **InpSt** programming instruction into an equation to use in an expression. It has two arguments: the name of the variable containing the string and the name of the variable to which to store the equation. When the instruction is executed, the string in the string variable is converted to an equation and stored in the equation variable.

St>Eq{string_name, equation_name}

Program Example

In a program, the following commands allow the user to enter a function to graph during execution.

```
:InpSt "Enter y1: ",STR:St>Eq(STR,y1)
```

The CHAR (Character) Menu

The CHAR menu accesses additional characters to use in variable names and display text.

The CHAR Menu

When you press **CHAR** (F2), the menu keys are labelled with the CHAR character menu.

MISC	GREEK	INTL		
Item	Accesses			
MISC	Menu of miscellaneous characters (page 9-7)			
?	#	&	%	^
!	@	\$	-	
~	~	~	~	~
GREEK	Menu of Greek characters (page 9-7)			
α	β	γ	Δ	δ
ε	θ	λ	μ	ν
Σ	~	τ	φ	ψ
INTL	Menu of accent marks to create international characters (page 9-8)			
ˆ	˜	˘	˙	˚

Accessing Miscellaneous and Greek Characters

The CHAR MISC and CHAR GREEK menus display miscellaneous characters and the most commonly used Greek characters for use in variable names, strings, and display text. When you select an item from the MISC or GREEK menu, the character is copied to the cursor

location.

Using Miscellaneous

Characters

To use a miscellaneous character in a name or text:

1. Press **[2nd]** **[CHAR]** to display the CHAR menu.
2. Select **(MISC)**. The menu keys are labelled with the first five items of the miscellaneous character menu. Press **(F5)** to move around the menu.

?	^	Δ	%	"
!	□	Σ	-	
£	N	Δ	Ç	Ç

3. Select the character, which is copied to the cursor location. You can continue to select characters from this menu.

Note: N, n, Ç and ç are the only miscellaneous characters that are valid in a variable name. !, %, and ' are functions.

Using Greek

Characters

To use a Greek character in a name, expression, or text:

1. Press **[2nd]** **[CHAR]** to display the CHAR menu.
2. Select **(GREEK)**. The menu keys are labelled with the first five items of the Greek letter menu. Press **(F5)** to move around the menu.

α	β	γ	Δ	δ
ε	ϵ	λ	μ	ρ
Σ	σ	τ	θ	Ω

3. Select the character, which is copied to the cursor location. You can continue to select characters from this menu.

Note: π is on the keyboard. On the TI-85, π is not a character and is not valid in variable names. Δ is implied multiplication.

Accessing International Characters

The CHAR INTL menu item accesses accent marks that can be combined with uppercase or lowercase vowels to create international characters for use in variable names and display text.

Using International Characters in an Expression

To use an international character in a name, expression, or text:

1. Press **[2nd]** (CHAR) to display the CHAR menu.
2. Select (INTL). The menu keys are labelled with the accent marks.
3. Use the menu keys to select an accent mark.
4. The keyboard is automatically set in ALPHA-lock (or alpha-lock if you manually set it for alpha or alpha-lock). To change to alpha-lock, press **[2nd]** (alpha). Press the key for the vowel.

The character that is copied to the cursor location includes the accent mark; for example, **ä**, **Å** or **å**. The keyboard remains in ALPHA-lock or alpha-lock.

Chapter 10: Number Bases

This chapter describes functions, instructions, and designators to enter and use numbers in binary, hexadecimal, octal, or decimal number bases on the TI-85.

Chapter Contents	Using Number Bases	10-2
	The BASE Number Base Menu	10-3
	Using the Number Bases	10-4
	Accessing Hex Digits	10-5
	Displaying Results in Another Number Base	10-6
	Using Boolean Operators	10-7
	Manipulating Number Base Digits	10-8

Using Number Bases

You can enter and display numbers on the TI-85 in binary, hexadecimal, octal, or decimal number base.

Number Bases

The **MODE** number base setting (Chapter 1) controls how an entered number is interpreted and how results are displayed on the Home screen. However, you can enter numbers in any number base using number base designators, and you can display the result on the Home screen in any number base using number base conversions.

All numbers are stored internally as decimal. If you perform an operation in a **MODE** setting other than **Dec** on the TI-85, performance is degraded, preventing efficient calculations and expression. For example, in Hex **MODE** $1/3 \div 7$ returns $7h \cdot 1$ divided by 3, truncated to 0, and then added to 7).

Number Base Ranges

Binary, octal, and hexadecimal numbers on the TI-85 are defined in the following ranges:

TYPE	High Value Low Value	Decimal Equivalent
Binary	0111 1111 1111 1111b	32,767
	1000 0000 0000 0000b	-32,767
Octal	2657 1420 0000 7777o	99,999,999,999,999
	5120 6357 4134 0001o	-99,999,999,999,999
Hexadecimal	0000 5AF3 107A 3FFFh	99,999,999,999,999
	FFFF A60C EF85 C001h	-99,999,999,999,999

One's and Two's Complements

To obtain the one's complement of a binary number, enter the **not** function (page 10-7) before the number. For example, **not 111100001111** in **Bin** **MODE** returns **1111000011110000b**.

To obtain the two's complement of a binary number, press **[+/-]** before entering the number. For example, **+/-111100001111** in **Bin** **MODE** returns **1111000011110001**.

The BASE (Number Base) Menu

The BASE menu accesses characters, designators, functions, and instructions to use with numbers in binary, hexadecimal, and octal number bases, in addition to decimal number base.

The BASE Menu

When you press **20** [BASE], the menu keys are labelled with the number base menu

A-F	TYPE	CONV	BOOL	BIT
Item	Accesses			
A-F	Hexadecimal characters (page 10-5).			
	A	B	C	D
	E	F		
TYPE	Number base designators (page 10-4).			
	b	h	o	█
CONV	Display conversion instructions (page 10-6).			
	►Bin	►Hex	►Oct	►Dec
BOOL	Boolean operators (page 10-7).			
	and	or	xor	not
BIT	Bit-manipulation functions (page 10-8).			
	rolR	rolL	shftR	shftL

Designating Number Bases

The BASE TYPE menu accesses the number base designators. You can enter a number in any number base using the number BASE designators: b (binary), h (hexadecimal), o (octal), or d (decimal). They must be entered from the BASE TYPE menu and cannot be typed from the keyboard.

Designating the Base of a Number

In an expression, you can enter a number in any number base, regardless of MODE. Enter the number, followed by the base designator.

1. Enter the number.
2. Press **2nd** [BASE] to display the number base menu.
3. Select (TYPE). The menu keys are labelled with the number base designators.

bhod
4. Select the type of number base.
The designator is copied to the cursor location.
5. Continue entering the expression.

Example of Number Base Entry

Set Dec (default)	10b+10	12
	10h+10	26
Set Bin MODE	10h+10	10010b
	10d+10	1100b
Set Oct MODE	10b+10	12o
	10d+10	22o
Set Hex MODE	10b+10	1Ah
	10d+10	1Ah

Accessing Hex Digits

The BASE A-F menu accesses the hexadecimal digits A to F, which are special characters on the TI-85. They must be entered from the BASE A-F menu and cannot be typed from the keyboard. The hexadecimal digits 0 to 9 can be typed from the keyboard.

Entering Hexadecimal Digits

To enter a hexadecimal number, type the digits 0 to 9 from the keyboard, just as you would for a decimal number. If one of the digits A to F is required:

1. Press **2nd** [BASE] to display the number base menu.
2. Select (A-F). The menu keys are labelled with the hexadecimal characters. Notice that they are slightly different from the letters A to F.
 - If you are on the Home screen, the menu keys are labelled:

A				
B	C	D	E	F

To enter A, press **2nd** [M1].

- If you are in an editor, the menu keys are labelled:

A-B	C	D	E	F
-----	---	---	---	---

To enter A or B, press **2nd** and the menu keys are labelled:

A	B	C	D	E-F
---	---	---	---	-----

3. Press the menu key associated with the character. The hexadecimal character is copied to the cursor location.
4. Continue entering the number. You may continue to select characters from this menu.

Note: If the MODE is not Hex, you must enter the h designator, even if the number contains a special hexadecimal character.

Displaying Results in Another Number Base

The **BASE CONV** menu accesses display conversion instructions. They are valid only at the end of a command and control how results are displayed, regardless of **MODE** setting. The expression is interpreted based on the **MODE** base setting. In all but **►Dec**, the result is truncated to an integer.

The **BASE CONV** Menu

When you select **(CONV)** from the **BASE** menu, the menu keys are labelled with the base conversion menu.

►Bin **►Hex** **►Oct** **►Dec**

The **►Bin** instruction

►Bin (display as binary) displays a real result in binary number base, including the **b** suffix. (Results outside the binary range are displayed according to the base **MODE**.)
result **►Bin** (Results outside the binary range are displayed according to the base **MODE**.)

The **►Hex** instruction

►Hex (display as hexadecimal) displays a real result in hexadecimal number base, including the **h** suffix.
result **►Hex**

The **►Oct** instruction

►Oct (display as octal) displays a real result in octal number base, including the **o** suffix.
result **►Oct**

The **►Dec** instruction

►Dec (display as decimal) displays a real result in decimal number base, including the **suffix** in **Bin**, **Hex**, or **Oct** **MODE**.
result **►Dec**

Example of Number Base Display

In **Dec** **MODE**, solve $10b + Fh + 10o + 10$, then increment by one and display in other number bases.

Set Dec MODE	$10b + Fh + 10o + 10$	35
binary display	Ans+1 ►Bin	100100b
Hex display	Ans+1 ►Hex	25h
Octal display	Ans+1 ►Oct	46o
Decimal display (current MODE)	Ans+1	39

Using Boolean Operators

The **BASE BOOL** menu accesses Boolean operators, which are functions that compare two arguments bit by bit.

The **BASE BOOL**
Menu

When you select **BOOL** from the **BASE** menu, the menu keys are labelled with the Boolean operators.

and **or** **xor** **not**

The Boolean
Operators **and**,
or, and **xor**

The operators **and**, **or**, and **xor** (exclusive or) require two real arguments (which can be expressions),
value and value

The Boolean
Operator **not**

The operator **not** requires one real argument (which can be an expression),
not value

Results

When the expression is evaluated, the arguments are converted to hexadecimal integers and the corresponding bits of the arguments are compared. The results are returned according to this table:

First argument	Second argument	and	or	xor	not (arg1)
1	1	1	1	0	0
1	0	0	1	1	0
0	1	0	1	1	1
0	0	0	0	0	1

The result is displayed according to the current **MODE** setting. For example:

- In **Bin MODE**, **101 and 110** returns **100b**.
- In **Hex MODE**, **5 and 6** returns **4h**.

Manipulating Number Digits

The **BASE BIT** menu accesses functions that manipulate bits in number base digits. These functions are valid in **Bin**, **Oct**, and **Hex MODE**.

The **BASE BIT** Menu

When you select **BIT** from the **BASE** menu, the menu keys are labelled with the bit manipulation functions.

rotR **rotL** **shR** **shL**

Note: Both the argument and the result must be within defined number ranges (page 10-2). Rotate and shift operates on 16 base digits. It is possible, especially if the argument is not entered in binary, to overflow on these calculations.

The Functions

rotR (rotate to the right) and **rotL** (rotate to the left) take one real argument (which can be an expression).

When the expression is evaluated, the argument is truncated to an integer, converted to the current base **MODE**, and the bits rotated.

rotR value or **rotL** value

For example, in **Bin MODE**, **rotL 0000111100001111** returns **11110000111100**.

In **Hex MODE**, **rotR A6** (1010 0110) returns **59** (0101 0011).

The Shift Functions

shR (shift to the right) and **shL** (shift to the left) take one real argument (which can be an expression).

When the expression is evaluated, the argument is truncated to an integer, converted to the current base **MODE**, and the bits shifted.

shL value or **shR** value

For example, in **Bin MODE**, **shR 0000111100001111** returns **111100001111**.

In **Oct MODE**, **shL 5** (101) returns **120** (001 010).

Chapter 11: Complex Numbers

This chapter describes how to enter and use complex numbers, describing additional functions and instructions to use with complex numbers on the TI-85.

Chapter Contents	Entering and Using Complex Numbers	11-2
	The CPLX (Complex Number) Menu	11-3

Entering and Using Complex Numbers

Complex numbers begin and end with parentheses, and have two elements separated by either a comma (rectangular format) or an angle symbol (polar format).

Complex Numbers

A complex number has two components. On the TI-85, the complex number $a+bi$ is entered as (a,b). In this guidebook, this is expressed as (real/mag) in rectangular format or (magnitude/angle) in polar format.

Lists, matrices, and vectors can have complex elements.

Entering Complex Numbers

Complex numbers are stored in rectangular format, but you can enter a complex number in rectangular or polar format, regardless of the format specified by the MODE setting. The separators, which are entered from the keyboard, determine the format. The components can be real numbers or expressions that evaluate to real numbers; the expression is evaluated when the command is executed.

Complex Number Variables

On the TI-85, complex numbers can be stored to and represented by variables.

Complex Results

Complex numbers in results, including list, matrix, and vector elements, are displayed in the format (rectangular or polar) specified by the MODE setting or by a display conversion instruction (page 11-4):

(real/mag) or (magnitude/angle)

For example, in **PolarC** and **Degree** MODE, (2,1)-(1 \angle 45) returns (1.32585429614 \angle 12.7843896828).

Using a Complex Number in an Expression

To use a complex number in an expression, you may:

- Type the complex number directly.
- Type the name of the complex-number variable (case-sensitive).
- Select the name from the VARS CPLX screen.

The CPLX (Complex Number) Menu

The CPLX menu accesses additional functions and instructions to use with complex numbers. Press $\boxed{\text{CPLX}}$ to move around the menu. When you select from the CPLX menu, the name of the function or instruction is copied to the cursor location. These examples assume Radian MODE.

The CPLX Menu

When you press $\boxed{\text{CPLX}}$, the menu keys are labelled with the first five items of the complex menu.

$\boxed{\text{conj}}$ $\boxed{\text{real}}$ $\boxed{\text{imag}}$ $\boxed{\text{mag}}$ $\boxed{\text{angle}}$
• Rec • Pol

Lists are valid arguments for all of these functions and instructions, returning a list of results calculated on an element-by-element basis.

The conj Function

$\boxed{\text{conj}}$ (conjugate) returns the complex conjugate of a complex number or list.

$\boxed{\text{conj}}$ (real,imag) returns (real,-imag) in RectC MODE.

$\boxed{\text{conj}}$ (magnitude \angle angle) returns (magnitude \angle -angle) in PolarC MODE.

For example, $\boxed{\text{conj}}$ (3,4) returns (3,-4) or (5 \angle -92.7295218002).

The real Function

$\boxed{\text{real}}$ returns the real portion(s) of a complex number or list as a real number.

$\boxed{\text{real}}$ (real,imag) returns real.

$\boxed{\text{real}}$ (magnitude \angle angle) returns magnitude*cos angle.

For example, $\boxed{\text{real}}$ (3,4) returns 3 and $\boxed{\text{real}}$ (3 \angle 4) returns

2.90943684703.

The imag Function

$\boxed{\text{imag}}$ (imaginary) returns the imaginary (nonreal) portion(s) of a complex number or list as a real number.

$\boxed{\text{imag}}$ (real,imag) returns imag.

$\boxed{\text{imag}}$ (magnitude \angle angle) returns magnitude*sin angle.

For example, $\boxed{\text{imag}}$ (3,4) returns 4 and $\boxed{\text{imag}}$ (3 \angle 4) returns -2.27040748592.

The CPLX (Complex Number) Menu (Continued)

The abs Function	abs (absolute value) returns the magnitude (modulus), $\sqrt{(\text{real}^2 + \text{imaginaire}^2)}$, of a complex number or list. abs (real,imag) returns $\sqrt{(\text{real}^2 + \text{imaginaire}^2)}$. abs (magnitude/angle) returns magnitude. For example, abs (3,4) returns 5 and abs (3/4) returns 3.
The angle Function	angle returns the polar angle of a complex number or list, calculated as $\tan^{-1}(\text{imag}/\text{real})$ (adjusted by $\pm\pi$ in the second quadrant or π in the third quadrant). angle (real,imag) returns $\tan^{-1}(\text{imag}/\text{real})$. angle (magnitude/angle) returns angle. For example, angle (3,4) returns 0.927295218 and angle (3/4) returns -2.28318530718.
The ►Rec Instruction	►Rec (display as rectangular) displays a complex result in rectangular format. It is valid only at the end of a command. It is not valid if the result is real. complex_result ►Rec displays (real,imag). For example, $\sqrt{-2}$ ►Rec displays (0,1.41421356237), even if the MODE is PolarC .
The ►Pol Instruction	►Pol (display as polar) displays a complex result in polar format. It is valid only at the end of a command. It is not valid if the result is real. complex_result ►Pol displays (magnitude/angle). For example, even if the MODE is RectC , $\sqrt{-2}$ ►Pol displays (1.41421356237/1.57079632679) in Radian MODE.

Chapter 12: Lists

This chapter describes functions and instructions to use with lists on the TI-85. Lists on the TI-85 can be any length, limited only by available memory.

Chapter Contents	Entering and Using Lists	12-2
	The LIST Menu	12-4
	Selecting a List	12-5
	Defining and Editing Lists with the Editor	12-6
	Using Math Functions with Lists	12-7
	List Functions	12-8
	Defining and Recalling List Dimensions	12-10

Entering and Using Lists

On the TI-85, you can enter and use real or complex lists of any length. You can enter lists, which begin with a (and end with a), in an expression directly from the keyboard. You also can define and edit lists in the LIST editor.

Lists

Lists on the TI-85 have three primary applications:

- To provide a list of values as function arguments.
- To graph a family of curves.
- To store and manipulate statistical data.

Using a List in an Expression

To use a list in an expression:

- Type the list directly.
- Type the name of the list variable (case-sensitive).
- Select the name from the VARS LIST screen.
- Select the name from the LIST NAMES menu.

Entering a List

You can enter, edit, and store a list in the LIST editor (page 12-6). You also can enter a list directly in an expression.

1. Press **[2nd]** **[LIST]** to display the LIST menu and select **(1)** to indicate the beginning of the list. **(** is copied to the cursor location.
2. Enter each element in the list, separated by commas. An element can be a real or complex number or an expression that evaluates to a real or complex number; the expression is evaluated when the command is executed. Commas are required on entry to separate elements, but are not displayed on output.
3. Select **(1)** from the LIST menu to indicate the end of the list. **)** is copied to the cursor location. This is not necessary at the end of a command or preceding the **[END]** key.

The completed expression for a list is in the form:

$(\text{element}_1, \text{element}_2, \dots, \text{element}_n)$

Storing a List

On the TI-85, lists can be stored to and represented by variables.

To store a list or a list result, press **[STO]** following the list and then enter the name of the variable to which to store it. The completed instruction is in the form:

`{element, element, ... element} → list_name`

Displaying a List

PRG/TEST

To display the contents of a list variable, use the LIST editor or enter the name of the list variable on a blank line on the Home screen and press **[ENTER]**.

Results of List Calculations

If a list result is too long to be displayed in its entirety, ellipsis marks (...) are shown at the left or right. Use **[▶]** and **[◀]** to scroll the list. Lists are displayed in the form:

`{element, element, ... element,}`

Lists as Arguments

Lists can be arguments for certain functions. The function returns a list of results calculated on an element-by-element basis. If two arguments of a function are lists, they must be the same length.

For example, $(1,2,3)^2$ returns $\{1\ 4\ 9\}$.

List Elements

A list element can be a real or complex number. If any element of a list is complex, all elements in the list are complex and are displayed as complex.

For example, $\{1,2,\sqrt{-4}\}$ returns $\{(1,0)\ (2,0)\ (0,2)\}$.

Accessing List Elements

To use an individual list element in an expression, enter the name of the list, followed by the number of the element in parentheses:

`list_name(element#)`

Note: The TI-85 does not interpret this as implied multiplication.

The LIST Menu

The LIST menu accesses the LIST identifier characters, the LIST editor (where you create, enter, and edit lists), and a menu of additional list functions and instructions.

The LIST Menu

When you press **[2nd] [LIST]**, the menu keys are labelled with the LIST menu.

{	NAMES		EDIT		OPS
<hr/>					
Item	Accesses				
{	list identifier character.				
<hr/>					
}	list identifier character.				
<hr/>					
NAMES	Menu of existing lists.				
<hr/>					
EDIT	LIST editor, where you enter and edit lists (page 12-5).				
<hr/>					
OPS	Menu of list functions and instructions (page 12-8).				
<hr/>					
	dimL	sortA	sortD	min	max
	sum	prod		li > vc	vc > li
	Fill				

Names of Lists

The LIST NAMES menu displays the names of existing lists in alphabetical order. Press **[2nd] [LIST]** to move around the menu. When you select an item, the name of the list is copied to the cursor location.

Selecting a List


To define a new list or edit an existing one, you first must enter or select the list name. You can then use the LIST editor to define a new list or edit an existing list (page 12-5).

Selecting a List

1. Select (EDIT) from the LIST menu to display the list selection screen. The menu keys are labelled with the names of existing lists in alphabetical order.



2. Enter the name of the list.
 - Select an existing name from the menu.
 - Type the name of a new or existing list of up to eight characters (case-sensitive). The keyboard is set in ALPHA mode.
3. Press **ENTER**. If you selected an existing list, the LIST editor displays its elements. In a new list, only the first element is displayed; the value is blank. A **↓** is displayed at the left of the line above the menu(s) if there are more elements in the list than can be displayed at one time.



Defining and Editing Lists with the Editor

After you have entered or selected the name of the list, the LIST editor prompts you to enter or edit the elements.

Editing a List with the LIST Editor

Enter new real or complex values (which can be expressions) for the list elements, as appropriate. Expressions are evaluated when you move off the element or leave the editor.

When you press **END** or **Y** at the bottom of a list, a prompt for a new element is added automatically.

Note: If you press a key that accesses a menu, the LIST editor moves to the seventh line (if it is not already there), and the selected menu is displayed on the eighth line.

Moving around the LIST Editor

Key	Action
←	Moves the cursor within a list element.
→	Moves the cursor between list elements.
END	Moves the cursor to the next list element.
INS	Inserts a new element above the cursor.
DEL	Deletes the element where the cursor is located.
REAL	Truncates the list in the editor to a real list.

Note: To move quickly to the final element in the list, press **↑** from the first element.

Using Functions with Lists


A list can be used to input several values to serve as arguments for certain functions. The function is evaluated for each element in the list and a list of results is returned.

Using Math Functions with Lists	Function	Display
	Addition and subtraction	$\{1,7,1\}-\{1,2,3\}$ $(0\ 5\ -2)$
		$3+\{1,7,(2,1)\}$ $\{(4,0)\ (10,0)\ (5,1)\}$
	Multiplication	$\{1,7,(2,1)\}*\{1,2,3\}$ $\{(1,0)\ (14,0)\ (6,3)\}$
		$3\{1,7,2\}$ $\{3\ 21\ 6\}$
	Division	$\{1,7,2\}/\{1,2,4\}$ $\{1\ 3\ 5\ .5\}$
		$\{1,7,2\}/5$ $\{2\ 14\ 4\}$
	Single-argument function	$\{1,7,2\}^2$ $\{1\ 49\ 4\}$ $\ln \{1,7,2\}$ $\{0\ 1.94591014906\ .69\ldots\}$
	Relational operators	$\{1,7,2\}<\{5,5,5\}$ $\{1\ 0\ 1\}$

Notes about Using Math Functions with Lists

- If a list is used as an argument to a function, the function must be valid for every element in the list, except in graphing.
- If two lists are used as arguments of two-argument functions, the length of the lists must be the same. The result is a list in which each element is the result of evaluating the function using the corresponding elements in the lists.
For example, $\{1,2,3\}+\{4,5,6\}$ returns $\{5\ 7\ 9\}$, evaluated as $\{1+4,2+5,3+6\}$.
- If a list and a value are used as arguments of two-argument functions, the value is used with each element in the list.
For example, $\{1,2,3\}+4$ returns $\{5\ 6\ 7\}$.

List Functions

The LIST OPS menu accesses functions and instructions to use with lists. Press  to move around the menu. When you select an item from the menu, the name is copied to the cursor location.

The LIST OPS Menu

When you select OPS from the LIST menu, the menu keys are labelled with the first five items of the LIST operations menu.

dimL	sortA	sortD	min	max
sum	prod	seq	ll+vc	vo+ll
Fill				

dimL is explained on page 12-10.

The Sort Functions

sortA (sort ascending) and **sortD** (sort descending) return lists with elements sorted in ascending or descending numerical order. Complex lists are sorted based on magnitude (modulus).

sortA (element₁, element₂, . . .) or **sortA** list_name

For example, **sortD** (2,7,-8,0) returns {7 2 0 -8}.

The min and max Functions

min (minimum) and **max** (maximum) return the smallest or largest element of a list. For a complex list, the element with smallest or largest magnitude (modulus) is returned. The parentheses are required.

min ((element₁, element₂, . . .)) or **max** (list_name)

For example, **min** ((2,7,-8,0)) returns -8.

The sum Function

sum (summation) returns the sum of the elements of a real or complex list.

sum (element₁, element₂, . . .) or **sum** list_name

For example, **sum** (2,7,-8,0) returns 1.

The prod Function	<p>prod (product) returns the multiplicative product of the elements of a real or complex list</p> <p>prod {element₁, element₂, ... } or prod list_name</p> <p>For example, prod {2,7,-8} returns -112.</p>
The seq Function	<p>seq (sequence) returns a real list, in which each element is the value of the expression, evaluated at increments for the specified variable from the beginning value to an ending value. The increment can be negative. seq is not valid within the expression.</p> <p>seq(expression,variable_name,begin,end,increment)</p> <p>For example, seq(M²,M,1,11,3) returns {1 16 49 100}.</p>
The li→vc Function	<p>li→vc (convert list to vector) returns a real or complex vector converted from a list.</p> <p>li→vc {element₁, element₂, ... } or li→vc list_name</p> <p>For example, 3li→vc {2,7,-8,0} returns {6 21 -24 0}.</p>
The vc→li Function	<p>vc→li (convert vector to list) returns a real or complex list converted from a vector.</p> <p>vc→li {element₁, element₂, ... } or vc→li vector_name</p> <p>For example, (vc→li {2,7,-8,0})² returns {4 49 64 0}.</p>
The Fill Instruction	<p>Fill stores a real or complex value to every element in an existing list.</p> <p>Fill(value,list_name)</p>

Defining and Recalling List Dimensions

You can access the dimension (length) of a list using the `dimL` function on the LIST OPS menu. If used as a function, `dimL` returns the number of elements of a list. Combined with the store instruction, you can use `dimL` to change the length of a list.

The List Dimension Function

`dimL` (list dimension) has three uses:

- To return the length (number of elements) of a list.
`dimL list`
For example, `1/dimL {2,7,-8,0}` returns .25.
- To create a new list of a specified length. The elements of the new list are zeros.
`length→dimL list_name`
For example: `3→dimL NEWLIST` creates **NEWLIST** {0 0 0}.
- To redimension an existing list. The elements of the old list that are within the new length are not changed. Any additional elements that are created are zeros.
`length→dimL list_name`
For example, if **MYLIST** contains {2 7 -8 0}.
`5→dimL MYLIST` changes **MYLIST** to {2 7 -8 0 0}.
`2→dimL MYLIST` changes **MYLIST** to {2 7}.

This chapter describes how to use matrices and vectors on the TI-85. The number of matrices and vectors that you can store in the TI-85 is limited only by available memory. Matrices have up to 255 rows and 255 columns. Vectors can have up to 255 elements.

Chapter Contents	Entering and Using Matrices	13-2
	The MATRIX (Matrix) Menu	13-5
	Defining and Editing Matrices with the Editor	13-6
	Using Math Functions with Matrices	13-10
	The MATRIX MATH Menu	13-12
	The MATRIX OPS (Operations) Menu	13-14
	Defining and Resizing Matrix Dimensions	13-15
	The ROW Functions	13-16
	The MATRIX Cplx (Complex) Menu	13-18
	Storing and Using Elements of a Matrix	13-19
	Entering and Using Vectors	13-20
	The VECTOR (Vector) Menu	13-23
	Defining and Editing Vectors with the Editor	13-24
	Using Math Functions with Vectors	13-26
	The VECTOR MATH Menu	13-27
	The VECTOR OPS (Operations) Menu	13-28
	Conversions	13-29
	The VECTOR Cplx (Complex) Menu	13-30

Entering and Using Matrices

A matrix is a two-dimensional real or complex array. Matrices, which begin with **[**, can be entered directly in an expression. They also can be defined and edited in the matrix editor.

Using a Matrix in an Expression

To use a matrix in an expression:

- Type the matrix directly.
- Type the name of the matrix variable (case-sensitive).
- Select the name from the VARS MATRIX screen.
- Select the name from the MATRIX NAMES menu.

Entering a Matrix

You can enter, edit, and store a matrix in the MATRIX editor (page 13-6). You also can enter a matrix directly in an expression.

1. Press **[2nd]** **[f1]** to indicate the beginning of the matrix.
2. Press **[2nd]** **[f2]** to indicate the beginning of a row.
3. Enter each element in the row, separated by commas. An element is a real or complex value (which can be an expression); the expression is evaluated when the command is executed. Commas are required on entry to separate elements, but are not displayed on output.
4. Press **[2nd]** **[f3]** to indicate the end of a row.
5. Repeat steps 2 to 4 to enter all of the rows.
6. Press **[2nd]** **[f4]** to indicate the end of the matrix.

The closing **]** is not necessary at the end of a command or preceding the **[ENTER]** key. The completed expression is in the form:

$$[[\text{element}_{1,1}, \dots, \text{element}_{1,n}] \dots [\text{element}_{m,1}, \dots, \text{element}_{m,n}]]$$

Note: Each row in a matrix is a vector, therefore, a vector can be used to define a row. For example, $[1,2,3] \rightarrow V1:[V1][V1]$ is equivalent to $[[1,2,3][1,2,3]]$.

Entering and Using Matrices (Continued)

Example

Calculate 2 times the matrix:

$$\begin{bmatrix} 5 & 3 & 2 \\ 2 & 1 \end{bmatrix}$$

Store it to a variable and recall element 1,2.

2	STO	[1]	[5]	[1]		
3	STO	[2]	[1]			
2	[1]	[2]	[1]	[2]	+	[1]
2	[1]	[2]	[1]			
						2[[5,3-2]][2,(2,1)]
						[[10,0] (2,0)]
						[[4,0] (4,2)]
MAT						Ans→MAT
						[[10,0] (2,0)]
						[[4,0] (4,2)]
MAT ALPHA						
1	[2]					
						MAT (1,2)
						(2,0)

Matrix Elements

A matrix element can be a real or complex value.

If any element of a matrix is complex, all elements in the matrix are complex.

Note: The TI-85 does not interpret the name of a matrix followed by an open parenthesis as implied multiplication. It accesses specific elements in the matrix (page 13-19).

The MATRX (Matrix) Menu

The MATRX menu accesses additional matrix capabilities of the TI-85. From this menu you create and enter matrices, change matrix elements, change the dimension of a matrix, and access additional matrix functions.

The MATRX Menu

When you press **2nd** [MATRX], the menu keys are labelled with the matrix menu.

NAMES	EDIT	MATH	OPS	CPLX	
Item	Accesses				
NAMES	Menu of existing matrices.				
EDIT	The matrix editor, where you enter and edit matrices (page 13-6).				
MATH	Matrix math functions (page 13-12).				
	del norm	T cnorm	norm LU	eigVl cond	eigVc
OPS	Matrix row functions and other matrix functions and instructions (page 13-14).				
	dim aug randM	Fill rSwap	Ident rAdd	row multR	col multC
CPLX	Complex matrix functions (page 13-16).				
	conj	real	imag	abs	angle

Names of Matrices

The MATRX NAMES menu displays the names of existing matrices in alphabetical order. Press **2nd** [MATRX] to move around the menu. When you select an item, the name of the matrix is copied to the cursor location.

Defining and Editing Matrices with the Editor

In addition to entering matrices directly in an expression, you can use the matrix editor to define a new matrix or to edit an existing matrix. To define a new matrix or edit an existing one, you must first select the matrix name.

Selecting a Matrix

1. Select (EDIT) from the MATRX menu to display the matrix selection screen. The menu keys are labeled with the names of existing matrices in alphabetical order.



2. Enter the name of the matrix.
 - Select an existing name from the menu.
 - Type the name of a new or existing matrix of up to eight characters (case-sensitive). The keyboard is set in ALPHA-lock.
3. Press (ENTER). If you selected an existing matrix, its dimensions and elements are displayed.

Accepting or Changing Matrix Dimensions

The dimensions of the matrix (rows \times columns) are displayed on the top line. The default dimension for a new matrix is 3×1 . The cursor is on the row dimension. You must accept or change the row dimension value and the column dimension value each time you enter the matrix editor.

- To accept the value, press (ENTER).
- To change the value, enter a number (up to 255) and press (ENTER).

Note: You can use (A) and (Y) to move onto and edit the matrix dimensions at any time in the editor.

Displaying Matrix Contents in the Editor

The matrix is displayed in the matrix editor one column at a time. For example, let **SAMPLE** be the 8 x 4 matrix:

1	2	1	4
2	2	2	2
1	3	3	4
0	0	5	3
2	0	9	4
5	0	0	0
5	0	2	-4
5	6	3	1.1

The six elements indicated in column 3 of **SAMPLE** would be displayed in the matrix editor as:

MATRIX: SAMPLE		8x4
↑	2	1
↓	3	2
↓	4	3
↓	5	5
↓	6	9
↓	7	0
↓	8	2

name & dimensions
row,column=value

Defining and Editing Matrices with the Editor (Continued)

Editing a Matrix with the Matrix Editor

In a new matrix, all values are zero. ↓ is displayed at the left of the line above the menu(s) if there are more rows in the matrix that can be displayed at one time.



name & dimensions
row,column=element

Enter new real or complex values (which can be expressions) for the matrix elements, as appropriate. Expressions are evaluated when you move off the element or leave the editor.

- Press **ENTER** after each value to enter the matrix row by row.
- Press **↓** after each value to enter the matrix column by column.

Note: If you press a key that accesses a menu, the matrix editor menu moves to the seventh line (if it is not already there), and the selected menu is displayed on the eighth line.

Moving around the Matrix Editor

When you select a matrix, the menu keys are labelled with the first five items of the matrix editing operations. Press **Q** to move around the menu.

<COL DELc	COL > >REAL	INSr	DELr	INSc
Key		Action		
→ or ←		Moves the cursor within a matrix element.		
↓ or ↑		Moves the cursor within the current column. If the cursor is on the first element, ↓ moves the cursor onto the dimensions. If the cursor is on the bottom element, ↑ moves the cursor to the top of the next column.		
ENT		Moves the cursor to the next column, same row, except on the final column (moves to first column, next row for convenience in entering).		
(<COL) or (COL >)		Displays the adjacent column, with the cursor on the same row.		
INSr		Inserts a new row above the cursor.		
DELr		Deletes the row where the cursor is located.		
INSc		Inserts a new column to left of the cursor.		
DELc		Deletes the column where the cursor is located.		
<>REAL		Truncates the matrix in the editor to a real matrix.		

To add a row at the bottom or a column on the right, change the dimensions. Each new element is zero.

Using Math Functions with Matrices

A matrix can be used in many expressions where a variable can be used. However, the dimensions of the matrices must be appropriate for the function. Math functions to use with matrices can be accessed from the keyboard, Math menu, and TEST menu, in addition to the MATRIX menu.

The Addition Subtraction Functions

To add or subtract matrices, the dimensions must be the same.
 $\text{matrix} + \text{matrix}$ or $\text{matrix} - \text{matrix}$

The Multiplication Function

To multiply matrices, the column dimension of the first matrix must match the row dimension of the second matrix.

$\text{matrix} * \text{matrix}$ or matrix matrix

You can multiply a value times a matrix or a matrix times a value.

value matrix or matrix value

The Negation Function

Negating a matrix negates each element in the matrix.

$-\text{matrix}$

The Inverse Function

To invert a matrix, the matrix must be square and the determinant cannot equal zero.

matrix^{-1}

The Square Function

To square a matrix, the matrix must be square.

matrix^2

The Power Function

To raise a matrix to a power, the matrix must be square. The power must be a real integer between 0 and 255.

$\text{matrix} \wedge \text{power}$

The round Function	<p>Rounding a matrix rounds each element in a real or complex matrix. The second argument (optional) is the number of decimal places (0 to 11) to round to. If there is no second argument, the number is rounded to twelve digits. The parentheses are required.</p> <p><code>round(matrix,decimals)</code> or <code>round(matrix)</code></p> <p>For example, <code>round([5.555,4.4][.001,0],2)</code> returns</p> $\begin{bmatrix} 5.56 & 4.4 \\ 0 & 0 \end{bmatrix}$
The Relational Functions	<p>To compare two matrices using the relational functions <code>=</code> and <code>*</code> the matrices must have the same dimensions. The matrices are compared on an element-by-element basis, and a 1 if true or a 0 if false is returned. If the matrix is complex, the magnitude (modulus) of each element is compared.</p> <p><code>matrix==matrix</code> returns 1 if every comparison is true; it returns 0 if any comparison is false.</p> <p><code>matrix<matrix</code> returns 1 if at least one comparison is false.</p>
The Exponential, sin, and cos Functions	<p><code>e^matrix</code>, <code>sin matrix</code>, and <code>cos matrix</code> return square, real matrices that are the matrix exponential, matrix sine, or matrix cosine of a square, real matrix. This is not the exponential, sine, or cosine of each element. The value returned for the exponential of a defective matrix may be incorrect.</p>
The iPart, fPart, and int Functions	<p><code>iPart matrix</code>, <code>fPart matrix</code>, and <code>int matrix</code> return a real or complex matrix containing the integer part, fractional part, or greatest integer of each element of a real or complex matrix.</p>

The MATRX Math Menu

The MATRX Math menu displays additional matrix math functions. Press $\boxed{\text{MATH}}$ to move around the menu. When you select an item from the menu, the name is copied to the cursor location.

The MATRX Math Menu

When you select MATH from the MATRX menu, the menu keys are labelled with the first five items of the menu.

det	T	norm	eigVl	eigVc
norm	cnorm	LU	cond	

The det Function

det (determinant) returns the determinant of a square matrix. The result is a real number if the matrix is real, a complex number if the matrix is complex.

det matrix

The Transpose Function

T (transpose) returns a transposed matrix. The result is a matrix in which $\text{element}(\text{row}, \text{column})$ is swapped with $\text{element}(\text{column}, \text{row})$. For complex matrices, the result is a matrix in which $\text{element}(\text{row}, \text{column})$ is swapped with $\text{element}(\text{column}, \text{row})$, and the conjugate is taken.

matrix^T

The norm Function

norm returns the Froebius norm, a number equal to $\sqrt{\text{of } \Sigma \text{ of } (\text{real}^2 + \text{imag}^2)}$ of each element of a real or complex matrix.

norm matrix

The eigVl Function

eigVl (eigenvalues) returns a list of the eigenvalues of a real or complex square matrix. The eigenvalues of a real matrix may be complex.

eigVl matrix

The eigVc Function

eigVc (eigenvector) returns a matrix containing the eigenvectors for a real or complex square matrix, each column corresponding to an eigenvalue. The eigenvectors of a real matrix may be complex.

eigVc matrix

The rnorm Function	rnorm (row norm) returns the largest of the sums of the absolute values of the elements (magnitudes of complex elements) in each row. rnorm matrix
The cnorm Function	cnorm (column norm) returns the largest of the sums of the absolute values of the elements (magnitudes of complex elements) in each column. cnorm matrix
The LU Instruction	LU (lower-upper decomposition) calculates the permutation matrix resulting from the Crout LU decomposition of a square real or complex matrix. It stores the lower triangular matrix, the upper triangular matrix, and the permutation matrix in the variables specified by the second, third, and fourth arguments, respectively. LU(matrix_name,umatrix_name,pmatrix_name)
The cond Function	cond (condition) returns $\text{norm}(\text{matrix})/\text{matrix}^{-1}$. This number indicates how well-behaved a real or complex square matrix is expected to be for certain matrix functions, particularly inverse. The condition number for a well-behaved matrix is close to 1. cond matrix For a matrix with no inverse, cond returns an error.

The MATRX OPS (Operations) Menu

The MATRX OPS menu displays the matrix row operations, the dimension function, and several additional matrix functions and instructions. Press **OPS** to move around the menu. When you select an item from the menu, the name is copied to the cursor location.

The MATRX OPS Menu

When you select **OPS** from the MATRX menu, the menu keys are labelled with the first five items of the matrix operations menu.

dim	Fill	Ident	ref	ref
aug	rSwap	OPS	multR	mRAdd
randM				

dim is explained on page 13-15. The row operations are explained on pages 13-16 and 13-17

The Fill **Fill(value,matrix_name)**

Fill stores a value to every element in an existing matrix.
Fill(value,matrix_name)

Note: A real value stored to a complex matrix makes the matrix real, and vice versa.

The Ident Function

Ident (identity) returns the identity matrix of the dimension specified.

Ident dimension

The aug Function

aug (augment) concatenates two matrices or a matrix and a vector (real or complex). The number of rows in the first matrix must equal the number of rows in the second matrix or the number of elements in the vector.

aug(matrixA,matrixB) or **aug(matrix,vector)**

For example, to augment $\begin{bmatrix} 1 & 2 \end{bmatrix}$ with $\begin{bmatrix} 3 & 4 \end{bmatrix}$ or $\begin{bmatrix} 5 & 6 \end{bmatrix}$ and $\begin{bmatrix} 7 & 8 \end{bmatrix}$:

aug([1,2],[3,4],[5,6],[7,8]) return $\begin{bmatrix} 1 & 2 & 5 & 8 \\ 3 & 4 & 7 & 8 \end{bmatrix}$

The randM Function

randM (create random matrix) returns a matrix of random one-digit integers (-9 to 9) of the dimensions specified.

randM(rows,columns)

For example, 0→**rand:randM(2,3)** create $\begin{bmatrix} 4 & -2 & 0 \\ -7 & 0 & 8 \end{bmatrix}$

Defining and Recalling Matrix Dimensions

Matrix dimensions can be accessed using the `dim` function on the **MATRIX OPS** menu. The `dim` function is used to recall or store the dimensions of a matrix.

The dim Function

dim (dimension) has three uses:

- To return a list containing the dimensions (number of rows and columns) of a matrix.

dim matrix

For example, `dim [[2,7,1]]-[3,0,1]` returns `[2 3]`

- **To create a new matrix of specified dimensions** (used with the store instruction). The elements in the new matrix are zeros.

```
(rows,columns) = dim matrix name
```

For example, `[2,2]-dim NEWMTRX` creates

NEWMATRIX ((0 0)
(0 0))

- To redimension an existing matrix (used with the store instruction). The elements in the old matrix that are within the new dimensions are not changed. Any additional elements that are created are zero.

[rows,columns] = dlm matrix name

For example, if MAT contains

$$\begin{pmatrix} 2 & 7 & 7 \\ -6 & 0 & 7 \end{pmatrix}$$
(2.2) \Rightarrow dim MAT changes MAT

in memory to

$$\begin{bmatrix} 2 & 7 \\ -8 & 0 \end{bmatrix}$$

{2,3} = dim MAT change MAT

in memory to

$$\begin{bmatrix} 2 & 7 & 0 \\ -6 & 0 & 0 \end{bmatrix}$$

The Row Functions

Six matrix row functions can be accessed from the **MATRIX OPS** menu. These functions, which can be used in an expression, do not change the original matrix. The result of each function is a temporary matrix. The value for a multiplier or a row can be an expression.

The ref Function	ref (row echelon form) returns the row echelon form of a real or complex matrix. The number of columns must be greater than or equal to the number of rows. ref matrix
The rref Function	rref (reduced row echelon form) returns the reduced row echelon form of a real or complex matrix. The number of columns must be greater than or equal to the number of rows. rref matrix
The rSwap Function	rSwap (row swap) returns a matrix after swapping two rows. It requires three arguments: the matrix, the number of the first row to swap, and the number of the row to swap with it. rSwap(matrix,row1,row2)
The rAdd Function	rAdd (row addition) returns a matrix after adding two rows and storing the results in the second row. It requires three arguments: the matrix, the number of the row to add, and the number of the row to add to and in which to store the results. rAdd(matrix,row1,row2)
The multR Function	multR (row multiplication) returns a matrix after multiplying a row by a value and storing the results in the same row. It requires three arguments: the value, the matrix, and the number of the row to multiply. multR(value,matrix,row)
The mRAdd Function	mRAdd (multiply and add row) returns a matrix after multiplying a row by a value, adding the results to a second row, and storing the results in the second row. It requires four arguments: the value, the matrix, the number of the row to multiply, and the number of the row to add to and in which to store the results. mRAdd(value,matrix,row1,row2)

The Row Functions (Continued)

Function	Display
Enter matrix	[[5,3,1,1] [2,0,4,2] [-3,-1,2,3]]→MTRX $\begin{bmatrix} 5 & 3 & 1 & 1 \\ 2 & 0 & 4 & 2 \\ -3 & -1 & 2 & 3 \end{bmatrix}$
Swap row 2 and row 3	rSwap(MTRX,2,3) $\begin{bmatrix} 5 & 3 & 1 & 1 \\ -3 & -1 & 2 & 3 \\ 2 & 0 & 4 & 2 \end{bmatrix}$
Add row 2 to row 3	rAdd(MTRX,2,3) $\begin{bmatrix} 5 & 3 & 1 & 1 \\ 2 & 0 & 4 & 2 \\ -1 & -1 & 6 & 5 \end{bmatrix}$
Multiply row 2 by 5	mMult(5,MTRX,2) $\begin{bmatrix} 5 & 3 & 1 & 1 \\ 10 & 0 & 20 & 10 \\ -3 & -1 & 2 & 3 \end{bmatrix}$
Multiply row 2 by 5, add to row 3	mRAdd(5,MTRX,2,3) $\begin{bmatrix} 5 & 3 & 1 & 1 \\ 2 & 0 & 4 & 2 \\ 7 & -1 & 22 & 13 \end{bmatrix}$
Return row echelon form	ref MTRX $\begin{bmatrix} 1 & .8 & .2 & .2 \\ 0 & 1 & -3 & -1.33333333 \\ 0 & 0 & 1 & .93333333 \end{bmatrix}$
Return reduced row echelon form	rref MTRX $\begin{bmatrix} 1 & 0 & 0 & -.866666666 \\ 0 & 1 & 0 & 1.466666666 \\ 0 & 0 & 1 & .933333333 \end{bmatrix}$

The MATRX CPLX (Complex) Menu

The MATRX CPLX menu displays complex functions to use with complex matrices. If a matrix has any complex element, all elements in the matrix are complex. When you select an item from the menu, the name is copied to the cursor location.

The MATRX CPLX Menu

When you select (CPLX) from the MATRX menu, the menu keys are labelled with the matrix complex menu.

conj real imag abs angle

The conj Function

conj (conjugate) returns the complex conjugate of a complex matrix. The result is a complex matrix in which each element is the complex conjugate of the original.

conj matrix

The real Function

real returns a real matrix containing the real portion of each element.

real matrix

The imag Function

imag (imaginary) returns a real matrix containing the imaginary portion of each element.

imag matrix

The abs Function

abs (absolute value) returns a real matrix. If an element is real, **abs** returns the absolute value of the element. If an element is complex, **abs** returns the magnitude (modulus), $\sqrt{(\text{real}^2 + \text{imag}^2)}$, of the element.

abs matrix

The angle Function

angle returns a real matrix containing the polar angle of each element, calculated as $\tan^{-1}(\text{imag}/\text{real})$, adjusted by $+\pi$ for second quadrant or $-\pi$ for the third quadrant.

angle matrix

Creating a Complex Matrix

You can create a complex matrix from two real matrices of the same dimensions, one containing the real part of each element and one containing the imaginary part of each element. The dimensions of the matrices must be the same.

real_matrix+(0,1)imag_matrix

Storing and Using Portions of a Matrix

A specific matrix element, row, or submatrix can be used in an expression. You can store to a specific matrix element, row, or submatrix from the Home screen or a program.

Accessing a Matrix Element

The name of a matrix followed by an open parenthesis accesses specific elements in the matrix. It does not indicate implied multiplication. The expression to access a matrix element is:

$$\text{matrix_name}(\text{row}, \text{column})$$

For example, if **MTRX** is

$$\begin{bmatrix} 1 & 2 & 3 \\ 4 & 5 & 6 \end{bmatrix}$$

MTRX(1,2) returns 2.

Accessing a Matrix Row

A matrix row is a vector. The expression to access all of a matrix row is:

$$\text{matrix_name}(\text{row})$$

For example, **MTRX(1)** returns

$$\begin{bmatrix} 1 & 2 & 3 \end{bmatrix}$$

Accessing a Submatrix

The expression to access a submatrix is:

$$\text{matrix_name}(\text{beginrow}, \text{begincolumn}, \text{endrow}, \text{endcolumn})$$

For example, **MTRX(1,1,2,2)** returns

$$\begin{bmatrix} 1 & 2 \\ 4 & 5 \end{bmatrix}$$

Changing a Matrix

7→MTRX(1,2) changes **MTRX** to

$$\begin{bmatrix} 1 & 7 & 3 \\ 4 & 5 & 6 \end{bmatrix}$$

(7,8,9)→MTRX(1) changes **MTRX** to

$$\begin{bmatrix} 7 & 8 & 9 \\ 4 & 5 & 6 \end{bmatrix}$$

The instruction to store to part of a matrix row is:

$$\text{vector} \rightarrow \text{matrix_name}(\text{row}, \text{column})$$

[1,2]→MTRX(2,2) changes **MTRX** to

$$\begin{bmatrix} 1 & 7 & 3 \\ 4 & 1 & 2 \end{bmatrix}$$

To store a submatrix, specify the beginning row and column.

[[5,7]][8,9]→MTRX(1,2) changes **MTRX** to

$$\begin{bmatrix} 7 & 6 & 7 \\ 4 & 8 & 9 \end{bmatrix}$$

Entering and Using Vectors

A vector is a one-dimensional array. You can enter and use real or complex vectors of up to 255 elements on the TI-85. Vectors, which begin with **f**, can be entered in an expression directly from the keyboard. They also can be defined and edited in the vector editor.

Vectors

Vectors are treated as $n \times 1$ arrays for calculation purposes, but are entered and displayed as $1 \times n$ arrays for convenience. A 2-element or 3-element vector may define magnitude and direction in 2-dimensional or 3-dimensional space.

Vectors of more than three elements must be entered in rectangular format. 2-element and 3-element vectors can be entered and displayed in several formats:

Format	Entry	Display
2-element rectangular	$\{x,y\}$	$\begin{bmatrix} x & y \end{bmatrix}$
2-element cylindrical or spherical	$\{r,\phi\}$	$\begin{bmatrix} r & \phi \end{bmatrix}$
3-element rectangular	$\{x,y,z\}$	$\begin{bmatrix} x & y & z \end{bmatrix}$
3-element cylindrical	$\{r,\phi,z\}$	$\begin{bmatrix} r & \phi & z \end{bmatrix}$
3-element spherical	$\{r,\theta,\phi\}$	$\begin{bmatrix} r & \theta & \phi \end{bmatrix}$

Note: Only real vectors are displayed in cylindrical or spherical format. Complex vectors are automatically displayed in rectangular format.

Using a Vector in an Expression

To use a vector in an expression:

- Type the vector directly.
- Type the name of the vector variable (case-sensitive).
- Select the name from the VARS VECTR screen.
- Select the name from the VECTR NAMES menu.

Entering a Vector

You can enter, edit, and store a vector in the VECTR editor (page 13-24). You also can enter a vector directly in an expression.

1. Press **2nd** **[F]** to indicate the beginning of the vector.
2. Enter each element in the vector, separated by a comma or angle symbol (the **2nd** function of **[<]**, depending on the preferred vector format). An element is a real or complex value (which can be an expression); the expression is evaluated when the command is executed.
3. Press **[2nd]** **[0]** to indicate the end of the vector. This is not necessary at the end of a command or preceding the **[STO]** key.

The completed expression is in the form:

$[element_1, \dots, element_n]$ or $[element_1 \angle element_2]$

Storing a Vector

On the TI-85, vectors can be stored to and represented by variables.

To store a vector or a vector result, press **[STO]** following the vector and then enter the name of the variable to which store it. When the instruction is executed, the TI-85 evaluates any elements contained as expressions and then stores the vector to the variable. The completed instruction is in the form:

$[element_1, \dots, element_n]$ vector name









Displaying a Vector Variable

Real 2-element and 3-element vector results are displayed in the format specified by the MODE setting (**RectV**, **CylV**, or **SphereV**) or by a display conversion instruction (page 13-29).

Entering and Using Vectors (Continued)

Example of Entering a Vector

In **RectV** MODE, calculate 6 times the vector $(5+1i)$, store the result, and then find the fractional portion.

			
		$6[5,1+1]$	$[3,1.2]$
		Ans→VECT	$[3,1.2]$
		IPart VECT	$[0,2]$

Vector Elements

An element of a vector can be a real or a complex number. If any element of a vector is complex, all elements of the vector are complex.

For example, $[1.2, (3,1)]$ returns $[(1.9), (2,0), (3,1)]$.

Using a Vector Element in an Expression

A specific vector element can be used in an expression. You can store to a specific vector element from the Home screen or a program.

value→**vector_name**(**element**)

The VECTR (Vector) Menu

The VECTR menu accesses additional vector instructions and functions. From this menu you create and enter vectors, change vector elements, change the dimension of a vector, and access additional vector functions.

The VECTR Menu

When you press **2nd** VECTR, the menu keys are labelled with the vector menu.

NAMES	EDIT	MATH	OPS	CPLX
Item	Accesses			
NAMES	Menu of existing vectors.			
EDIT	The vector editor, where you enter and edit vectors (page 13-24).			
MATH	Vector math functions (page 13-27).			
	unHV	dot		
OPS	Vector functions and display conversion instructions (page 13-28).			
	dim	Fill	►Pol	►Cyl
	►Rec	ll=vc	vc=ll	►Sph
CPLX	Complex vector functions (page 13-30).			
	conj	real	imag	abs
				angle

Names of Vectors

The VECTR NAMES menu displays the names of existing vectors in a prioritized order. Press **2nd** to move around the menu. When you select an item, the name of the vector is copied to the cursor location.

Defining and Editing Vectors with the Editor


In addition to entering vectors directly in an expression, you can use the vector editor to define a new vector or to edit an existing vector. To define a new vector or edit an existing one, you must first select the vector name.

Selecting a Vector

1. Select **EDIT** from the **VECT** menu to display the vector selection screen. The menu keys are labelled with the names of existing vectors in alphabetical order.



2. Enter the name of the vector.
 - Select an existing name from the menu.
 - Type the name of a new or existing vector of up to eight characters (case-sensitive). The keyboard is set in ALPHA-lock.
3. Press **ENTER**. If you selected an existing vector, its dimension and elements are displayed. For a new vector only the first element is displayed. If the dimension is zero, a sphere is at the left of the dimension (the minus). If there are more elements in the vector than can be displayed at one time,








4. Change the dimension if desired. Press **ENTER**.

Editing a Vector with the Vector Editor

Enter new real or complex values (which can be expressions) for the vector elements, as appropriate. The expression is evaluated when you move off the element or leave the editor.

Note: If you press a key that accesses a menu, the vector editor menu moves to the seventh line (if it is not already there), and the selected menu is displayed on the eighth line.

Moving around the Vector Editor

Key	Action
 	Moves the cursor within a vector element.
 	Moves the cursor between vector elements.
	Moves the cursor to next vector element.
INS	Inserts a new element above the cursor.
DEL	Deletes the element where the cursor is located.
(←REAL)	Truncates the vector in the editor to a real vector.

Note: To move quickly to the final element in the vector, press  from the dimension.

Using Math Functions with Vectors

A vector can be used in many expressions where a variable can be used. Math functions to use with vectors can be accessed from the keyboard, from the Math menu, and from the TEST menu.

The Addition and Subtraction Functions

To add or subtract real or complex vectors, the length must be the same. The result is a vector in which each element is the result of operating on the corresponding elements.

vector+vector or vector-vector

The Multiplication and Division Functions

You cannot multiply a vector times a vector, square a vector, or raise a vector to a power. You can multiply a vector times a real or complex value or vice versa. You can divide a vector by a real or complex value.

value vector or vector/value

An $m \times n$ matrix multiplied by an n -element vector returns an m -element vector.

The Negation Function

Negating a vector negates each element in the vector.

-vector

The IPart, fPart, and Int Functions

IPart (integer part), **fPart** (fractional part), and **Int** (greatest integer) return a real or complex vector containing the integer part, fractional part, or greatest integer of each element of a real or complex vector.

IPart vector, fPart vector, or Int vector

The round Function

round rounds each element of a vector. The parentheses are required.

round(vector,decimals) or round(vector)

The Relational Functions

To compare two vectors of the same dimension, use the relational functions **=** and **<**. The vectors are compared on an element-by-element basis and a 1 if true or 0 if false is returned. If the vector is complex, the magnitude (modulus) of each element is compared.

vector=vector returns 1 if every comparison is true; it returns 0 if any comparison is false.

vector<vector returns 1 if at least one comparison is false.

The VECTR Math Menu

The VECTR Math menu displays additional vector math functions. Some vector functions are valid only for 2-element or 3-element vectors. When you select an item from the menu, the name is copied to the cursor location.

The VECTR Math Menu

When you select **Math** from the VECTR menu, the menu keys are labelled with the menu.

cross **unitV** **norm** **dot**

The cross Function

cross (cross product) returns the cross product of two real or complex 2-element or 3-element vectors. For example,

cross(a,b,c),(d,e,f) returns $(bf-ce, c-a-df, ad-bc)$

The unitV Function

unitV (unit vector) returns the unit vector (each element divided by the norm of the vector) of any real or complex vector. For example,

unitV(a,b,c) returns $(a/norm, b/norm, c/norm)$.

The norm Function

norm returns the length of any real or complex vector, calculated as $\sqrt{2 \times \text{real}^2 + \text{imag}^2}$. For example,

norm(a,b,c) returns $\sqrt{(a^2 + b^2 + c^2)}$

The dot Function

dot (dot product) returns the dot product of any two real or complex vectors. The result is a real number if the vectors are real or a complex number if the vectors are complex. For example,

dot(a,b,c),(d,e,f) returns $ad+be+cf$.

The VECTR OPS (Operations) Menu

The VECTR OPS menu displays operations for vectors. Press **Ops** to move around the menu. When you select an item from the menu, the name is copied to the cursor location. Some vector operations are valid only for 2-element or 3-element vectors.

The VECTR OPS Menu

When you select OPS from the VECTR menu, the menu keys are labelled with the vector operations menu.

dim **Fill** **↗Pol** **↖Cyl** **↘Sph**
↖Vec **0↗vc** **vc↖ll**

The dim Function

dim (dimension) has three uses:

- To return the length (number of elements) of a vector.
dim vector
For example, **dim [1,0,1]** returns 3.
- To create a new vector of specified length (used with the store instruction). The elements in the new vector are zeros.
length↗dim vector_name
For example, **4↗dim NEWVECT** creates **NEWVECT** and stores **[0 0 0 0]** in it.
- To redimension an existing vector (used with the store instruction). The elements in the old vector that are within the new dimensions are not changed. Any additional elements that are created are zeros.
length↗dim vector_name
For example, if **VECT** contains **[2 7 7]**, **2↗dim VECT** changes **VECT** in memory to **[2 7]**. Then **3↗dim VECT** changes **VECT** in memory to **[2 7 0]**.

Note: The name of a vector followed by an open parenthesis accesses a specific vector element. It does not indicate implied multiplication.

The Fill Instruction

Fill stores a value to every element in an existing vector.

Fill(value,vector_name)

Display conversion instructions in the VECTR OPS menu control how a 2-element or 3-element vector result is displayed, regardless of the MODE setting. They are valid only at the end of command. The values in the expression are interpreted according to the current MODE setting.

Display Conversion	The 3-element vector conversion equations are: <div> <div> Cylindrical $(r\ \theta\ z)$ $x = r \cos\theta$ $y = r \sin\theta$ $z = z$ </div> <div> Spherical $(r\ \theta\ \phi)$ $x = r \cos\theta \sin\phi$ $y = r \sin\theta \sin\phi$ $z = r \cos\theta$ </div> </div>	
The ►Pol Instruction	►Pol (display as polar) displays a 2-element real vector result in polar format, even if the MODE is not CylV or SphereV vector ►Pol displays $[r\ z\ 0]$. For example, $[-2,0]\text{►Pol}$ displays $[2.3.14159265359]$.	
The ►Cyl Instruction	►Cyl (display as cylindrical) displays a 2-element or 3-element real vector result in cylindrical format, even if the MODE is not CylV vector ►Cyl displays $[r\ z\ 0]$ or $[r\ z\ \theta\ z]$. For example, $[-2,0]\text{►Cyl}$ displays $[2.3.14159265359\ 0]$ (a 3-element vector is stored in Ans), and $[-2,0,1]\text{►Cyl}$ displays $[2.3.14159265359\ 1]$.	
The ►Sph Instruction	►Sph (display as spherical) displays a 2-element or 3-element real vector result in spherical format, even if the MODE is not SphereV. vector ►Sph displays $[r\ z\ \theta\ 0]$ or $[r\ z\ \theta\ z]$. For example, $[0,0]\text{►Sph}$ displays $[0.0\ 0\ 0]$ (a 3-element vector is stored in Ans), and $[0,0,-1]\text{►Sph}$ displays $[1.0\ 3.14159265359]$.	
The ►Rec Instruction	►Rec (display as rectangular) displays a 2-element or 3-element real vector result in rectangular format, even if the MODE is not RectV vector ►Rec displays $[x\ y]$ or $[x\ y\ z]$. For example, $[2\ z\ z]\text{►Rec}$ displays $[0\ 0\ 2]$.	
The ►vc Function	►vc (convert list to vector) returns a real or complex vector converted from a list. For example, $\text{►vc } \{1,2,3\}$ returns $\{1\ 2\ 3\}$.	
The vc►li Function	vc►li (convert vector to list) returns a real or complex list converted from a vector. For example, $\text{vc►li } \{1,2,3\}$ returns $\{1\ 2\ 3\}$.	

The VECTR CPLX (Complex) Menu

The VECTR CPLX menu displays complex functions to use with vectors with complex elements. If a vector has any complex element, all elements in the vector are complex. When you select an item from the menu, the name is copied to the cursor location.

The VECTR CPLX Menu	When you select (CPLX) from the VECTR menu, the menu keys are labelled with the vector complex menu. conj real imag abs angle
The conj Function	conj (conjugate) returns the complex conjugate of a complex vector. The result is a complex vector in which each element is the complex conjugate of the original. conj vector
The real Function	real returns a real vector containing the real portion of each element. real vector
The imag Function	imag (imaginary) returns a real vector containing the imaginary portion of each element in a complex vector. imag vector
The abs Function	abs (absolute value) returns a real vector. If an element is real, abs returns the absolute value of the element. If an element is complex, abs returns the magnitude (modulus), $\sqrt{x(\text{real})^2 + \text{imag}^2}$, of the element. abs vector
The angle Function	angle returns a real vector. If an element is real, angle returns 0. If an element is complex, angle returns the polar angle of the complex elements of a vector, calculated as $\tan^{-1}(\text{imag}/\text{real})$ (adjusted by $+\pi$ in second quadrant, $-\pi$ in third quadrant). angle vector
Creating a Complex Vector	You can create a complex vector from two real vectors, one containing the real part of each element and one containing the imaginary part of each element. real_vector+(0,1)imag_vector→cplx_vector

Chapter 14: Equation Solving

This chapter describes three equation-solving features of the TI-85. The SOLVER solves single equations for any variable in the equation. The POLY (Polynomial) Root Finder solves for the real and complex roots of polynomials. The SIMULT (Simultaneous) Equations Solver solves a system of real or complex simultaneous linear equations.

Chapter Contents	Entering an Equation in the SOLVER	14-2
	Defining the Variables	14-3
	Solving the Equation	14-4
	Factoring the Solution Graphically	14-6
	Constructing the Solution	14-7
	Entering the POLY (Polynomial) Equation	14-8
	Solving the Polynomial	14-9
	Entering SIMULT (Simultaneous) Equations	14-10
	Solving Simultaneous Equations	14-11
	Example: Simultaneous Equations	14-12

Entering an Equation in the SOLVER

The TI-85 SOLVER allows you to solve for any variable in the equation. You first enter the equation, then enter values for each variable in the equation, and then solve for the unknown variable. (Getting Started contains a complete example using the SOLVER.)

Entering the Equation

To display the SOLVER equation entry screen, press **[2nd]** **[SOLVER]**.



The SOLVER uses the equation in the equation-variable **eqn**, which contains the last equation used in the SOLVER if any. It is displayed on the top line. (See example in Getting Started.) You may insert or edit the displayed equation, or you may press **[2nd]** **[CLR]** to clear the line and enter a new equation. As you enter an equation, it is stored in the variable **eqn**.

The equation can have more than one variable to the left of the equal sign; for example, $A+B=C+\sin D$.

You can enter an expression (without an equal sign). The expression is assumed equal to the variable **exp**. For example, if you enter $E+F \ln G$, you will solve the equation $\text{exp}=E+F \ln G$.

The menu keys are labelled with the names of previously defined equation variables.

- If you select a name from the menu, the name is copied to the cursor location.
- If you press **[2nd]** **[RCL]** and then select a name from the menu, the contents are inserted at the cursor location.


If an equation is too long to display in its entirety, ellipsis marks (...) are shown at the left or right. **[2nd]** **[←]** and **[2nd]** **[→]** move the cursor to the beginning and end of the equation quickly.

Defining the Variables

All variables except the unknown variable for which you are solving must contain values. The unknown variable may contain a value, which is used as an initial guess. Constants and most system variables are valid in equations. Constants and some system variables cannot be used for.

Displaying the Variables

To display the SOLVER edit screen, enter the equation and press **2ND**.



The equation is displayed on the top line. To move onto the equation, press **Δ** on the first variable; the equation entry screen is displayed.

Variables are listed in the order in which they appear (left to right) in the equation. If any have values, the value is displayed. If you entered an expression (rather than an equation) for eqn, exp is the first variable listed.

If you used an equation variable in the eqn equation, the variables in that equation variable are displayed. For example, if the variable A contains $B+C$, the equation $D=2A$ can be solved; the variables B, C, and D are displayed on the SOLVER edit screen.

bound=(lower,upper) defines the bound between which the solution is sought (page 14-7). When you enter the SOLVER, lower = $-1E99$ and upper = $1E99$. You can edit the list containing lower and upper (bound) in the SOLVER.

Entering Variable Values

You may enter an expression for a variable value. It is evaluated when you move off the variable. If you enter a value or edit an existing value, the value of the variable in memory is changed also.

Expressions must resolve to real numbers at each step during the iteration.

Equations with Multiple Roots

More than one solution may exist for an equation. You can enter a new initial guess or a new bound to look for additional solutions (page 14-7).

You also can use the graphing feature to select a new initial guess or set a new bound.

Further Solutions

After solving for a variable, you can continue to explore solutions from this display. Edit the values of any of the variables and solve again.

Editing the Values of Variables

Use the cursor keys to move between and edit the values. The square dot to the left of the variable that you solved for and left-rt disappear if you edit any variable. Select **SOLVE** to solve the equation again.

The Solver Instruction on a Command Line

The instruction **Solver** on the Home screen or in a program, which can be copied from the CATALOG, accesses the **SOLVER** feature.

Solver(equation,variable_name,guess,bound)

equation can be an equation or an expression (which is assumed equal to 0). variable_name is the name of the variable to solve for. guess is a real value or a list of two real values to use as a guess. bound is a list of two real values that bound the solution and is optional. -1E99 and 1E99 are used if not specified.

Values must be stored to every variable in the equation, except the one being solved for, before executing the instruction.

When the instruction is executed, the value of the variable for which you are solving is calculated and stored.

For example, **5→A:2→B:Solver(A=B+ln C,C,1)** displays **Done** and stores **20.0855369232** in **C**, but not **Ans**.

Exploring the Solution Graphically

You can examine the equation graphically. On the graph, you can see how many real solutions exist for the equation and use the cursor to select an initial guess.

The Graph

You can display a graph that plots the solution set to the equation. Place the cursor on the unknown variable and select (GRAPH). The unknown variable is plotted on the x axis; left-rt is plotted on the y axis. Solutions exist for the equation where the graph crosses the x axis.

Displaying the Graph

1. SOLVER uses the same RANGE and FORMT settings as the current graphing mode. You may select RANGE to display and edit the (RANGE) variables or mode. Select FORMT and choose graph format. The current x and y axes are based on the current graphing mode. The SOLVER does not display or affect the $y(x)$ or other graphing functions.
2. Select (GRAPH) to display the graph.



Exploring the Graph

To explore the graph further, you may:

- Use the free-moving cursor (Chapter 4). The coordinate value for the variable and left-rt are displayed.
- Select ZOOM. The menu keys are labelled with the ZOOM features (Chapter 4). Many ZOOM features are available in the SOLVER. After executing a ZOOM operation, press [2nd] to display the SOLVER menu.
- Select (TRACE). The panning and QuickZoom features (Chapter 4) are available in the SOLVER. Press [2nd] to display the SOLVER menu.

You can enter an initial guess and set the upper and lower bound of the solution to help the SOLVER find the solution, whether from the SOLVER edit screen, the SOLVER graph, or the Solver instruction. The ROOT and ISCT operations on the GRAPH MATH menu also use the SOLVER to find solutions.

Using the SOLVER

By selecting a bound and/or an initial guess, you can control the iterative SOLVER process to:

- Find a solution.
- Define which solution you want for equations with multiple solutions. (Use a close bound, in addition to initial guess, for best results when solving for a particular root.)
- Find the solution more quickly.

Bounding the Solution

The SOLVER seeks a solution only within a bound. On the SOLVER edit screen, the bound is displayed as **bound=(lower,upper)** and can be edited. On a graph, **lower** and **upper** are displayed as the upper and lower bound of the input line segment that is the set. You can enter values to **lower** and **upper** with **⏏**. The SOLVER automatically uses **lower** and **upper** to define the solution. The bound argument is specified, which does not change **lower** and **upper** manually.

Setting the Lower and Upper Bounds from a SOLVER Graph

When you select **GRAPH** from the SOLVER menu, the variables **lower** and **upper** (bound) are changed immediately to the values of **xMin** and **xMax**, if they are outside of **xMin** and **xMax**. If you zoom on a graph, **lower** and **upper** are changed to **xMin** and **xMax**.

To set the value of **lower** or **upper**, press **⏏** from the SOLVER graph and then select **LOWER** or **UPPER**. Move the cursor to the position you want for the bound. Press **⏏** to change the value in memory. A triangular indicator at the top of the screen shows the point.


Initial Guess

You may enter one or two initial guesses on the SOLVER edit screen. If no guess is given, **(upper-lower)/2** is used as the initial guess. On the SOLVER graph, you can move the cursor to set the initial guess. The third argument for the Solver instruction sets one or two initial guesses. The guess(es) must be within the bound.

Selecting a New Guess from a SOLVER Graph

Position the free-moving cursor or the TRACE cursor at the value you want to use as a new initial guess and select **SOLVE**. The result is displayed on the SOLVER edit screen.


Entering the POLY (Polynomial) Equation

 **POLY** accesses the POLY (polynomial) Root-Finding capabilities of the calculator. You can solve real or complex polynomials of up to 30th order.

Entering the Polynomial

1. Press  **POLY**. The POLY order screen appears.



2. Enter an integer between 1 and 30 (which can be an expression). Press . The coefficient entry screen is displayed. An example for a fourth-order polynomial is shown.



The equation is displayed on the top line for reference; you cannot edit it. The coefficients are used for POLY entry only; they do not update variables a_0 , a_1 , a_2 , etc.

3. Enter a real or complex value (which can be an expression) for the coefficient. Press .
4. Continue entering the coefficients.

Note: Select **CLRn** from the POLY editor menu to clear all of the coefficients. **CLR** clears only the line on which the cursor is located.


Note: If you press a key that accesses a menu, the POLY editor menu moves to the seventh line (if it is not already there), and the selected menu is displayed on the eighth line.

Solving the Polynomial

You can solve for all roots of the polynomial, real and complex.

Solving the Polynomial

Once you have entered all of the coefficients, select **SOLVE**. The roots of the polynomial are calculated and displayed. Results can be scrolled, if necessary. Results cannot be edited and they are not stored in variables.



Storing Values

You can store any value on the polynomial entry or results screen to a variable. Press **STO>** and enter the variable name after the **Names** prompt on the seventh line.

To store the coefficients of the polynomial in a list, select **STO>**, and then enter the name of the list.

Editing the Coefficients

You can edit the coefficients and calculate new solutions. Select **(COEFS)** to return to the coefficient entry screen.

The poly Function In an Expression

The **poly** function on the Home screen or in a program, which can be copied from the **CATALOG**, accesses the **POLY** (polynomial) root-finder feature.

poly a_list

a_list is a real or complex list containing the coefficients of the polynomial. When the expression is evaluated, the result is a list containing the solutions to the polynomial.

Entering SIMULT (Simultaneous) Equations


The **SIMULT** key accesses the Simult (simultaneous) Equations solving capabilities of the calculator. You can solve systems of up to 30 linear equations with 30 unknowns.

Entering the Equations

1. Press **[SIMULT]**. The **SIMULT** screen appears.



2. Enter an integer between 1 and 30 (which can be an expression) for the number of simultaneous equations. Press **[ENTR]**. The coefficient entry screen for the first equation appears. An example for a system of four equations and four unknowns is shown. The equation is displayed on the top line for reference; you cannot edit it.



3. Enter a real or complex value (which can be an expression) for the first coefficient, $a_{1,1}$. Press **[ENTR]**.
4. Enter all coefficients for the first equation. If you press **[ENTR]** after entering the last coefficient or select **<NEXT>**, the second equation is displayed. Enter the remaining coefficients.

<PREV> and **<NEXT>** move between equations. **[↑]**, **[↓]**, and **[ENTR]** move between coefficients and equations. **[CLR]** clears only the line on which the cursor is located. **<CLR>** clears the coefficients for the current equation.


Note: If you press a key that accesses a menu, the **SIMULT** editor menu moves to the seventh line (if it is not already there), and the selected menu is displayed on the eighth line.

Solving Simultaneous Equations

After you find the solutions to the simultaneous equations, you can store the results.

Solving the Equations

After entering the coefficients, select **SOLVE**.



Storing the Coefficients or Results

The results are displayed only; they cannot be edited and they are not stored in memory. The coefficients are used for **SIMULT** entry only; they do not update variables **a1**, **b1**, **x1**, etc.

- To store coefficients $a_{1,1}$, $a_{1,2}$, ..., $a_{n,n}$ into an $n \times n$ matrix, select **STOA**.
- To store coefficients b_1 , b_2 , ..., b_n into a vector of dimension n , select **STOB**.
- To store the results x_1 , x_2 , ..., x_n into a vector of dimension n , select **STOX**.

Storing a Single Value

You can store any value on the coefficients entry or results screen to a variable. Press **STO>** and enter the variable name after the **Name=** prompt.

Editing the Equation

You can edit the coefficients and calculate new solutions. Select **COEFS** to return to the first coefficient entry screen.

The **simult** Function in an Expression

The **simult** function on the **Home** screen or in a program, which can be copied from the **CATALOG**, accesses the **SIMULT** equation-solver feature.

simult(a_matrix,b_vector)

a_matrix is an $n \times n$ real or complex matrix containing the a coefficients. **b_vector** is an n -dimension real or complex vector containing the b coefficients. When the expression is evaluated, the result is an n -dimension vector containing the values of x .

Example: Simultaneous Equations


The **SIMULT** feature of the TI-85 can solve large systems of linear equations. Solve the 10 by 10 system below.

Problem

$$\begin{aligned} 4x_1 + 9x_2 + 7x_3 + 8x_4 + 3x_5 + 5x_6 + 9x_7 + 5x_8 + 8x_9 + 6x_{10} &= 3 \\ 8x_1 + 3x_2 + 5x_3 + 9x_4 + 9x_5 + 5x_6 + 4x_7 + 7x_8 + 0x_9 + 0x_{10} &= 7 \\ 1x_1 + 2x_2 + 8x_3 + 7x_4 + 7x_5 + 0x_6 + 3x_7 + 4x_8 + 1x_9 + 5x_{10} &= 9 \\ 4x_1 + 4x_2 + 1x_3 + 3x_4 + 0x_5 + 5x_6 + 7x_7 + 7x_8 + 2x_9 + 4x_{10} &= 6 \\ 7x_1 + 5x_2 + 0x_3 + 7x_4 + 0x_5 + 0x_6 + 1x_7 + 0x_8 + 1x_9 + 0x_{10} &= 5 \\ 2x_1 + 7x_2 + 1x_3 + 4x_4 + 4x_5 + 7x_6 + 5x_7 + 0x_8 + 0x_9 + 0x_{10} &= 1 \\ 2x_1 + 6x_2 + 1x_3 + 1x_4 + 1x_5 + 1x_6 + 7x_7 + 0x_8 + 1x_9 + 1x_{10} &= 5 \\ 4x_1 + 5x_2 + 0x_3 + 7x_4 + 0x_5 + 7x_6 + 9x_7 + 1x_8 + 0x_9 + 1x_{10} &= 0 \\ 2x_1 + 1x_2 + 9x_3 + 3x_4 + 8x_5 + 6x_6 + 9x_7 + 5x_8 + 7x_9 + 6x_{10} &= 0 \\ 9x_1 + 4x_2 + 3x_3 + 0x_4 + 9x_5 + 8x_6 + 8x_7 + 0x_8 + 1x_9 + 1x_{10} &= 0 \end{aligned}$$

Procedure

1. Press **(2nd)** **(SIMULT)**. Enter 10 for the number of equations.
2. Enter the coefficients for each of the equations in the coefficient editor.



3. Select **(SOLVE)**. The results are displayed.
4. Select **(STOA)**, **(STOB)**, and **(STOX)** to store the coefficients and results to **SA**, **SB**, and **SX**.



This chapter describes the TI-85 tools for entering and analyzing statistical data. These include entering data points in the STAT editor, calculating statistical results, performing regression analyses, and displaying statistical data graphically.

Chapter Contents	Statistical Analysis	15-2
	The STAT Statistical Menu	15-3
	Selecting and Loading Lists	15-4
	Loading Lists in the Editor	15-5
	Entering and Editing Data	15-6
	Calculating Statistical Results	15-8
	Statistical Results Display	15-9
	Statistical Results	15-10
	The GRAPH Menu	15-12
	Displaying Statistical Data	15-13
	Processing a Statistical Data Value	15-14
	Using STAT Operations on a Command Line	15-15
	Example: Analyzing Two-Variable Statistics	15-16

Statistical Analysis

The TI-85 analyzes one-variable and two-variable statistical data. Statistical data is stored in lists. Seven types of regression analyses are available to analyze statistical data.

One-Variable Statistics

One-variable statistics is used to analyze data with one measured variable. The optional **y** element is the frequency of occurrence of the associated **x** element. The **y** value must be an integer greater than or equal to zero or an error will result during the statistical results calculation.

Two-Variable Statistics

Two-variable statistics is used to analyze paired results between which there is a relationship. The **x** element is the value of the independent variable; the **y** element is the value of the dependent variable.

Statistical Data

A statistical analysis requires a set of data points (**x,y** pairs), each with an **x** value and a **y** value.

The data sets are stored in memory as two lists that can have user-assigned names. One list contains **x** values and the other contains **y** values.

- A pair of lists can be entered or edited as data points in the STAT editor (pages 15-4 to 15-7).
- A list can be entered, stored, and used from a command line (Chapter 12).
- A single list can be entered, stored, and edited element by element in the LIST editor (Chapter 12).

Statistical Analysis

When you perform a statistical analysis:

- The statistical results are calculated and stored in the result variables. You can display and use the contents of the current result variables, but you cannot store to them.
- The regression equation and the polynomial regression coefficients are calculated and stored for two-variable data.
- The list variables **xStat** and **yStat** are updated with the data from the lists used in the analysis.

Result variables always match the data in **xStat** and **yStat**. If you change **xStat** or **yStat** or edit any lists in the STAT editor, the result variables are cleared.

The STAT (Statistical) Menu

The STAT menu accesses the statistical editor, where you enter or edit lists, and commands to calculate and display statistical results, calculate regressions, draw (plot) statistical data, and forecast values based on the current regression equation.

The STAT Menu

When you press **STAT**, the menu keys are labelled with the statistical menu.

CALC	EDIT	DRAW	FCST	VARS
Accesses				
CALC	STAT list selection screen and menu of calculation instructions (page 15-8).			
	1-VAR P2REG	LINR P3REG	LNR P4REG	EXPR PWRR
EDIT	STAT list selection screen and editor, where you enter and edit data (page 15-4).			
DRAW	Menu of STAT drawing instructions (page 15-12).			
	HIST DrawF	SCAT STPIC	xyLINE RCPIC	DRREG CLDRAW
FCST	The forecast editor (page 15-14).			
VARS	Menu of statistical result variables (page 15-10).			
	\bar{x} Sy $\sum xy$ n	$\sum x$ RegEq PRegC	Sx $\sum x^2$ corr	\bar{y} $\sum y$ a b

Selecting and Loading Lists


To define new lists, edit existing lists, or calculate statistical results, you first must select the lists.

Selecting the List Names

1. From the STAT menu, either:

- Select (EDIT) to enter or edit lists.
- Select (CALC) to calculate statistical results.

The list-selection screen is displayed. The names of the lists must be exactly entered on the list-selection screen are displayed. **xStat** and **yStat** are the first two menu items. The other menu keys are labelled with the names of existing lists in alphabetical order.



2. Enter the name of the list of **x** values and then press **ENTER**. You can:

- Use the displayed name.
- Select an existing name from the menu, which replaces the name that is displayed.
- Type the name of a new or existing list of up to eight characters (case-sensitive). The keyboard is set to ALPHA-lock.

3. Enter the name of the list of **y** values and then press **ENTER**. Either:

- The **STAT** editor is displayed (page 15-6).
- The **CALC** menu is displayed (page 15-8).

Loading Lists in the Editor

Data points for statistical analysis can be entered in the STAT editor. You can select the names of existing lists to edit. You can enter data points to define new lists.

Loading the Lists

After you have selected the names of the lists, they are displayed in the STAT editor.

- If the lists are new, only the first data point is displayed. The x element is blank and the y element has a default value of 1.
- If the lists already exist, the contents are displayed.

If you load lists of unequal lengths, a warning message **list length mismatch** is displayed.


- To load the lists in the STAT editor, select (CONT). x elements are filled with 0's or y elements are filled with 1's in the shorter list.
- To leave the STAT application and return to the Home screen, select (EXIT).

Entering and Editing Data

After you have selected the names of the lists, you enter new data points and edit existing data points in the STAT editor. As you edit the data points, the lists that you are editing are changed in memory.

Editing Data Points with the STAT Editor

In the STAT editor, you enter or edit a pair of lists on a point-by-point basis. ↓ is displayed at the left of the fifth line if there are more than two data points. An example for two new lists is shown.









Enter new real values (which can be expressions) for the data points, as appropriate. The expression is evaluated when you move off the element or leave the editor.

If you change any data point in the editor, the current statistical results are cleared.

Note: If you press a key that accesses a menu, the STAT editor menu moves to the seventh line (if it is not already there), and the selected menu is displayed on the eighth line.

Moving around the STAT Editor

Key	Action
 	Moves the cursor within a list element.
 	Moves the cursor between list elements.
	Moves the cursor to the next list element.
(INS)	Inserts new data point (x,y pair) above the data point where the cursor is located.
(DEL)	Deletes both the x and y values of the data point where cursor is located.

Note: To move quickly to the final data point, press  from the first x value.

Sorting Lists

The TI-86 can sort the current data points into numerical order, from smallest to largest, based on either the x values or the y values.

- Select **(SORTx)** to sort based on the x values.
- Select **(SORTy)** to sort based on the y values.

The data points in the STAT editor are sorted and the elements in both the x list and the y list in memory are reordered correspondingly.

Note: To sort one of the lists without affecting the other list, use the **LIST sortA** or **sortB** instruction from the Home screen or from a program, or sort the list in the LIST editor.

Clearing Lists

To clear all data points in both lists, select **(CLRxy)** from the STAT editor menu.

- The data points in the STAT editor are cleared and only the first data point is displayed. The x value is blank and y has a default value of 1.
- The lists in memory are cleared.

Calculating Statistical Results

To calculate statistical results or to perform a regression analysis, first select the lists to use and then select the type of calculation using the STAT CALC instructions. Press **52** to move around the menu.

The STAT CALC Menu

After you select the lists to use in the calculation (page 15-4), the menu keys are labelled with the first five items of the statistical calculation menu.

1-VAR P2REG	LINR P3REG	LNRR P4REG	EXPR STREG	PWRR
Analysis			Regression Equation	
One-variable results			for $y = \text{integers} \geq 0$	
Linear regression			$y = a + bx$	
Logarithmic regression			$y = a + b \ln(x)$, for $x > 0$	
Exponential regression			$y = a \cdot b^x$, for $y > 0$	
Power regression			$y = a \cdot x^b$, for x and $y > 0$	
2nd-order polynomial regression			$y = a_2x^2 + a_1x + a_0$	
3rd-order polynomial regression			$y = a_3x^3 + \dots + a_1x + a_0$	
4th-order polynomial regression			$y = a_4x^4 + \dots + a_1x + a_0$	

* The coefficients a_4, \dots, a_0 are returned in the list **PRegC**; they do not update variables $a0, a1$, etc.

Notes about Statistical Calculations

For regression analysis, the statistical results are calculated using a least-squares fit. The transformed values used are:

- The linear model uses x and y .
- The logarithmic model uses $\ln(x)$ and y .
- The exponential model uses x and $\ln(y)$.
- The power model uses $\ln(x)$ and $\ln(y)$.

The polynomial models **P2REG**, **P3REG**, and **P4REG** use quadratic, cubic, and quartic polynomial least-squares regression (page 15-11).

Statistical Results Display

When you select the type of statistical calculation, it is calculated, the results are stored in the statistical result variables, and the most commonly referenced statistical result variables are displayed.

Calculating the Results

One-Variable Analysis


The results screens for 1-VAR, LINR, and P2REG for the lists $T0, T0^2, T0, T0^2, T0^3$ and $1, 3, 2, 3, 1$ are shown below.



Regression



Polynomial Regression



Continuing Calculations

To perform another type of statistical calculation on the same lists, select the type from the menu. The new calculation is performed immediately and the results are displayed.

Statistical Results

The TI-85 updates the statistical result variables when a one-variable or two-variable (but not polynomial) analysis is performed; you cannot store to them. These variables can be recalled using the STAT VARS menu (order shown below) or the VARS STAT (alphabetical order) screen.

The Statistical Result Variables

Variable Name	Meaning
\bar{x}	Mean of x values
σx	Standard x values
Sx	Sum of the squares of x values
\bar{y}	Sample standard deviation of x
σy	Population standard deviation of x
Sy	Mean of y values
$\sum x$	Sum of x values
$\sum x^2$	Sum of the squares of y values
$\sum y$	Sample standard deviation of y
$\sum y^2$	Population standard deviation of y
$\sum xy$	Sum of the product of x and y values
RegEq	Regression equation
corr	Correlation coefficient
a	y intercept of regression equation
b	Slope of regression equation
n	Number of data points
PRegC	Polynomial regression coefficients

One-Variable Results

After the 1-VAR instruction is executed, only the result variables \bar{x} , σx , Sx , \bar{y} , σy , and n have a calculated value and are valid in expressions. The other result variables are not valid and cause an error if used.

Two-Variable Results

After a two-variable regression model (other than a polynomial regression) is executed, all result variables are calculated and are valid in expressions.

corr, the correlation coefficient, measures the fit of the equation with the data points. In general, the closer corr is to 1 or -1, the better the fit. If corr is zero, then x and y are completely independent.

Storing Results

To store results, return to the Home screen and store from the command line. You can access the names of the statistical result variables from the STAT VARS menu or from the VARS STAT screen.

Using a Statistical Result Variable in an Expression	All statistical result variables, including RegEq (regression equation) and PRegC (polynomial regression coefficients), can be used in expressions. To use a statistical result variable in an expression, type in the name or use the STAT VARS menu or the VARS STAT screen to copy the name, or RCL the contents into the expression.
Displaying the Value of a Statistical Result Variable	To display the value of a statistical result variable, enter the name of the variable on a blank line on the Home screen and press ENTER . The value is displayed.
The Regression Equation	RegEq , the regression equation, has numeric values for all coefficients, not the variable names; for example, $3+5x$. The coefficients have up to 14 digits. When RegEq is evaluated, the current value of x is used.
Storing the Regression Equation	STREG (store regression) stores the current regression equation. When you select STREG , the cursor is positioned after Name= on the prompt line. Enter the name to which to store the regression equation. Press ENTER . The equation is stored to the equation variable. For example, select STREG and then type $y1$ ENTER to store the regression equation for graphing.
Polynomial Regressions	P2REG , P3REG , and P4REG (second, third, and fourth order polynomial regressions) perform a polynomial regression or a polynomial fit depending on the number of data points in the STAT lists. For example, P3REG performs a regression for 5 or more data points and a fit for 4 data points. The result for a polynomial regression is stored in PRegC (polynomial regression coefficients), a list containing the coefficients for the polynomial regression equation. For example, for P3REG , the result PRegC ={3 5 -2 7} would represent $y=3x^3+5x^2-2x+7$. PRegC is the only statistical result variable calculated for a polynomial regression.

The DRAW Menu

A STAT DRAW operation can be selected to display statistical data graphically. Lists $xStat$ and $yStat$ are used if current, otherwise the lists most recently selected for editing or calculating are used. Press \square to move around the menu. See Chapter 4 for information about graphing and drawing.

STAT Menu

When you select DRAW from the STAT menu, the current graph is displayed and the menu keys are labelled with the statistical drawing menu.

HIST DrawF	SCAT STPIC	xyLINE RCPIC	DRREG	CLDRW
---------------	---------------	-----------------	-------	-------

Item	Action
------	--------

HIST	Draws a histogram of one-variable data.
------	---

SCAT	Draws a scatter plot of the data points.
------	--

xyLINE	Plots and connects data points with lines.
--------	--

DRREG	Draws the regression equation (page 15-13).
-------	---

CLDRW	Clears all drawings on current graph.
-------	---------------------------------------

DrawF	Instruction that draws a function.
-------	------------------------------------

STPIC	Stores the current picture (page 15-13).
-------	--

RCPIC	Superimposes picture on graph (page 15-13).
-------	---

Histogram

HIST draws one-variable data as bar charts. The RANGE variable $xSci$ defines the width of the bars (up to 69 bars). A data value on the edge of a bar is counted in the bar to the right.

Scatter Plot

SCAT draws each data point as a coordinate.

Line Drawing

xyLINE draws each data point as a coordinate in the order they are in the data lists and connects the points with a line. You may want to use SORTX to sort the data first.

Clearing a Drawing

CLDRW displays the current graph with no drawn elements.

The DrawF Function

When you select DrawF, the instruction DrawF is copied to the Home screen. It draws a function in the current graphing MODE (Chapter 4).

Three instructions, HIST, SCAT, and xyLINE draw statistical data on the current graph. The regression equation resulting from a statistical regression analysis can be drawn on the current graph.

Before Drawing

The STAT DRAW instructions are tied closely to the GRAPH operations (Chapter 4).

- The current RANGE variables define the viewing rectangle. You may want to check and change the RANGE variables.
- Any currently selected functions will be plotted. You may want to edit, select, or unselect functions in the GRAPH editor.
- Any drawings on the current graph will display. You may want to select CLDRAW to clear any existing drawings and display the graph.

Drawing Statistical Data

To plot a graph of statistical data you have entered, select the type of drawing (HIST, SCAT, or xyLINE) from the STAT DRAW menu. If you have calculated a regression (or 1-VAR), xStat and yStat are used; otherwise the last lists edited are used.


Plotting Statistical Data and Regression Equations

DRREC (draw regression) draws the current regression equation on the current graph.

To compare statistical data graphically to more than one regression:

1. After you calculate each regression, in Func MODE, select (STORE) from the STAT CALC menu. Enter y n to the Name= prompt. The contents of the current regression equation are copied to the y(x) function.
2. Select SCAT from the STAT DRAW menu. The regressions will be plotted and then the points will be drawn on the same graph.

Storing and Recalling a Stored Drawing

The STPIC instruction stores the current picture as a named item. The RCPIC instruction superimposes the stored picture on the current graph. When you select (STPIC) or (RCPIC), the cursor is positioned after Name= on the prompt line. The menu keys are labelled with the names of existing pictures. Enter the name Press .

Forecasting a Statistical Data Value

The forecasting screen provides a simple method for forecasting either an x or a y value based on the current regression equation. An error is returned and you cannot enter FCST if there is not a current regression equation.

The Forecasting Screen

When you select (FCST) from the STAT menu, the forecasting screen is displayed. The current regression equation model is on the top line. You cannot move the cursor onto the equation.



Entering the x or y Value

1. You must enter a real value (which can be an expression) for either x or y .
2. Position the cursor on the variable for which you want to solve and select (SOLVE). The value, if any, in the variable is ignored; you need not clear it.

The solution is displayed on the same screen. A square dot in the first column indicates the variable for which you solved. FCST does not update the variables x , y , and Ans.

Further Solutions

You can continue to enter and forecast x and y values from this display.

Storing x and y

You can store either value in the FCST editor to a variable. With the cursor on the value to store, press (STO), type the variable name after the Sto prompt on the line above the menu. Press (ENTER).

Polynomial Regression

If the most recent calculation was a polynomial regression, then only y values can be forecast.

Using STAT Operations on a Command Line

You can access the statistical analysis capabilities of the TI-85 on the Home screen and in the program editor. Names of functions and instructions can be typed, selected from the CATALOG, or selected from the STAT menu in the program editor.

Using STAT Operations on the Home Screen or from ■ Program

To use a STAT operation on the Home screen or from a program, enter the name of the instruction or function:

- Type the name.
- Select the name from the CATALOG.
- In the program editor, you can select the name from ■ STAT menu.

Specifying the Lists

Sortx, **Sorty**, and the **CALC** and **DRAW** instructions can be entered with or without list arguments.

- If there are no arguments, **xStat** and **yStat** are used as the lists of *x* and *y* values.
- If the second argument is omitted, frequencies of 1 are assumed for **OneVar** calculations.
- If you enter arguments to the instruction, they specify the *x* list and *y* list to use. You can enter the names of lists, or copy the names from the STAT NAME or LIST NAME menus.
- You may type a list directly in the form: {1,2,3}. This is a temporary list; however, when a statistical analysis is performed, the list is stored in **xStat** or **yStat**.

Note: STAT lists must be real, not complex. The lists must be the same length.

The STAT Menu in the Program Editor

When you press **STAT** in the program editor, the menu keys are labelled with the program STAT menu.

CALC
Sortx

VARS
Sorty

DRAW

tcslx

tcsty

The STAT CALC Instructions

The **OneVar** instruction can have 0, 1, or 2 arguments:

OneVar, **OneVar** *x_list*, or **OneVar** *x_list*,*freq_list*

The **LnR**, **LnR**, **ExpR**, **PwrR**, **P2Reg**, **P3Reg**, and **P4Reg** instructions can have 0 or 2 arguments:

LnR or **LnR** *x_list*,*y_list*

If a statistical calculation is performed from the Home screen or from a program, the results screen is not displayed automatically; you must use the **ShwSt** instruction to display it.

The **ShwSt** instruction displays the current **OneVar** results or the most frequently used current regression results. **ShwSt** has no arguments.

When the instruction is executed, the results screen is displayed. In a program, if **Pause** (Chapter 16) is the next program command, the program halts temporarily for you to examine the screen. Execution resumes when you press **ENTER**.

The STAT CALC Menu in the Program Editor

The STAT CALC menu in the program editor is:

One-Var	LnR	LnR	ExpR	PwrR
P2Reg	P3Reg	P4Reg	ShwSt	

The STAT VARS Menu in the Program Editor

The STAT VARS menu lists the statistical result variables for use in expressions.

The STAT Forecast Functions

fcstx or **fcsty** returns a forecasted value for *x* or *y* based on the current regression equation. One argument, the known value, is required:

fcstx *y_value* and **fcsty** *x_value*

The STAT DRAW Instructions

Hist displays the current graph with the histogram. **Hist** can have 0, 1, or 2 arguments:

Hist, **Hist x_list** or **Hist x_list,F_list**

Scatter displays the current graph with a scatter drawing. **xyline** displays the current graph with a drawing of connected data points. **Scatter** and **xyline** can have 0 or 1 arguments:

Scatter or **Scatter x_list,y_list**

DrawF draws a function on the current graph. It requires one argument, an expression in terms of **x**:

DrawF expression

CIDrw clears all drawings on the current graph, but does not display the graph.

CIDrw has no arguments.

StPic stores the current graph picture as a named item. **RcPic** superimposes the stored picture on the current graph.

StPic pic_name or **RcPic** pic_name

The STAT DRAW

Menu in the Program Editor

The STAT Sort Instructions

The STAT DRAW menu in the program editor is:

Hist	Scatte	xyline	DrawF	CIDrw
StPic	RcPic			

Sortx sorts the elements in the specified existing lists as data points, according to their order in the **x** values. **Sorty** sorts based on the **y** values. The lists are changed in memory. If **xStat** or **yStat** are used for either list, the result variables are cleared.

Sortx x_list_name,y_list_name

Example: Analyzing Two-Variable Statistics

Find the best regression to fit the observed data by displaying the data graphically and then determining the best fit visually.

Problem

x	y	x	y
4.4	8.5	4.7	8.0
.4	-.9	-.6	3.5
-1.7	8.4	3.5	1.5
1.9	-1.9		

Procedure

1. Press **[STAT]**. Select **(EDIT)**. Enter the names of the lists, **XLIST** and **YLIST**. Enter the data points. Select **(SORT)** to order the points.
2. Return to the Home screen. Use the **min** and **max** functions from the **MATH NUM** menu to set meaningful **RANGE** values.
min(XLIST)→xMin
max(XLIST)→xMax
min(YLIST)→yMin
max(YLIST)→yMax
4. Press **[F6]** **CATALOG** **[F1]** (the keyboard is already in **ALPHA-LOCK**; this moves the cursor to the first command beginning with **F**). Press **(PAGE↓)** and copy **FnOff** to the Home screen and press **[ENTER]** to turn off all **y(x)** equations.
5. Press **[F5]** **DRAW** **xyLINE**. The seven observed points are plotted. Press **(CLEAR)** to clear the menus.
6. Press **[F2]** **CALC**. Press **[ENTER]** **[ENTER]** to accept the lists **XLIST** and **YLIST**.
7. Based on the scatter plot, select **(P2REG)**, which is the best regression to fit the data.
8. The regression equation is calculated and the polynomial coefficients stored in **PRegC**. Select **(STREG)** and store the regression equation in **y1**.
9. Press **[F5]** **DRAW** **xyLINE** to plot the regression equation on top of the points. Press **(ZOOM)** to view the entire graph.

Chapter 16: Programming

This chapter describes specific programming commands and how to enter and execute programs on the TI-85.

Chapter Contents	Using Programs	16-2
	Sample Program	16-4
	The PRGM Program Menu	16-5
	Entering and Editing a Program	16-6
	The I/O Input/Output Menu	16-9
	The Input/Output Instructions	16-10
	Phase 1: Control Menu	16-14
	The Control Instructions	16-15
	Creating Other Programs	16-19
	Using Application Operations in Programs	16-20

Using Programs

Most features of the TI-85 are accessible from programs. Programs can access all variables and named items. The number and size of programs that you can store are limited only by available memory.

Notes about Using Programs

On the TI-85, programs are identified in memory by names. Program names are governed by the same rules as variable names (Chapter 2).

A program consists of a series of program commands, which begin with a colon (:). A program command can be an expression or an instruction.

The TI-85 checks for errors during program execution, not as you enter or edit the program.

Variables are global. All variables can be accessed from all programs. Storing a value to a variable from a program changes the value in memory during program execution.

Programs update the variable Ans during program execution, just as expressions do on the Home screen.

Programs do not update Last Entry as each command is executed.

Menu in the Program Editor

When you display an application menu from the program editor (page 16-20), the menu may be reorganized. You see only the menu items that are allowed in programming (characters or the names of variables and functions or instructions).

Memory Management

The number of programs that you can store is limited only by available memory. Memory status is displayed on the MEM RAM screen. To increase available memory, delete variables and named items, including other programs, from the MEM DELE screen (Chapter 18).

To access the memory management menu, press **(2nd) [MEM]** from the Home screen.

Executing a Program To execute a program, begin on a blank line on the Home screen.

1. Enter the program name in one of the following ways:
 - Type the name (case-sensitive).
 - Copy the name from the VARS PRGM screen.
 - Copy the name from the PRGM NAMES menu.
2. Press **ENTER** and begin execution of the program.

While the program is executing, the busy indicator is displayed.

Note: There may be a brief pause the first time a program is executed while the TI-85 prepares to run the program.

**"Breaking" a
Program**

ON acts as a break during program execution. When you press **ON** to stop program execution, **ERROR 06 BREAK** is displayed on the error screen.

- To go to where the interrupt occurred, select **GOTO**.
- To return to the Home screen, select **QUIT**.

Erasing a Program

1. If you are in the program editor, press **2nd** **QUIT** to return to the Home screen.
2. Press **2nd** **MEM** and then select **DELET** to display the data types menu.
3. Select **PRGM**.
4. Move the cursor to the name of the program you want to delete and press **ENTER**.

Sample Program

A program is a set of commands that can be executed sequentially, as if the commands had been entered one at a time on the Home screen. The sample program below shows how a TI-85 program appears. The program instructions are explained in this chapter.

Sample Program

The program below creates a table by evaluating a function, its first derivative, and its second derivative, at intervals in the graphing range, stores the results in a matrix and displays them. Then the function, its derivative, and its integral are graphed and displayed for the user to trace.

The program I/O (Input/Output) instructions allow you to enter values and display results during program execution (page 16-9).

The program CTL (control) instructions make it easy to repeat or skip a group of commands during program execution (page 16-14).

```
PROGRAM:FUNCTABL
:Func:Fix 2:FnOff
:ZDecm
:FUNCTION=.5x cos x
:CILCD
:Eq>SI(FUNCTION,STRING)
:Disp "FUNCTION=",STRING
:{13,4}→dim MVALUES
:For(y,1,13)
:xMin→y*10:x→POINT
:POINT→MVALUES(y,1)
:evalF(FUNCTION,x,POINT)
→MVALUES(y,2)
:der1(FUNCTION,x,POINT)
→MVALUES(y,3)
:der2(FUNCTION,x,POINT)
→MVALUES(y,4)
:End
:Pause MVALUES
:y1=FUNCTION
:y2=der1(FUNCTION,x)
:y3=der2(FUNCTION,x)
:Trace
```

Name of program
Set MODE, turn off functions (GRAPH)
~~Set viewing rectangle (GRAPH)~~
Define the function (assignment statement)
Clear the display (I/O menu)
Convert equation to string (STRING)
Display the function (I/O menu)
Create matrix to contain table (MATRX)
Begin For loop (CTL menu)
Evaluate at every 10th x value
Store x value in column 1 of table
Store evaluated function in column 2 of table

Store value of first derivative in column 3 of table

Store value of second derivative in column 4 of table
End of For loop (CTL menu)
Display table
Graph the function
Graph the first derivative
Graph the second derivative
Display the graph to ~~GRAPH~~

The (Program) Menu

The PRGM menu accesses the names of all existing programs and the program editor, where you enter and edit programs.

The PRGM Menu


When you press , the menu keys are labelled with the program menu.

NAMES



Item	Accesses
NAMES	Menu of existing programs
EDIT	The program editor, where you enter and edit program commands (page 16-5).

Names of Programs

The PRGM NAMES menu displays the names of existing programs in alphabetical order. Press  to move around the menu. When you select an item, the name of the program is copied to the cursor location.

Entering and Editing a Program

In general, any command that can be executed from the Home screen can be included in a program, and vice versa. A program command always begins with a colon.

Selecting a Program

To enter a new program or edit an existing one, you first must select the program name. Program names follow the rules for variable names.


1. Select (EDIT) to display the program selection screen.



2. Enter the name of the program to edit. The keyboard is set in ALPHA-lock. The menu keys are labelled with the names of existing programs in alphabetical order.
 - Type the name of the program, new or existing, up to eight characters (case-sensitive).
 - Select the name from the menu.
3. Press **ENTER** to display the program editor.
 - For a new program, the name of the program and the colon at the beginning of the first command line are displayed.
 - For an existing program, the instructions in that program are displayed.

Entering Program Commands

The program editor displays the name of the program and the editor menu.



```
PROGRAM:FUNCTION
1: F1:=1+2:IF F1<0
2: GOTO 10
3: F1:=1+2:IF F1<0
4: GOTO 10
5: F1:=1+2:IF F1<0
6: GOTO 10
7: F1:=1+2:IF F1<0
8: GOTO 10
9: PAGE:PAGE+1:END
```

A colon indicates the beginning of each program command. Press **ENTER** to indicate the end of a command line. A command may be longer than one line on the screen; if so, it will wrap to the next screen line. **←** and **→** move the cursor to the beginning and end of the command line.

To enter more than one command on a command line, separate them with a colon (Chapter 1).

You can use the RCL feature (Chapter 2) to copy (insert) the contents of a variable into a program, and then edit the characters.

You can use the RCL feature to copy (insert) all of the commands of one program into another, and then edit the commands. You can use this feature to create templates for frequently used groups of instructions, such as setting RANGE variables.

In the program editor, if you press a key that accesses a menu, the program editor menu moves to the seventh line (if it is not already there), and the selected menu is displayed on the eighth line.

To enter comments in a program, enter the comments as a string, for example: "Test for change<.01"

Changing a Program Command	<p>To change a program command, move the cursor to the command.</p> <ul style="list-style-type: none">• Position the cursor and then make the changes.• Press CE to clear (blank out) the entire command line (the leading colon is not deleted), and then enter a new program command.
Inserting a Program Command	<p>INS (insert a command) inserts a blank command line above the command line where the cursor is positioned.</p>
Deleting a Program Command	<p>DEL (delete a command) is in the second set of menu items in the program editor menu.</p> <p>To delete a command line, move the cursor to anywhere on the line and select DEL. The entire command line (up to 100 characters), including any colons, is deleted.</p>
"Undoing" a Program Command	<p>You can use DEL and UNDEL to "cut and paste" a program command line.</p> <p>UNDEL (undelete) is in the second set of menu items in the program editor menu.</p> <p>You can "undelete" the last command line (up to 100 characters) that you deleted. Position the cursor where you want the command and select UNDEL. The command line, including the beginning colon, is inserted at the cursor position.</p>
Copying a Program Command	<p>You can "undelete" the last deleted command (up to 100 characters) more than once to copy it to other locations in the program, where you can edit it. You can "undelete" it into other programs, also.</p>
Leaving the Program Editor	<p>When you finish entering or editing a program, press Q (QUIT) to leave the program editor and return to the Home screen, in order to execute the program.</p>

The I/O (Input/Output) Menu

The PRGM I/O menu displays the program input/output instructions. Press **IO** to move around the menu. When you select an item from the menu, the name is copied to the cursor location.

The PRGM I/O Menu

When you select **IO** from the program editor menu, the menu keys are labelled with the first five items of the PRGM I/O menu.

Input InpSt	Prompt getKy	Disp CILCD	DispG PrtSc	Output
Item	Accesses			
Input	Instruction to enter and store values during execution or to use the free-moving cursor on a graph (page 16-10).			
Prompt	Instruction to prompt for entry of values for one or more variables (page 16-10).			
Disp	Instruction to display text, a value or the Home screen (page 16-11).			
DispG	Instruction to display the current graph (page 16-12).			
Output	Instruction to display text at a specified position on the display (page 16-12).			
InpSt	Instruction to enter and store a string during execution (page 16-12).			
getKy	Instruction to check the keyboard for a keystroke (page 16-13).			
CILCD	Instruction to clear the display (page 16-13).			
PrtScrn	Instruction to print the current screen on a printer connected to an IBMPC-compatible or MacintoshR computer (page 16-13).			
"	" character for entering display text.			

The Input/Output Instructions

The I/O instructions control input to and output from a program during execution. These instructions are on the PRGM EDIT I/O menu, which you access in the program editor.

The Input Instruction	<ul style="list-style-type: none">• If the input instruction has no arguments, it is used to explore a graph.• If the input instruction has one or two arguments, it is used to store a value to a variable.
The Input Instruction with Graphing	<p>Input with no arguments displays the current graph. You can move the free-moving cursor, which updates x and y (and r and θ in Polar/IC graph format). The dotted bar busy indicator displays. Press ENTER to resume execution.</p>
The Input Instruction with Variables	<p>Input with one argument (a variable name) displays a ? during execution. Enter a value and press ENTER. The value is stored to that variable, and the program resumes execution.</p> <p>Input variable_name</p> <p>Input with two arguments (a string of up to 21 characters to display as a prompt and a variable name) displays the string. Enter a value and press ENTER. The value is stored to that variable, and the program resumes execution.</p> <p>Input "string", variable_name</p>
The Prompt Instruction	<p>Prompt has one or more variable names as arguments. During execution the TI-85 displays each variable name, one at a time, followed by =?. Enter a value and then press ENTER for each variable. The values are stored, and the program resumes execution.</p> <p>Prompt variable1_name, variable2_name, . . .</p>
Notes	<p>If an expression is entered in response to Input or Prompt, the expression is evaluated and then stored.</p> <p>The y_c and other graphing variables are not valid arguments for Input or Prompt.</p>

- The **Disp** instruction:
- If **Disp** has no arguments, it displays the Home screen.
 - If **Disp** has one or more arguments, it displays text and values.

Displaying the Home Screen

Disp with no arguments displays the Home screen.


Displaying Messages and Values

Disp (display) with one or more arguments displays the value of each argument.

Disp value1,value2,...

If an expression is entered for the value, it is evaluated and then displayed according to the current **MODE** settings. String arguments display on the left of the current display line. Numerical values are displayed on the right of the following line.

For example, **Disp** "The result is",2 π displays



```
The result is
1.57079632679
```

If **Pause** (page 16-17) is the next program command, the program halts temporarily so you can examine the screen. Press **ENTER** to resume execution.

Note: If a value or string is too large to display in its entirety, ... is displayed in the rightmost column, but the value cannot be scrolled. (To scroll value, use **Pause** value instead.)


The Input/Output Instructions (Continued)

The DispG Instruction	<p>DispG (display graph) displays the current graph. If Pause (page 16-17) is the next program command, the program halts temporarily so you can examine the screen. Press ENTER to resume execution.</p> <p>DispG has no arguments.</p>
The Outpt Instruction	<p>Outpt (output) displays text or values beginning at a specific position on the display and typing over any existing characters. Outpt requires three arguments. The first argument is the line (1 to 8), the second argument is the column (1 to 21), and the third argument is a string or a value. Expressions are evaluated and values are displayed according to the current MODE settings. Matrices are displayed in entry format and wrap to the next line.</p> <p>Outpt(line,col,string) or Outpt(line,col,value)</p>
The InpSt Instruction	<p>InpSt (input string) is used to enter strings during execution.</p> <p>InpSt with one argument (a variable name) prompts with a ? . Enter the characters to be stored in a string and press ENTER. Do not enter the quotation marks. The string is stored to that variable, and the program resumes execution.</p> <p>InpSt variable_name</p> <p>InpSt with two arguments (a string of up to 21 characters and a variable name) displays the string. Enter the characters to be stored in the string variable and press ENTER. Do not enter the quotation marks. The string is stored to that variable, and the program resumes execution.</p> <p>InpSt string,variable_name</p> <p>Note: InpSt is used with the St>Eq instruction to input equations for graphing or solving. For example,</p> <p>InpSt "Enter function ",STRING:St>Eq(STRING,FUNCTION) in the sample program (page 16-4) lets the user enter the function.</p>

The Input/Output Instructions (Continued)

The getKey Function

getKey (got key) returns a number corresponding to the last key pressed, according to the diagram below. If no key has been pressed, it returns 0. **getKey** can be used inside loops to transfer control. **getKey** has no arguments.



Note: You can press **ON** at any time to act as a break during execution (page 16-3).

The CLCD Instruction

CLCD (clear LCD) clears the Home screen during execution and places the cursor in the upper left corner, but program execution does not pause unless **Pause** is the next command. **CLCD** has no arguments.

The PrtScr Instruction

PrtScr (print screen) prints the current screen on a printer attached to an IBM[®]-compatible or Macintosh[®] computer if you are using LINK-85 software (Chapter 19). The dotted bar busy indicator displays. Press **ON** to resume execution. **PrtScr** has no arguments.

PrtScr acts like **Pause** if you are not using LINK-85.

The CTL (Control) Menu

The PRGM CTL menu displays the program control instructions. Press **☞** to move around the menu. When you select an item from the menu, the name is copied to the cursor location.

The PRGM CTL Menu When you select CTL, the menu keys are labelled with the first five items of the menu.

If While IS>	Then Repeat DS<	Else Menu Pause	For Lbl Return	End Stop
Item	Instruction			
If	Instruction to create conditional test (page 16-15).			
Then	Instruction used with If instruction (page 16-15).			
Else	Instruction used with If-Then instructions (page 16-15).			
For	Instruction to create incrementing loop (page 16-18).			
While	Instruction to create conditional loop (page 16-18).			
Repeat	Instruction to create conditional loop (page 16-18).			
End	Instruction to signify end of a loop, If-Then, or Else (page 16-15).			
Menu	Instruction to define menu items and branches (page 16-17).			
Lbl	Instruction to define a label (page 16-17).			
Goto	Instruction to branch to a label (page 16-17).			
IS>{	Instruction to increment and skip if greater than (page 16-18).			
DS<{	Instruction to decrement and skip if less than (page 16-18).			
Pause	Instruction to pause program execution (page 16-18).			
Return	Instruction to return from a subroutine (page 16-18).			
Stop	Instruction to stop execution (page 16-18).			

The Control Instructions

The **PRGM CTL** (control) instructions direct the flow within an executing program. These instructions are on the **PRGM EDIT CTL** menu, which you access in the program editor.

The If Instruction

If is used for testing and branching. It has one argument: an expression defining a condition, frequently a relational test (Chapter 3).

If the condition is false (the argument evaluates to zero), the next program command is skipped. If the condition is true (the argument is nonzero), execution continues with the next program command. **If** instructions can be nested.

```
If condition
:command if true
:command
```

The If-Then Instructions

Then following an **If** instruction executes a group of commands if the argument is true. An **End** instruction identifies the end of the loop.

```
:If condition
:Then
:command if true
:command if true
:End
:command
```

The If-Then-Else Instructions

Else following **If-Then** instructions executes a group of commands if the argument is false. An **End** instruction identifies the end of the loop.

```
:If condition
:Then
:command if true
:command if true
:Else
:command if false
:command if false
:End
:command
```

The End Instruction

End identifies the end of a group of program commands. Each **For**, **While**, **Repeat**, or **Else** loop must have an **End** instruction at the "bottom," as must a **Then** loop without an associated **Else**.

The Control Instructions (Continued)

The For instruction	<p>For is used for looping and incrementing. It has four arguments: the name of the variable to be incremented, a beginning value, a maximum or minimum value not to be exceeded, and a real increment (optional; the default: 1). An End instruction identifies the end of the loop. For loops can be nested.</p> <pre>.For(variable_name,begin,end,increment) :command while end not exceeded :command while end not exceeded End :command</pre>
The While instruction	<p>While performs a group of commands while a condition is true. It has one argument: an expression defining a condition, frequently a relational test (Chapter 3). An End instruction identifies the end of the loop.</p> <p>The condition is tested when the While instruction is encountered. If the condition is true (the argument is nonzero), the program executes the next commands until an End instruction is encountered. If the condition is false (the argument evaluates to zero), the program executes the commands following the End instruction. While instructions can be nested.</p> <pre>.While condition :command while condition is true :command while condition is true End :command</pre>
The Repeat instruction	<p>Repeat repeats a group of commands until a condition is true. It is similar to the While instruction, but the condition is tested when the End instruction is encountered; thus the commands will always be executed at least once. Repeat instructions can be nested.</p> <pre>.Repeat condition :command until condition is true :command until condition is true End :command</pre>

The Menu Instruction **Menu** sets up branching within a program as selected from menu keys. The **Menu** instruction is executed during execution through the loop of the display activities. The specified menu items, the dotted bar, and cursor are displayed, and execution pauses until a menu key is pressed.

Menu can have up to 15 arguments: up to five sets of three arguments. The first argument in each set is the number of the menu key (1 to 5). The second argument is a string to display as the menu item, either the name of a string or text enclosed between ' marks. The third argument is the label to branch to if that key is pressed. Undefined menu items are blank.

Menu(n,string,label,... of 255,string,label)

For example, during execution the instruction
Menu(1,"a=1",A1,5,1,"a>1",A2,5,"a=0",A0) displays

```
| a=1 | a>1 | a=0 |
```

Then the program pauses until you press **[F1]**, **[F2]**, or **[F5]**. If you press **[F1]**, for example, the menu disappears and the program continues execution at the **Lbl A1** command.

The Lbl and Goto Instructions

Lbl (label) and **Goto** (go to) are used together for branching.

Lbl has one argument, which assigns a label to a program command. A label can be up to eight characters, following the rules for variable names.

Lbl label

Goto has one argument, a label to which to branch. The instruction transfers control to that label.

Goto label

The Control Instructions (Continued)


The IS> Instruction	<p>IS> (increment-and-skip) has two arguments: the name of a nanosystem variable and a real value not to be exceeded (which can be an expression). The instruction adds 1 to the variable; if the result is greater than the second argument, the next program command is skipped.</p> <p>IS>(variable_name,value) :command if variable ≤ value :command if variable > value</p>
The DS< Instruction	<p>DS< (decrement-and-skip) has two arguments: the name of a nanosystem variable and a real value which can be an expression. The instruction subtracts 1 from the variable; if the result is less than the second argument, the next program command is skipped.</p> <p>DS<(variable_name,value) :command if variable ≥ value :command if variable < value</p>
The Pause Instruction	<p>Pause suspends execution of the program so you can see results or debug. Pause can be used with no arguments or with one argument. The value of the argument is displayed and can be edited. While the program is paused, the instruction history continues to display. Press ENTER to resume execution.</p> <p>Pause or Pause expression</p>
The Return Instruction	<p>Return exits a subroutine and returns to the calling program (page 16-19), even if encountered within nested loops. Any loops are ended. There is an implied Return at the end of any program called as a subroutine. Within the main program, it stops execution and returns to the Home screen.</p> <p>Return has no arguments.</p>
The Stop Instruction	<p>Stop stops execution of a program and returns you to the Home screen.</p> <p>Stop has no arguments.</p>

Calling Other Programs

On the TI-85, any program can be executed as a program or called from another program to function as a subroutine. Enter the name of the program to use as a subroutine on a line by itself (as a command).

Calling a Program from Another Program

To call one program from another, enter the name of the program as a command:

- Type the name of the program (case-sensitive).
- Select the name from the VARS PRGM screen.
- Press  and select the name from the menu.

When this command is encountered during execution, the next command that the program executes is the first command in the second program. It returns to the subsequent command in the first program when it encounters either a **Return** instruction or the implied **Return** at the end.

```
PROGRAM:VOLCYL
:Prompt DIAM
:Prompt HT
:AREACIRC --
:VOL=AREA*HT
:Disp VOL
```

```
PROGRAM:AREACIRC
:RADIUS=DIAM/2
:AREA= $\pi$ *RADIUS2
:Return
```

Notes about Calling Programs

Variables are global. The same variable name in two programs or on the Home screen accesses the same location in memory. If you store a new value to a variable from a program, it is changed in memory. Any future references to that variable use the new value.

The **Goto** and **Lbl** arguments are local to the program in which they are located. A label in one program is not "known" by another program. You cannot use a **Goto** instruction to branch to a label in another program.

The **Return** instruction exits a subroutine and returns to the calling program, even if encountered within nested loops. There is an implied **Return** at the end of any program called as a subroutine.

Using Application Operations in Programs

In the program editor, you can access application menus to copy instructions, functions, and names to program commands. Some may require arguments.

Accessing Application Operations in the Program Editor

To enter the name of an instruction or function from an application in a program command:

- Type the name (not case-sensitive).
- Select the name from the CATALOG.
- Select the name from the application menu.

In the program editor, you can access items on application menus using keystrokes similar to those you used in the application. For example, in the program editor you can press [MATRX] [MATH] to access **del** on the MATRX MATH menu. Menu items that are not appropriate as instructions or functions (EDIT, for example) do not appear. Therefore, items may be arranged slightly differently.

Applications using full-screen editors, such as SOLVER, SIMULT, POLY and MATH INTER, can be accessed from programs as instructions or functions with arguments. Appendix A lists instructions, functions, and their arguments.

When you select the item, the name is copied to the cursor location.

Setting Modes and Formats from Programs

To set modes or graph formats in a program, enter the name of the mode or format as an instruction, preceded by a colon. You can type in the name, select it from the CATALOG, or select it from the MODE or GRAPH FORMT screen.

To select the name from the MODE or GRAPH FORMT screen, from the program editor press [2nd] [MODE] or [2nd] [FORMT], place the cursor on the mode or format that you want to set, and press [ENTER]. The name is copied to the cursor location.

Note: If you select the number of digits for fixed mode, the instruction **Flx n** is copied to the cursor location.

Chapter 17: Applications

This chapter contains application examples that incorporate features described in the preceding chapters. Two of the examples use a program.

Chapter Contents	Characteristic Polynomial and Eigenvalues	17-2
	The Fundamental Theorem of Calculus	17-4
	Symmetry of the Roots of a Complex Number	17-6
	Fractions and Matrices	17-7
	Finding the Area between Curves	17-8
	Measuring the Solid of Revolution	17-9
	Electrical Circuits	17-10
	Universal Equation	17-12
	Program: Taylor Series	17-14
	Program: Sierpinski Triangle	17-16

Characteristic Polynomial and Eigenvalues

Use the matrix and graphing features of the TI-85 to explore the relationship between the characteristic polynomial and eigenvalues of a matrix.

Procedure

1. On the Home screen or using the matrix editor, enter matrix A:
$$\begin{bmatrix} 2 & 2 & 1 & 4 \\ 3 & -2 & 3 & 6 \\ 7 & -2 & 6 & 0 \\ -5 & 2 & 6 & -2 \end{bmatrix}$$
2. The characteristic polynomial is defined as $\det(A - X \cdot I)$. To graph the polynomial, in Func MODE press $\boxed{\text{GRAPH}}$, select $y(x)=$, select (ALL) to turn off all functions, and then enter:
 $y1 = \det(A - x \cdot \text{Ident } 4)$
3. Select (RANGE). For exploration with TRACE and the free-moving cursor, you can enter expressions for xMax and yMax to set nice values of Δx (.2) and Δy (100) directly from the RANGE screen.
 $xMin = -10$ $yMin = -2500$
 $xMax = -10 + .2 \cdot 126$ $yMax = -2500 + 100 \cdot 62$
 $xScl = 10$ $yScl = 500$
4. Select (ROOT) from the GRAPH MATH menu and find both real roots.



Calculator
(Continued)

- Return to the Home screen and solve for the eigenvalues directly:
elgVl A

There are two real and two complex eigenvalues. Compare the real eigenvalues with the real roots found in step 4.

- 2ND** **MEMO** and select (TRACE). Choose five integer points on the function, for example:

-2	-87.2
0	-94.1
2	-106.0
4	-124.0
5	-155.0

- Press **500** and enter the coordinates into lists **AX** and **AY** in the STAT editor.
- Select (CALC), specify lists **AX** and **AY**, and then select (P4REG). This gives a unique fourth-order polynomial that contains these points.
- MODE** **2ND**. Select **y(x)=** and enter:
y2=pEval(PRegC,x)
- Select (TRACE) and compare **y1** and **y2**.
- Return to the Home screen and find the roots of the **PRegC** polynomial:
poly PRegC
- Compare the results to the values found in steps 4 and 5.

The Fundamental Theorem of Calculus

The TI-85 can graph functions that are defined by integrals or derivatives.

Problem 1

Demonstrate graphically that

$$F(x) = \int_1^x \frac{1}{t} dt = \ln(x), \quad x > 0 \quad \text{and that}$$
$$D_x \left[\int_1^x \frac{1}{t} dt \right] = 1/x$$

Procedure 1

1. Press $\boxed{\text{2nd}}$ [TOLEF] and set tol=1 and $\delta=.01$.
2. In Func MODE, press $\boxed{\text{GRAPH}}$. Select RANGE. Set the RANGE variables:

xMin=.01	yMin=-1.5
xMax=10	yMax=2.5
xScl=1	yScl=1
3. Select FORMT. Select SimulG.
4. Select $y(x)=$, select (ALL-) to turn off all functions, and then enter:
 $y3=\text{fnInt}(1/t,1,x)$
 $y4=\ln x$
5. Select TRACE. The busy indicator displays while the graph is being plotted. Use the cursor keys to compare the values of the two graphed functions, y3 and y4.
6. Select $y(x)=$, select (ALL-) to turn off y3 and y4, and then press $\boxed{\text{2nd}}$ [TOLEF]:
 $y5=\text{nDer}(y3,x)$
 $y6=1/x$
7. Select TRACE. The busy indicator displays while the graph is being plotted. Again, use the cursor keys to compare the values of the two graphed functions, y5 and y6.

Problem 2 Explore the functions defined by

$$y = \int_{-2}^x t^2 dt, \int_0^x t^2 dt, \text{ and } \int_2^x t^2 dt$$

Procedure 2

1. Press **2ND**, select **y(x)=**, and select **(ALL)** to turn off all functions. On the TI-85, the three functions above can be defined simultaneously by:
y7=fnInt(t²,t,(-2,0,2),x)
2. Select **FORMAT**. Select **SeqG**.
3. Select **(ZSTD)** from the **GRAPH ZOOM** menu.
4. Select **(TRACE)**. Notice that the functions appear identical, but, shifted vertically by a constant.
5. Select **y(x)=**, select **(ALL)** to turn off **y7**, and then enter:
y8=nDer(y7,x)
6. Select **(TRACE)**. Notice that although the three graphs defined by **y7** are unique, they share the same derivative

Symmetry of the Roots of a Complex Number

Find the cube roots of 1.2). The n th roots of a complex number (a,b) are evenly spaced on a circle of radius $\text{abs}(a,b)^{(1/n)}$, centred at the origin. In fact, all roots of a complex number are defined for $k=0,1,\dots,n-1$ by

$$(a,b)^{(1/n)} = \text{abs}(a,b)^{(1/n)} \cdot e^{i((0,\text{angle}(a,b)+2k\pi)/n)}$$

Procedure

1. In Func MODE, press **GRAPH**. Select **y(x)=** and select **ALL** to turn off all functions.

2. Select **RANGE**, set **yMin=-2**, **yMax=2**, **xMin=-2**, and **xMax=2**, and then select **ZOOM** (**ZSQR**) to set the aspect ratio.

3. On the Home screen, enter and execute these instructions.
The first four instructions initialize values to set up the problem. The next instruction stores the expression that defines the first root, which is a complex number when it is evaluated.

```
1→K:3→N:1→A:2→B:P1=ab  
■(A,B)^(1/N)*e^i((0,angle(A,B)+2*K*pi)/N):  
PtOn(real P1,imag P1)  
:K+1→K
```

The last instruction draws the root as a point.

4. On the Home screen, press **2ND** (**ENTRY**) to recall Last Entry. Delete the first instruction **1→K**.
5. Press **ENTER** to execute all the commands again. The second point is drawn.
6. Return to the Home screen. Press **2ND** (**ENTER**) to execute all the commands again. Repeat until all \blacksquare points are drawn.
7. Press **GRAPH** (**DRAW**) (**CIRCLE**).
8. Press **ENTER** to set the centre of the circle at the origin, then move the cursor to one of the points. Press **ENTER** again. The circle is drawn, intersecting all points.
9. Select **CLEAR** from the **DRAW** menu. Return to the Home screen. Recall Last Entry. Insert the instruction **1→K** at the beginning. Change **N** (number of points) to **10**. Press **ENTER**. Repeat steps 4 to 8.

Fractions and Matrices

The TI-85 has the capability to compute and display fractions.

Procedure

1. In the **MATRIX** editor, enter matrix **A**:
$$\begin{bmatrix} 0 & 4 & 5 & 7 \\ 9 & 7 & 0 & 7 \\ 1 & 2 & 1 & 3 \\ 7 & 4 & 0 & 0 \end{bmatrix}$$
2. On the **Home** screen, augment the identity matrix to **A** and find A^{-1} using the **rref** function.
`rref aug(A,ident 4)`
3. Display the solution portion of the result matrix as a fraction using the **▸Frac** instruction.
`Ans(1,5,4,8)▸Frac`
$$\begin{bmatrix} 14/25 & 16/25 & -14/5 & -7/25 \\ -49/50 & -28/25 & 49/10 & 37/50 \\ 31/50 & 7/25 & -21/10 & -3/50 \\ 13/50 & 11/25 & -13/10 & -19/50 \end{bmatrix}$$
4. Check the result by computing $A^{-1} \cdot A$.
`round(Ans*A,0)`
$$\begin{bmatrix} 1 & 0 & 0 & 0 \\ 0 & 1 & 0 & 0 \\ 0 & 0 & 1 & 0 \\ 0 & 0 & 0 & 1 \end{bmatrix}$$

Finding the Area between Curves

Find the area of the region bounded by

$$f(x) = 300x/(x^2 + 625)$$

$$g(x) = 3 \cos 0.1x$$

$$x = 75$$

Procedure

1. In Func MODE, press $\boxed{\text{2ND}} \boxed{\text{Y=}}$, select $y(x)=$, select (ALL-) to turn off all functions, and enter:
 $y9=300x/(x^2+625)$
 $y10=3 \cos .1x$
2. Select (RANGE). Set the RANGE variables:
 $xMin=0$ $yMin=-5$
 $xMax=100$ $yMax=10$
 $xScl=10$ $yScl=1$
3. Select (GRAPH).
4. Select (MATH) (F5) (F6). Move the TRACE cursor near the intersection of the functions. Press $\boxed{\text{F5}}$ to select $y9$. The cursor moves to $y10$. Press $\boxed{\text{F6}}$. The solution uses the SOLVER. The cursor location is used as an initial guess. The value of x at the intersection, which is the lower limit of the integral, is stored in Ans and x .
5. Return to the Home screen. To see graphically the area you are going to integrate, enter:
 $\text{Shade}(y10,y9,Ans,75)$



6. Press $\boxed{\text{2ND}} \boxed{\text{F5}}$ (TOLER) and set $\text{tol}=1E-5$. Return to the Home screen and compute the integral.
 $\text{fnInt}(y9-y10,x,Ans,75)$
The area is 325.839961996

Minimizing the Solid of Revolution

Consider the solid of revolution determined by revolving the regions bounded by the line $y=c$ for $0 \leq x \leq 1$ and the curve $y=\sin x$ for $0 \leq x \leq \pi$ about the line $y=c$. Find the value of c that minimizes this volume and the minimum volume.

Problem



1. Let $a=\sin^{-1} c$ and $b=\pi-\sin^{-1} c$. From visual inspection, the problem can be divided into three intervals: 0 to a , a to b , to π . For any value of c , $0 \leq c \leq 1$, the volume of the solid of revolution is given by

$$V = \int_0^a \pi(c - \sin x)^2 dx + \int_a^b \pi(c - \sin x)^2 dx + \int_b^\pi \pi(c - \sin x)^2 dx$$

2. By symmetry around $\pi/2$, the volume simplifies to

$$V = 2 \cdot \left(\int_0^a \pi(c - \sin x)^2 dx + \int_a^{\pi/2} \pi(c - \sin x)^2 dx \right) = 2\pi \cdot \int_0^{\pi/2} (c - \sin x)^2 dx$$

3. Press **2nd** **TOLER** and set **tol**=1E-5
4. Press **2nd** **MODE**. Select **type**= and select **(ALL)** to turn off all functions. On the TI-85, **x** is the independent variable for function graphing, so substitute **t** for **x** and **c** for **y**:

$$y1=2\pi\int\sin t((x-\sin t)^2,1,0,\pi/2)$$

5. Select **(RANGE)**. Set the **RANGE** variables.

$$\begin{array}{ll} xMin=0 & yMin=0 \\ xMax=\pi & yMax=5 \\ xScl=.5 & yScl=1 \end{array}$$

6. Select **(FMIN)** from the **GRAPH MATH** menu. The busy indicator displays while the function is plotted.
7. Press **2nd** **ENTER** to select **y1**. The busy indicator displays and the solutions are displayed at the bottom. The minimum volume occurs at $x=.63662089163$ ($c=2/\pi$). It is $y=.93480220056$ ($V(c)=\pi^2/2-4$).

Electrical Circuits

Use the list and statistical drawing features of the TI-85 to analyze an unknown electrical circuit.

Problem

The d.c. current in milliamperes (CURR) and voltage in volts (VOLT) data shown was measured on an unknown circuit in a "black box." Calculate power in milliwatts.

What is the average of the measured power?

Estimate the power in milliwatts at a current of 125 ma using three TI-85 features: free-moving cursor, interpolate, and regression forecast.

CURR (ma)	V (volt)
10	2
20	4.2
40	10
60	18
80	32.8
100	56
120	73.2
140	98
160	136

Procedure

1. Press **2ND** **LIST**. Use the list editor to enter list CURR.
2. Press **2ND** **LIST**. Use the list editor to enter list VOLT.
3. Press **2ND** **QUIT** to return to the Home screen.
4. Calculate and store values for power. Use the LIST editor, the STAT editor, or display the lists on the Home screen to see the results.

CURR*VOLT→POWER

5. Press **2ND** **RANGE**. Set the RANGE variables:

xMin=0	yMin=0
xMax=max(POWER)	yMax=max(CURR)
xScl=1000	yScl=10

Procedure (Continued)

8. Return to the Home screen. Plot the pairs.
FnOff
xyLine POWER,CURR
7. Use the free-moving cursor to estimate **POWER** at **CURR=125**
8. Press **2nd** (MATH) and select **INTP0**. To interpolate **POWER** at **CURR=125** enter the nearest pairs: **x1=POWER(7)**, **y1=CURR(7)**, **x2=POWER(8)** and **y2=CURR(8)**. Enter **y=125** and solve for **x**.
9. Press **STAT**, select (CALC) and specify lists **POWER** and **CURR**. Calculate each of the regression types in turn to determine which gives the best value of **corr** (PWR).
10. Execute the best regression again. Select (FCS7). To forecast **POWER** at **CURR=125**, enter **y=125** and solve for **x**. Compare to your answers from steps 7 and 8.



Unusual Equation

Using the SOLVER or GRAPH MATH operations, you can easily solve problems that are difficult or impossible to solve analytically.


Problem

Solve for x

$$\int_0^x \frac{\sin t}{t} dt = 1.8$$

Procedure

1. On the Home screen, enter:
`y12=intt(sin t/t,0,x)`
 2. On the TOLERANCES editor, set `tol=1`.
 3. On the SOLVER editor, define `eqn` as:
`y12-1.8`
 4. On the SOLVER variables screen, enter 0 as your initial guess for x , and select (SOLVE). (It is a dummy variable of integration and may be any value; use 1.) The busy indicator displays while the solution is calculated.
 5. Select (RANGE). Change the RANGE variables:

<code>xMin=0</code>	<code>yMin=-.5</code>
<code>xMax=10</code>	<code>yMax=.5</code>
<code>xSol=1</code>	<code>ySol=1</code>
 6. Select (GRAPH). The value of `left-rt` for each value of x is plotted. Notice that the problem has at least two solutions.
- 

7. Move the cursor near the solution that you did not find in step 4. Press (SOLVE) to calculate the second solution using the cursor location as your initial guess

8. Press **GRAPH** ($y(x)=$). Notice that $y12$ contains the expression stored from the Home screen in step 7. Enter $y13=1.8$.
9. Select **RANGE**. Set the **RANGE** variables:

xMin=0	yMin=0
xMax=10	yMax=2
xScl=1	yScl=.1
10. Select **FORMAT**. Select **SimulG**.
11. Select **DSECT** from the **GRAPH MATH** menu.



12. Move the cursor to one of the intersection points and press **ENTER** to select the function.
Hint: You can **TRACE** more quickly by placing the cursor on function **y13**. Use **F2** for the function evaluation for each **x** is faster.
13. Press **F2** to select the other function. The busy indicator (a squiggle) will momentarily not be displayed.
14. Repeat for the other intersection. Compare the solutions.

Program: Taylor Series

This program lets the user enter a function and specify the order and centre point, calculates the Taylor series approximation for the function, and plots them both. It demonstrates several CTL and I/O statements.

Instructions

1. Enter the program to store the Mobius series. This program will be executed from the TAYLOR program as a subroutine.

```
PROGRAM:MOBIUS
```

```
:(1,-1,-1,0,-1,1,-1,0
```

```
:(0,1,-1,0,-1,1,1,0,-1
```

```
:(0,-1,0) -MSERIES
```

```
:Return
```

2. Enter the program to calculate the Taylor series.

```
PROGRAM:TAYLOR
```

```
Func:FncOff
```

```
:y14=peval(TPOLY,x-co  
nter)
```

```
:1E-9=>eL3->rr
```

■ ■ on CHARS MISC menu

```
:CILCO
```

```
:InpSt "FUNCTION: ",E
```

User enters y(x) function

```
Q
```

```
St>Eq(EO,y13)
```

```
:Input "ORDRE: ",orde
```

User enters order

```
r
```

```
:order+1 -dimL TPOLY
```

```
Ffill(0,TPOLY)
```

```
:Input "CENTRE: ",cen
```

User enters centre

```
ter
```

```
:evalF(y13,x,center) -
```

```
f0
```

```
:f0 -TPOLY(order+1)
```

```
:If order:1
```

```
:der1(y13,x,center) -T
```

```
POLY(order+)
```

```
:If order:2
```

```
:der2(y13,x,center)/2
```

```
:TPOLY(order+1)
```

```
:If order:3
```

```
:Then
```

Begin Then group

```
:MOBIUS
```

Call as subroutine

```
:For(1,3,order,1)
```

Begin For group

```
:abs f0 -gmax:gmax -bm1
```

```
:1 ->m:0 ->ssum
```

:While max bml>= *gmax	Begin max group
:While M SERIES(m)=0	Begin While group
:m+1 → m	
:End	End max group
:0 → bsum	
:For(1,m',1)	Begin For group
:rr*e^(2*(g/(m^n))*(0	
.1))+(center,0) → x	
real y13 → gval	
:bsum+gval → bsum	
:max(abs gval,gmax) → g	
max	
:End	End For group
:bsum/(m'!)-10 → bml	
:ssum+M SERIES(m)*bml →	
ssum	
:m+1 → m	
:End	End While group
:ssum/(rr^*) → TPOLY(or	
der+1-N)	
:End	End For max
:End	End Then group
max	

3. Return to Home screen, execute program TAYLOR
4. When prompted, enter the function, order, and centre of the series approximation.

Note: The higher-order derivative values necessary for this program are calculated numerically based on the methods in J. N. Lyness and C. B. Moler, "Numerical Differentiation of Analytic Functions," SIAM Journal of Numerical Analysis 4(1967): 202-210.

Program: Sierpinski Triangle

This program creates a drawing of a famous fractal, the Sierpinski Triangle, and stores the drawing in a picture variable, **TRIANGLE**.

Answer Key

1. Enter the program:
PROGRAM:SIERPIN
:FnOff
:CIDrW
:0→J
:0→xMin
:1→xMax
:0→yMin
:1→yMax
:rand→x
:rand→y
:While(J=3000)
:rand→N
:If N<(1/3)
:Then
:5x→x
:5y→y
:PtOn(x,y)
:End
:If N<(1/3) and N<(2/3)
3)
:Then
:5(.5+x)→x
:5(1-y)→y
:PtOn(x,y)
:End
:If N<(2/3)
:Then
:5(1-x)→x
:5y→y
:PtOn(x,y)
:End
:J+1→J
:End
:StPic TRIANGLE
2. Return to Home screen, execute program **SIERPIN**.

Note: After executing this program, you can recall and display the picture **TRIANGLE**.

Chapter 18: Memory Management

This chapter describes how to manage memory on the TI-85. To increase the amount of memory available for use in new applications, occasionally you may want to delete from memory items that you are no longer using.

Chapter Contents	The MEM (Memory) Menu	18-2
	Managing Memory	18-3
	Deleting Items from Memory	18-4
	Resetting the TI-85	18-5
	Leaving the Memory Management Screen	18-6

The MEM (Memory) Menu

The **MEM** menu accesses memory management, where you display the amount of memory available and used, delete variables, clear memory, or reset the calculator.

The MEM Menu

When you press **MEM** (MEM), the menu keys are labelled with the memory menu.

RAM	DELET	RESET				
Item	Accesses					
RAM	Displays the amount of RAM available and used, by type of named item (page 18-3).					
DELET	Allows you to access named items by data type to delete (page 18-3)..					
	ALL	REAL	CPLX	LIST	VECTR	
	MATRX	STRNG	EQU			
		PIC	STAT			
RESET	Allows you to delete all named items, reset defaults, or both (page 18-5).					

Deleting Items from Memory

Any item that you have created and named can be deleted from memory from the DELETE screen.

Deleting Individual Named Items

1. Press **[2nd]** **[MEM]** to display the memory management menu.
2. Select **(DELETE)**. The DELETE screen and menu temporarily replace the screen on which you are working.

ALL	REAL	CPLX	LIST	VECTR
MATRX	STRNG	EQU	CONS	PRGM
GDB	PIC	STAT		

3. Select the data type. The names of the variables in that data type are displayed in alphabetical order.



4. An arrow at the left of the name indicates the selection cursor. To move around the list:
 - Press a letter to move quickly to function names beginning with that letter. (The keyboard is set in ALPHA-lock.)
 - Use **(PAGE←)** and **(PAGE→)** to move to the next screen of **variables**.
 - Use **↑** and **↓** to move up and down the list.
5. Select **(ENTER)** to delete the item that the cursor is on. The item is deleted immediately.

You may continue to select single items to delete.

Note: You cannot delete **xStat**, **yStat**, **PRgC**, or **RegEq**. To delete a parametric equation, delete the **xtn** component.

Resetting the TI-85

Resetting the TI-85 restores memory to the factory settings. Because there are other operations that clear only selected portions of memory, the TI-85 should need to be reset only under special circumstances.

Resetting the Calculator

To reset the TI-85:

1. Press **[2nd]** (**MEM**) to display the memory management menu.
2. Select **(RESET)**. The menu keys are labelled with the **RESET** menu.

ALL MEM DFLT5

3. Make the appropriate menu selection.
 - To reset both memory and defaults, select **(ALL)**.
 - To clear only values stored in memory, including programs, graph databases, and pictures, but leave the defaults as you have them set, select **(MEM)**.
 - To return the defaults to the factory settings, but leave values stored in memory, select **(DFLT5)**.
4. The message **Are you sure?** is displayed.
 - If you do not want to reset, select **(NO)**. You are returned to the Home screen.
 - If you want to reset, select **(YES)**. The TI-85 is reset and the messages **Mem cleared** and/or **Defaults set** are displayed on the Home screen.

Leaving ■ Memory Management Screen

You can leave any memory management screen at any time.

Leaving a Memory Management Screen

To leave any memory management screen or menu:

- Press the appropriate keys to go to an application.
- Press **[EXIT]** (QUIT) to return to the Home Screen.

Chapter 19: Communications Link

The TI-85 has a port to let you communicate with another TI-85 or with a PC or Macintosh®. This chapter describes how to communicate with another TI-85.

Chapter Contents	The TI-85 Link	19-2
	Selecting Items to Send	19-3
	Transmitting Items	19-5
	Receiving Items	19-6
	Backing Up Memory	19-7
	Example	19-8

The TI-85 Link

The TI-85 communication capability lets you share variables and programs or entire memory contents with another TI-85. You also can share TI-85 variables, programs, or memory backup with a PC and print TI-85 screens on a printer connected to a PC.

-
- Linking Two TI-85s** The software to communicate between two TI-85s is built into the TI-85. The instructions are given in this chapter. The cable to link two TI-85s comes with the TI-85.
- Linking a TI-85 to a PC or Macintosh** An optional accessory, LINK-85, allows a TI-85 to communicate with a personal computer. To obtain the special cable, computer software (for either an PC-DOS compatible computer or a Macintosh[®] computer), and the instruction booklet, contact your local Texas Instruments Repaire.

- Connecting the TI-85 Link Cable** The TI-85 Link port is located at the centre of the bottom edge of the calculator.

1. Insert either end of the cable into the port firmly.
2. Repeat with the other TI-85.

- The LINK Menu** When you press **[2nd]** **[LINK]**, the screen is cleared and the menu keys are labelled with the LINK menu.

SEND

RCV

Menu

Meaning

SEND

Accesses a menu of types of data to send.

RCV

Puts calculator in mode to receive.

- Leaving a LINK Screen or Menu**
- From **SEND** mode, press **[2nd]** or **[2nd]** **[QUIT]**.
 - From **RCV** mode or while transmitting, press **[ON]** to interrupt and then **[EXIT]** to leave the **ERROR** screen.
 - From an **ERROR** screen, select **[EXIT]** to leave the **ERROR** screen.
 - After transmitting, press **[2nd]** or **[2nd]** **[QUIT]**.

Selecting Items to Send

You can send individual items (variables), all items, groups of items, or a memory backup from one TI-85 to another. To transmit from the TI-85, you first select what you want to send. The transmission does not begin until you select **XMIT** from the menu.

The SEND Menu

When you select **SEND**, the menu keys are labelled with item types. Press **WIN** to move around the menu.

BACKUP	PRGM	MATRX	GDB	ALL
LIST	VECTR	REAL	CPLX	DATA
CONS	PIC	RANGE	STRNG	

- You can transmit individual items (variables).
- You can transmit all items.
- You can transmit groups of items.
- You can transmit an exact image of memory.

Selecting items within a Type

When you select a variable type, the **SEND** selection screen is displayed. It lists the names of the variables in alphabetical order. (If there are no variables of the type selected, the message **NO VARS OF THIS TYPE** is displayed.)



An arrow at the left of the name indicates the selection cursor. Use **Y** and **A** to move the cursor.

- **SELECT** reverses the selection status of the name where the cursor is located. Selected names are marked with a square dot.
- **ALL+** selects all variables of this type.
- **ALL-** unselects all variables of this type.

Selecting Items to Send (Continued)

The RANGE Items

If you select (RANGE), the selection screen is:



Use the menu keys to select the graphing mode(s) that you want to send. The variables that will be sent are:

- For **Func**, all variables on the **Func RANGE** screen, plus lower and upper, plus the **FORMT** settings.
- For **Pol**, all variables on the **Pol RANGE** screen, plus the **FORMT** settings.
- For **Param**, all variables on the **Param RANGE** screen, plus the **FORMT** settings.
- For **DfEq**, all variables on the **DfEq RANGE** screen, including **dfTol**, and the **AXES** settings, plus the **FORMT** settings.
- For **ZRCL**, all user-zoom **RANGE** variables, regardless of the current graphing **MODE**, plus the **FORMT** settings.

Transmitting Items

Once you have selected what to send and the receiving unit is ready, you can begin transmitting. For easy distribution of items to several TI-85 units, items remain selected in both the sending and receiving unit and only three keystrokes are required to transmit the items again.

Transmitting Items

When you have selected what you want to transmit, select XMIT. The receiving unit must be set to RECV before transmission can begin (page 19-6).

The name and type of each item is displayed, one per line, as the TI-85 tries to transmit it. After transmission is complete for all items, the message **Done** is displayed. Press **[A]**, and **[V]** to scroll through the names.

After transmission is complete, the LINK menu is displayed on the bottom line.

Transmitting Items to an Additional TI-85

After sending or receiving data, you can repeat the same transmission to a different TI-85 without selecting what to send. The items selected on the sending unit or received on the receiving unit remain selected.

Before you make another selection, simply connect the unit to another TI-85, put the new unit in RECV mode, and select (SEND) ALL XMIT.

Error Conditions

A transmission error will occur after one or two seconds if:

- There is not a cable attached to the port of the sending unit.
- There is not a receiving unit attached to the cable.
- The receiving unit is not in RECV mode.

If the **[C]** key is pressed to interrupt transmission, an ERROR screen is displayed.

Select (EXIT) to leave the ERROR screen.

Receiving Items

Items are not transmitted until the receiving unit is ready.

The Receiving Unit

When you select (RECV) from the LINK menu, the message **Waiting** is displayed and the receiving unit is ready to receive transmitted items.

The receiving unit displays the name and type of each item as it is accepted. After transmission is complete for all items, the message **Done** is displayed. Press **[A]** and **[V]** to scroll through the names. The unit is not in RECV mode; select (RECV) to receive new items.

To leave RECV mode without receiving items, press **[B]**. Select (EXIT) to leave the ERROR screen.

Duplicate Name

If an item of that name exists in the receiving unit, the receiving unit displays **ERROR 36 LINK DUPLICATE NAME** and the name and type of the item. The menu keys on the receiving unit are labelled:

RENAM	OVERW	SKIP	EXIT
-------	-------	------	------

- To store the item to a different name, select (RENAM). After **Name=** on the prompt line, enter a variable name that does not exist in the receiving unit (the keyboard is in ALPHA lock). Press **[EXIT]**. Transmission resumes.
- To overwrite the existing item, select (OVERW). Transmission resumes.
- To skip this item (not copy it to the receiving unit), select (SKIP). Transmission resumes with the next item.
- To leave RECV mode, select (EXIT).

Insufficient Memory in Receiving Unit

If the receiving unit does not have sufficient memory to receive the item, the receiving unit displays **ERROR 34 LINK MEMORY FULL** and the name and type of the item. The menu keys on the receiving unit are labelled:

SKIP	EXIT
------	------

- To skip this item, select (SKIP). Transmission resumes with the next item.
- To leave RECV mode, select (EXIT).

Backing Up Memory

BCKUP transmits an image of memory to the receiving unit.

Memory Backup	<p>To copy the exact contents of memory in the sending unit to the memory of the receiving unit, select (BCKUP).</p> <p>When you select (BCKUP) from the LINK menu, the message Memory Backup is displayed.</p> <p>Warning: BCKUP overwrites the memory in the receiving unit and all information in the memory of the receiving unit is lost. Press (END) to leave LINK.</p> <p>Select (EXIT) to begin transmission.</p>		
The Receiving Unit	<p>As a safety check to prevent accidental loss of memory, when the receiving unit receives notice of a backup, the message WARNING Memory Backup is displayed. The menu keys are labelled:</p> <table><tr><td>CONT</td><td>EXIT</td></tr></table> <ul style="list-style-type: none">• To continue with the backup process, select (CONT). The transmission will begin.• To prevent the backup, select (EXIT). <p>Note: If a transmission error occurs during a backup, the receiving unit is reset.</p>	CONT	EXIT
CONT	EXIT		

Example

Create and store a random matrix and a random complex number and then transfer them to another TI-85.

Example

1. From the Home screen, create and store the variables:
`randM(3,3)→RM`
`(rand,rand)→RCN`
2. Connect two TI-85s with the cable.
3. On the receiving unit:
 - Press **[2nd]** **[LINK]** to display the LINK menu.
 - Press **[F2]** to select (RCV).
4. On the sending unit:
 - Press **[2nd]** **[LINK]** to display the LINK menu.
 - Press **[F1]** to select (SEND).
 - Press **[F3]** to select (ALL).
 - Move the cursor to **RM**. Press **[F4]** to select **RM**. Repeat for **RCN**.
5. On the sending unit, press **[F5]** to select (QUIT). The items are transmitted and both units display:




6. Press **[2nd]** **[QUIT]** to leave LINK.

Appendix A : Tables

This appendix provides a list of all TI-85 command-line instructions that you can use on the Home screen and in programs and functions that you can use in expressions.

Appendix Contents	Table of Functions	Instructions	A-2
	Table of System Variables		A-22

Table of Functions and Instructions

Functions (F) return a value, list, matrix, vector, or string and can be used in an expression; instructions (I) initiate an action. Some, but not all, have arguments. Menu/keys marked  are interactive except in the program editor, but can be typed on a command line or copied from the CATALOG.














Operations and Arguments	Result	Menu/Keys	Fn Page
abs arg1 • arg1 : real/cplx num/list/matrix/vector	Returns absolute value of real number or magnitude of complex number arg1; matrix of absolute values of arg1 matrix elements; vector of absolute values of arg1 vector elements	 [MATH] (NUM) (abs)  [CPLX] :abs:  [MATRIX] (CPLX) (abs)  [VECTR] (CPLX) (abs)	F 3-5 F 11-4 F 13-18 F 13-30
Addition : arg1+arg2 • arg1 : real/cplx num/list/matrix/vector • arg2 : real/cplx num/list/matrix/vector	Returns arg1 plus arg2. Adds elements of list, matrix, or vector. If number and list, adds number to each list element. See concatenation		F 3-2 12-7 13-10 13-26
arg1 and arg2 • arg1 : real num • arg2 : real num	Returns bit comparison of arg1 and arg2 (truncated to integers)	 [BASE] (BOD) (and)	 10-7
angle arg1 • arg1 : real/cplx num/list/matrix/vector	Returns polar angle of a number arg1, or of each element of a list, matrix, or vector arg1	 [CPLX] (angle)  [MATRIX] (CPLX) (angle)  [VECTR] (CPLX) (angle)	F 11-4 F 13-18 F 13-30
arc (arg1,arg2,arg3,arg4) • arg1 : expression • arg2 : var name • arg3 : real num • arg4 : real num	Returns length along function arg1 in variable arg2 from point arg3 to point arg4	 [CALC] (arc)	F 3-16
Assignment : arg1=arg2 • arg1 : var name • arg2 : expression	Store arg2 as variable arg1 without evaluation	 [=]	I 2-9
aug(arg1,arg2) • arg1 : real/cplx matrix • arg2 : real/cplx matrix	Returns matrix arg1 augmented by matrix arg2	 [MATRIX] (OPS) (aug)	F 13-14

Table of Functions and Instructions (Continued)














Axes(arg1,arg2) • arg1 : xaxis variable • arg2 : yaxis variable	Define which variables are plotted for the axes in DiffEq MODE	 AXES	I 7-1
AxesOff • no arguments	Set axis graphing format off	 OFF	I 4-7
AxesOn • no arguments	Set axis graphing format on	 ON	I 4-7
arg1b • real integer	Designates arg1 as binary entry	 BASE	entry 10-4
Bin • no arguments	Set binary number base MODE	 MODE	I 1-26
arg1>Bin • arg : real/cplx num-list-matrix-vecr	Display result arg1 as binary	 (BASE) (CONV) (>Bin)	I 10-6
Circ(arg1,arg2,arg3) • arg1 : x-value of centre • arg2 : y-value of centre • arg3 : radius	Draw a circle with centre (arg1,arg2) and radius arg3	 (DRAW) (Circ)	I 4-36
CIDrw • no arguments	Delete all drawn elements from a graph or drawing	 (DRAW) (CIDrw)	I 4-31
		 (DRAW) (CIDrw)	I 15-17
CILCD • no arguments	Clear screen	 (EDIT) (/C) (CILCD)	I 16-13
cnorm arg1 • arg1 : real/cplx matrix/vecr	Returns column norm of matrix or vector arg1	 (MATRIX) (MATH) (cnorm)	F 13-13
Concatenate : arg1+arg2 • arg1 : string • arg2 : string	Returns a concatenated string		F 9-4
cond arg1 • arg1 : real/cplx matrix	Returns condition number of square matrix arg1	 (MATRIX) MATH+ (cond)	F 13-13

Table of Functions and Instructions (Continued)














conj arg1 • arg1: real/cplx num/list/matrix/vectr	Returns conjugate of number arg1, or of elements of list, matrix or vector arg1	 [CPLX] (conj)  [MATRX] CPLY (conj)  [VECTR] CPLY (conj)	F 11-3 F 13-18 F 13-30
CoordOff • no arguments	Set coordinate graphing format off	 (FORMAT) CoordOff '	I 4-7
CoordOn • no arguments	Set coordinate graphing format on	 (FORMAT) CoordOn '	I 4-7
cos arg1 • arg1: real/cplx num/list or square real matrix	Returns cosine of arg1	 COS	F 3-2 13-11
cos⁻¹ arg1 • arg1: real/cplx num/list	Returns arccos of arg1	 (COS ⁻¹)	F 3-2
cosh arg1 • arg1: real/cplx num/list	Returns hyperbolic cosine of arg1	 [MATH] CHYP (cosh)	F 3-8
cosh⁻¹ arg1 • arg1: real/cplx num/list	Returns hyperbolic arccos of arg1	 [MATH] CHYP (cosh ⁻¹)	F 3-8
cross arg1, arg2 • arg1: real/cplx 2-D/3-D vectr • arg2: real/cplx 2-D/3-D vectr	Returns cross product of vectors arg1 and arg2	 [VECTR] (MATH) (cross)	F 13-27
arg1 ← Cyl • arg1: real 2-D/3-D vectr	Display result arg1 as cylindrical coordinates	 [VECTR] GPS → CYL	I 13-29
CylV • no arguments	Set cylindrical display MODE for vectors	 [MODE] CylV '	I 1-27
arg1 d • real number	Designates arg1 as decimal entry	 [BASE] TYPE d	entrée 10-4

Table of Functions and Instructions (Continued)













Dec • no arguments	Set decimal number base MODE	 [MODE] [Dec]	I 1-26
arg1 → Dec • arg1 : real/cplx num/list/matrx/vectr	Display result arg1 as decimal	 [BASE] [CONV] [→Dec]	I 10-6
Degres : arg1 • arg1 : real/cplx num/list	Interpret arg1 as degrees	 [MATH] [ANGLE (°)]	F 3-7
Degree • no arguments	Set degree MODE	 [MODE] [Degrée]	I 1-25
der1(arg1,arg2,arg3) • arg1 : expression • arg2 : var name • arg3 : real/cplx num/list (opt)	Returns first derivative value of function arg1 with respect to variable arg2 at value arg3	 [CALC] [der1]	F 3-14
der2(arg1,arg2,arg3) • arg1 : expression • arg2 : var name • arg3 : real/cplx num/list (opt)	Returns second derivative value of function arg1 with respect to variable arg2 at value arg3	 [CALC] [der2]	F 3-14
det arg1 • arg1 : real/cplx square matrix	Returns determinant of matrix arg1	 [MATRIX] [MATH] [det]	F 13-12
DifEq • no arguments	Set differential equation mode MODE	 [MODE] [DifEq]	I 1-26
dim arg1 • arg1 : real/cplx matrx/vectr	Returns dimensions of matrix arg1 as a list or length of vector arg1	 [MATRIX] [OPS] [dim]  [VECTR] [OPS] [dim]	F 13-16 F 13-28
arg1 → dim arg2 • arg1 : real integer • arg2 : matrix name	Interprets (dimension, ...) as dimensions of matrix arg2 to dimension arg1	 [MATRIX] [OPS] [dim]	F 13-15
arg1 → dim arg2 • arg1 : real integer • arg2 : vectr name	Creates (if necessary) or defines vector arg2 to dimension arg1	 [VECTR] [OPS] [dim]	F 13-28

Table of Functions and Instructions (Continued)

dimL arg1 • arg1: real/cplx list	Returns length of list arg1	2x: DIML DMS: dimL	F 12-10
arg1 → dimL arg2 • arg1: real/integer ≥ 0 • arg2: list name	Creates (if necessary) or redimensions list arg2 to length arg1	2x: DIML DMS: dimL	F 12-10
Disp • no arguments	Display Home screen	PRG: DISP EX: Disp	1 16-11
Disp arg1, arg2, ... • arg: value or string	Display variable arg1	PRG: DISP EX: Disp	1 16-11
DispG • no arguments	Display graph	2x: DISP DMS: Disp PRG: Disp EX: Disp	1 4-43 16-12
Division arg1/arg2 • arg1: real/cplx num/list/vectr • arg2: real/cplx num/list ≠ 0	Returns arg1 divided by arg2	\div	F 3-2 12-7 13-26
arg1 → DMS • arg1: real/num	Display result arg1 in DMS format	2x: MATC DMS: DMS → DMS	1 3-7
Entry DMS arg1, arg2, arg3 • arg1: real/integer • arg2: real/integer • arg3: real/num	Interpret entries as: arg1: degrees arg2: minutes arg3: seconds	2x: MATC ANGLE: x	entry 3-7
dot(arg1, arg2) • arg1: real/cplx vectr • arg2: real/cplx vectr	Returns dot product of vectors arg1 and arg2	2x: VECTOR MAT: dot	F 14-27
DrawDot • no arguments	Set dot graphing format	DRAW: DORMT DRAW: dot	1 4-7
DrawF arg1 • arg1: expression in x	Draw function arg1	DRAW: DRAW DRAW: $\frac{1}{x}$ F: DRAW DRAW: F	1 4-37 1 15-12

Table of Functions and Instructions (Continued)



DrawLine • no arguments	Set connected line graphing format	 (F- FORMAT) DrawLine [†]	I 4-7
DrInV arg1 • arg1 : expression in x	Draw inverse of function arg1	 (DRAW) DrInV	I 4-37
DS< (arg1,arg2) • arg1 : user var name • arg2 : real num	Decrement variable arg1 by 1, skip next command if arg1 < arg2	 (EDIT) (CTL) (DS)>	I 16-18
dxDer1 • no arguments	Set der1 as differentiation type	 (MODE) dxDer1 [†]	I 1-27
dxNDer • no arguments	Set nDer as differentiation type	 (MODE) dxNDer [†]	I 1-27
e arg1 • arg1 : real/cplx num/list or square real matrix	Returns e raised to arg1 power	 (e ^x)	F 3-2 13-11
eigVc arg1 • arg1 : real/cplx square matrix	Returns matrix of eigenvectors of matrix arg1	 (MATRIX) (MATH) (eigVc)	F 13-13
eigVl arg1 • arg1 : real/cplx square matrix	Returns list of eigenvalues of matrix arg1	 (MATRIX) (MATH) (eigVl)	F 13-13
Else : If arg1:Then:commands Else:commands...:End • arg1 : condition	Execute Then commands if arg1 is true, Else commands if arg1 is false	 (EDIT) (CTL) (Else)	I 16-15
End • no arguments	Identifies end of While, For, Repeat, or If-Then-Else loop	 (EDIT) (CTL) (End)	I 16-15
Eng • no arguments	Set engineering display MODE	 (MODE) (Eng) [†]	I 1-26
Eq>S (arg1,arg2) • arg1 : equation var name • arg2 : string var name	Convert equation arg1 to a string and store in string arg2	 (STANG) (Eq>S)	I 9-5

Table of Functions and Instructions (Continued)













Equal to : arg1=arg2 • arg1 : real/cplx num/list/matrix/vector/string • arg2 : real/cplx num/list/matrix/vector/string	Returns 1 if arg1=arg2 Returns 0 if arg1≠arg2 If arg1 and arg2 are lists, returns 1 if all elements, by element comparison	 (TEST)	F 3-18 13-11 13-26
Equal arg1=arg2 • arg1 : expression • arg2 : expression	Returns arg1=arg2 if arg1 is not a variable instruction the beginning of a line		F 1-8
eval arg1 • arg1 : real/num	Returns list of all special graph functions at x=arg1	 (MATH) (MSG)	F 3-10
evalf(arg1,arg2,arg3) • arg1 : expression • arg2 : variable • arg3 : real/cplx num	Returns variable function arg1 eval matrix for variable arg2 at value arg3	 (ALC)	F 3-12
Exponent arg1,arg2 • arg1 : real/cplx num/list • arg2 : real/num/integer/000	Returns arg1 raised to arg2 power of 1-1		F 2-1
ExpR arg1,arg2 • arg1 : x list (real) (opt) • arg2 : y list (real) (opt)	Perform exponential model regression on lists using lists arg1 and arg2	 (CALC) (GRAPH)	F 15-16
Factorial! : arg1 • arg1 : 0 sintgr/list 5449	Returns factorial of arg1	 (MATH) (PROB: 0)	F 3-6
fcstx arg1 • arg1 : real num	Returns forecasted x at y=arg1 using current RegEq	 (STAT)	F 15-16
fcsty arg1 • arg1 : real num	Returns a forecasted y at x=arg1 using current RegEq	 (STAT)	F 15-16
Fill(arg1,arg2) • arg1 : real/cplx num • arg2 : list/matrix/vector name	Store value arg1 to each element in list, matrix, or vector arg2	 (LIST) (OPS) (FILL)  (MATRIX) (OPS) (FILL)  (VECT) (OPS) (FILL)	F 12-9 1 13-14 1 13-28

Table of Functions and Instructions (Continued)












Fix arg1 • arg1: integer ≤11	Set fixed display MODE for arg1 decimal places	 [MODE] (Fix)	I 1-25
Float • no arguments	Set floating display MODE	 [MODE] (Float)	I 1-25
fMax(arg1,arg2,arg3,arg4) • arg1: expression • arg2: var name • arg3: real num • arg4: real num	Returns x value for maximum of function arg1, with respect to variable arg2, between lower value arg3, upper value arg4	 [CALC] (fMax)	F 3-16
fMin(arg1,arg2,arg3,arg4) • arg1: expression • arg2: var name • arg3: real num • arg4: real num	Returns x value for minimum of function arg1, with respect to variable arg2, between lower value arg3, upper value arg4	 [CALC] (fMin)	F 3-16
fIntf(arg1,arg2,arg3,arg4) • arg1: expression • arg2: var name • arg3: real num • arg4: real num	Returns function integral of arg1, with respect to variable arg2 between lower limit arg3, upper limit arg4	 [CALC] (fIntf)	F 3-15
FnOff • no arguments	Unselect all functions	 [GRAPH] (FnOff)	I 4-11
FnOff arg1,arg2,arg3 • arg: 1≤integers≤9	Unselect arg1, arg2, arg3 functions	 [GRAPH] (FnOff)	I 4-11
FnOn • no arguments	Select all functions	 [GRAPH] (FnOn)	I 4-11
FnOn arg1,arg2,arg3,... • arg: 1≤integers≤9	Select arg1, arg2, arg3, ... functions	 [GRAPH] (FnOn)	I 4-11
For(arg1,arg2,arg3,arg4): commands...End • arg1: var name • arg2: real num • arg3: real num • arg4: real num (opt)	Execute loop, incrementing variable arg1, beginning at arg2, by increment arg4, until arg1>arg3	 [EDIT] (CTL: fFor)	I 16-16
fPart arg1 • arg1: real/cplx num/ list/matrix/vectr	Return fractional part of arg1 or of each element of arg1	 [MATH] (NUM) (fPart)	F 3-4 13-11 13-26

Table of Functions and Instructions (Continued)

arg1 → Frac • arg1 : real/cplx num/ list/matrix/vector	Display result arg1 as most simplified fraction	[MATH] [MISC] (→Frac)	I 3-10
Func • no arguments	Set function graphing MODE	[MODE] (Func) ¹	I 1-26
gcd(arg1,arg2) • arg1 : 0≤integers<1E11 • arg2 : 0≤integers<1E11	Returns greatest common denominator of arg1 and arg2	[MATH] [MISC] (gcd)	F 3-10
getKey • no arguments	Return value of last keystroke	[EDIT] [O/D] (getKey)	F 16-13
Goto arg1 • arg1 : label name	Transfer control to label arg1	[EDIT] [CTL] (Goto)	I 16-17
Greater than : arg1>arg2 • arg1 : real num/list • arg2 : real num/list	Returns 1 if arg1>arg2 Returns 0 if arg1≤arg2 If arg1 and arg2 are lists, returns list	[TEST] (>)	F 3-18
Greater than or equal to : arg1≥arg2 • arg1 : real num/list • arg2 : real num/list	Returns 1 if arg1≥arg2 Returns 0 if arg1<arg2 If arg1 and arg2 are lists, returns list	[TEST] (≥)	F 3-18
GridOff • no arguments	Set grid graphing format off	[FORMAT] [GridOff]	I 4-7
GridOn • no arguments	Set grid graphing format on	[FORMAT] [GridOn] ¹	I 4-7
arg1h • real integer	Designates arg1 as hexadecimal entry	[BASE] (TYPE) (h)	10-4 10-4
Hex • no arguments	Set hexadecimal number base MODE	[MODE] (Hex)	I 1-26
arg1 → Hex • arg1 : real/cplx num/ list/matrix/vector	Display result arg1 as hexadecimal	[BASE] (CONV) (→Hex)	I 10-6

Table of Functions and Instructions (Continued)











Hist arg1,arg2 • arg1 : x list (read) (opt) • arg2 : freq list (integers≥0) (opt)	Draws histogram of stat data using lists arg1 and arg2 or xStat and frequencies of 1	 (DRAW) (HIST)	I 15-17
Ident arg1 • arg1 : integer>0	Returns identity matrix of dimension arg1	 (MATRIX) (OPS) Ident	F 13-14
If arg1 : command1 :command2 • arg1 : condition	If arg1=0 (false), skip command1	 (EDIT) (CTL) If	I 16-15
If arg1:Then:commands... :End • arg1 : condition	Execute command after Then if arg1 is true	 (EDIT) (CTL) Then	I 16-15
If arg1:Then:commands... :Else:commands...:End • arg1 : condition	Execute Then commands if arg1 is true, Else commands if arg1 is false	 (EDIT) (CTL) Else	I 16-15
Imag arg1 • arg1 : real/cplx number	Returns nonreal part of arg1	 (CPLX) (Imag)	F 11-3
Imag arg1 • arg1 : real/cplx matrix	Returns matrix of nonreal part of matrix arg1	 (MATRIX) (CPLX) Imag	F 13-18
Imag arg1 • arg1 : real/cplx vector	Returns vector of nonreal part of vector arg1	 (VECTOR) (CPLX) Imag	F 13-30
InpSt arg1 • arg1 : var name	Prompt for string to store to variable arg1	 (EDIT) (I/O) InpSt	I 16-12
InpSt arg1,arg2 • arg1 : string • arg2 : var name	Display string arg1, read entered string to arg2	 (EDIT) (I/O) InpSt	I 16-12
Input • no arguments	Display graph	 (EDIT) (I/O) Input	I 16-10
Input arg1 • arg1 : var name	Prompt for value to store to variable arg1	 (EDIT) (I/O) Input	I 16-10

Table of Functions and Instructions (Continued)











Input arg1,arg2 • arg1 : string • arg2 : var name	Display string arg1, store entered value to arg2	 (EDIT) (I/O) (Input)	I 16-10
int arg1 • arg1 : real/cplx num/ list/matrix/vectr	Returns greatest integer contained in arg1 or in each element of arg1	 (MATH) (NUM) (Int)	F 3-4 13-11 13-26
Inter (arg1,arg2,arg3,arg4,arg5) • arg1 : real/num • arg2 : real/num • arg3 : real/num • arg4 : real/num • arg5 : real/num	Returns interpolated or extrapolated value at $x=arg5$ given arg1,arg2, and arg3,arg4	 (MATH) (Inter)	F 3-11
Inverse arg • arg : real/cplx num/list or square matrix <size>	Returns 1/divided by arg1 or inverted matrix	 (MATH)	F 3-2 13-10
iPart arg1 • arg1 : real/cplx num/ list/matrix/vectr	Returns integer part of arg1 or of each element of arg1	 (MATH) (NUM) (iPart)	F 3-4 13-11 13-26
IS> (arg1,arg2) • arg1 : user var name • arg2 : real/num	Increment variable arg1 by 1, skip next command if arg1>arg2	 (EDIT) (CTL) (IS>)	I 16-18
LabelOff • no arguments	Set axis label graphing format off	 (FORMAT) (LABEL) (Off)	I 4-7
LabelOn • no arguments	Set axis label graphing format on	 (FORMAT) (LABEL) (On)	I 4-7
Lbl arg1 • arg1 : label name	Assign label arg1 to the command	 (EDIT) (CTL) (Lbl)	I 16-17
lcm (arg1,arg2) • arg1 : 0<integers<1E11 • arg2 : 0<integers<1E11	Returns least common multiple of arg1 and arg2	 (MATH) (MISC) (lcm)	F 3-8

Table of Functions and Instructions (Continued)













Less than : arg1<arg2 • arg1 : real num/list • arg2 : real num/list	Returns 1 if arg1<arg2 Returns 0 if arg1≥arg2 If arg1 and arg2 are lists, returns list	 (TEST)	F 3-18
Less than or equal to : arg1≤arg2 • arg1 : real num/list • arg2 : real num/list	Returns 1 if arg1≤arg2 Returns 0 if arg1>arg2 If arg1 and arg2 are lists, returns list	 (TEST) (s)	F 3-18
Line:arg1,arg2,arg3,arg4) • arg1 : 1st x value • arg2 : 1st y value • arg3 : 2nd x value • arg4 : 2nd y value	Draw a line from (arg1,arg2) to (arg3,arg4)	 (DRAW) LINE	I 4-34
LnR arg1,arg2 • arg1 : x list (real) (opt) • arg2 : y list (real) (opt)	Perform linear model regression analysis using lists arg1 and arg2	 (CALC) LnR	I 15-16
ll→vc arg1 • arg1 : real/cplx list	Returns list arg1 converted to a vector	 (LIST)  (ll→vc)  (VECTR)  (ll→vc)	F 12-9 F 13-29
ln arg1 • arg1 : real/cplx num/list	Returns natural logarithm of arg1		F 3-2
lngh arg1 • arg1 : string	Returns length of string arg1	 (STANG) (lngh)	F 9-4
LnR arg1,arg2 • arg1 : x list (real) (opt) • arg2 : y list (real) (opt)	Perform logarithmic model regression analysis using lists arg1 and arg2	 (CALC) LnR	I 15-16
log arg1 • arg1 : real/cplx num/list	Returns logarithm of arg1		F 3-2

Table of Functions and Instructions (Continued)









LU(arg1,arg2,arg3,arg4) • arg1 : real/cplx square matrix • arg2 : matrix name • arg3 : matrix name • arg4 : matrix name	Calculates LU decomposition of matrix arg1, stores lower triangular matrix in arg2, upper in arg3, permutation matrix in arg4	 (MATRIX) (MATH) (LU)	I 13-12
max(arg1,arg2) • arg1 : real/cplx num/list • arg2 : real/cplx num/list	Returns the larger of arg1 and arg2	 (MATH) (NUM) (max)	F 3-5
max(arg1) • arg1 : real/cplx list	Returns largest value in list arg1	 (LIST) (OPS) (max)	F 12-8
Menu(arg1,arg2,arg3,...) • arg1 : 1, 2, 3, 4 ou 5 • arg2 : string • arg3 : label	Sets up branches based on menu items	 (EDIT) (CTL) (Menu)	I 16-17
min(arg1,arg2) • arg1 : real/cplx num/list • arg2 : real/cplx num/list	Returns the smaller of arg1 and arg2	 (MATH) (NUM) (min)	F 3-5
min(arg1) • arg1 : real/cplx list	Returns smallest value in list arg1	 (LIST) (OPS) (min)	F 12-8
mod(arg1,arg2) • arg1 : real num • arg2 : real num	Returns the modulus of arg1 with respect to arg2	 (MATH) (NUM) (mod)	F 3-5
mRAdd(arg1,arg2,arg3,arg4) • arg1 : real/cplx num • arg2 : real/cplx matrix • arg3 : integer>0 • arg4 : integer>0	Returns matrix with row arg3 of matrix arg2 multiplied by arg1, added to row arg4, and stored in row arg4	 (MATRIX) (OPS) (mRAdd)	F 13-16

Table of Functions and Instructions (Continued)











Multiplication : $\text{arg1} \times \text{arg2}$ • arg1 : real/cplx num/ list/matrix/vectr • arg2 : real/cplx num/ list/matrix/vectr	Returns arg1 multiplied by arg2	 (X)	F 3-2 12-7 13-10 13-26
multR($\text{arg1}, \text{arg2}, \text{arg3}$) • arg1 : real/cplx num • arg2 : real/cplx matrix • arg3 : integer > 0	Returns matrix with row arg3 of matrix arg2 multiplied by arg1 , and stored in row arg3	 (MATRIX) (OPS) multR	F 13-16
$\text{arg1} \text{ nCr } \text{arg2}$ • arg1 : integer > 0 • arg2 : integer > 0	Returns number of combinations of arg1 items taken arg2 at a time	 (MATH) (PROB) nCr	F 13-16
nDer($\text{arg1}, \text{arg2}, \text{arg3}$) • arg1 : expression • arg2 : var name • arg3 : real/cplx num (opt)	Returns approximate numerical derivative of function arg1 with respect to arg2 at value arg3	 (CALC) nDeriv	F 3-13
Negation : arg1 • arg1 : real/cplx num/ list/matrix/vectr	Returns negative of arg1 Negates elements of list, matrix, or vector	 (-)	F 3-2 13-10 13-26
norm arg1 • arg1 : real/cplx num/ list/matrix/vectr	Returns norm of matrix or vector arg1 . Returns absolute value of number or list arg1	 (MATRIX) MATH: norm/  (VECTR) MATH: norm	F 13-12 13-27
Normal • no arguments	Set normal display MODE	 (MODE) (Normal) \uparrow	1 1-26
not arg1 • arg1 : real num	Returns one's complement of arg1	 (BASE) (BOOL) not	F 10-7
Not equal : $\text{arg1} = \text{arg2}$ • arg1 : real/cplx num/list/ matrix/vectr/string • arg2 : real/cplx num/list/ matrix/vectr/string	Returns 1 if $\text{arg1} = \text{arg2}$ Returns 0 if $\text{arg1} \neq \text{arg2}$ If arg1 and arg2 are lists, returns list for element-by-element comparison	 (TEST) (=)	F 3-18 13-11 13-26

Table of Functions and Instructions (Continued)












arg1 nPr arg2 • arg1 : integer > 0 • arg2 : integer > 0	Returns number of permutations of arg1 items taken arg2 at a time	 (MATH) (PROB) (nPr)	F 3-6
arg1o • real integer	Designate arg1 as octal entry	 [BASE] (TYPE) (o)	entree 10-1
Oct • no arguments	Set octal number base MODE	 [MODE] (O=0)	1 1-26
arg1 > Oct • arg1 : real/cplx num/ list/matrix/vector	Display result arg1 as octal	 [BASE] (CONV) (=O=)	1 10-6
OneVar arg1, arg2 • arg1 : x list (real) (opt) • arg2 : freq list (Integers ≥ 0) (opt)	Perform one-variable statistical analysis using lists arg1 and arg2	 (CALC) (1-Var)	1 15-16
arg1 or arg2 • arg1 : real num • arg2 : real num	Returns bit comparison of arg1 and arg2 (truncated to integer)	 [BASE] (BOOL) (or)	F 10-7
Output(arg1, arg2, arg3) • arg1 : 1 ≤ integer ≤ 8 • arg2 : 1 ≤ integer ≤ 1 • arg3 : value/string	Display arg3, beginning at line arg1, column arg2	 (EDIT) (I/O) (Output)	1 16-12
P2Reg arg1, arg2 • arg1 : x list (real) (opt) • arg2 : y list (real) (opt)	Perform second order polynomial regression using lists arg1 and arg2	 (CALC) (P2Reg)	1 15-16
P3Reg arg1, arg2 • arg1 : x list (real) (opt) • arg2 : y list (real) (opt)	Perform third order polynomial regression using lists arg1 and arg2	 (CALC) (P3Reg)	1 15-16
P4Reg arg1, arg2 • arg1 : x list (real) (opt) • arg2 : y list (real) (opt)	Perform fourth order polynomial regression using lists arg1 and arg2	 (CALC) (P4Reg)	1 15-16
Param • no arguments	Set parametric graphing MODE	 [MODE] (Param)	1 1-26

Table of Functions and Instructions (Continued)















Pause • no arguments	Suspend execution until  is pressed	 (F2) CTL (Pause)	1 16-14
Pause arg1 • arg1 : real/cplx num/list/ matrix/vector/string	Display arg1, suspend execution until  is pressed	 (EDIT) (CTL) (Pause)	1 16-18
Percent : arg1% • arg1 : real num	Returns arg1 divided by 100	 (MATH) MISC (%)	F 3-10
pEval(arg1,arg2) • arg1 : real/cplx list • arg2 : real/cplx value	Returns value of polynomial with arg1 coefficients at x=arg2	 (MATH) MISC pEval	F 3-10
Pol • no arguments	Set polar graphing MODE	 (MODE) (Pol)	1 1-26
arg1 ► Pol • arg1 : cplx num/list/ matrix/vector	Display result arg1 as polar coordinates	 (CPLX) (►Pol)	1 11-4
arg1 ► Pol • arg1 : real 2-D vectr	Display result arg1 as polar coordinates	 (VECTR) (OPS) (►Pol)	1 13-29
PolarC • no arguments	Set polar display for complex numbers	 (MODE) (PolarC)	1 1-26
Polar complex : (arg1<arg2) • arg1 : real num • arg2 : real num	Interpret arg1 as magnitude, arg2 as angle	 (I/Z)	entrée 11-2
PolarGC • no arguments	Set polar graphing coordinate format	 (FORM) (PolarGC)	1 4-7
poly arg1 • arg1 : real/cplx list	Returns list of roots of polynomial with arg1 coefficients	 (POLY)	F 14-9
Power of ten : 10^arg1 • arg1 : real/cplx num/list	Returns 10 raised to arg1 power	 (10^x)	F 3-2

Table of Functions and Instructions (Continued)













Power : arg1, arg2 • arg1 : real/cplx num/list or square matrix • arg2 : real/cplx num/list	Returns arg1 raised to arg2 power. arg1 must be real integer if arg1 is matrix.	 [MATH]	F 3-2 13-10
prod arg1 • arg1 : real/cplx list	Returns product of list arg1.	 [MATH] MATH prod  [LIST] OPS prod	F 3-9 P 12-9
Prompt arg1, arg2, arg3 • arg1 : var name	Prompt for variable arg1, then variable arg2, etc.	 [EQ-T] EQ Prompt	I 16-10
PrtScn • no arguments	Send current display to printer.	 [IO] PrtScn	I 16-13
PtChg (arg1, arg2) • arg1 : x value • arg2 : y value	Change point at (arg1, arg2).	 [DRAW] DRAW PtChg	I 4-39
PtOff (arg1, arg2) • arg1 : x value • arg2 : y value	Erase point at (arg1, arg2).	 [DRAW] DRAW PtOff	I 4-39
PtOn (arg1, arg2) • arg1 : x value • arg2 : y value	Draw point at (arg1, arg2).	 [DRAW] DRAW PtOn	I 4-39
PwrR arg1, arg2 • arg1 : x list (real) (opt) • arg2 : y list (real) (opt)	Perform power model regression analysis using lists arg1 and arg2.	 [CALC] PWR	I 15-16
rAdd (arg1, arg2, arg3) • arg1 : real/cplx matrix • arg2 : integer > 0 • arg3 : integer > 0	Returns matrix with row arg2 of matrix arg1 added to row arg3, and stored in row arg3.	 [MATRIX] OPS rAdd	F 13-16
Radian : arg1 • arg1 : real/cplx num/list	Interpret arg1 as radians.	 [MATH] [ANGLE] °	F 3-7
Radian • no arguments	Set radian MODE.	 [MODE] Radian	I 1-25

Table of Functions and Instructions (Continued)














rand • no arguments	Returns 0<random number<1 seeded from value in rand	 (MATH) (PROB) rand	F 3-6
randM(arg1,arg2) • arg1 : integer > 0 • arg2 : integer > 0	Returns an arg1xarg2 matrix with random -9<integers<9 elements	 (MATRIX) (OPS) randM	F 13-14
RcGDB arg1 • arg1 : database name	Recalls graph database arg1 as the current graph	 RcGDB	I 3-40
RcPic arg1 • arg1 : picture name	Recalls picture arg1 onto the current graph	 RcPic STAT DRAW RcPic	I 4-41 1 15-17
real arg1 • arg1 : real/cplx num/ list/matrix/vectr	Returns real part of number arg1 or of each element of list, matrix, or vector arg1	 (CPLX) real  (MATRIX) (CPLX) real  (VECTR) (CPLX) real	F 11-3 F 13-18 F 18-30
arg1 => Rec • arg1 : cplx num/list/ matrix/vectr	Display result arg1 as rectangular coordinates	 (CPLX) (=Rec)	I 11-4
arg1 => Rec • arg1 : real 2-D vectr	Display result arg1 as rectangular coordinates	 (VECTR) (OPS) (=Rec)	I 13-29
RectC • no arguments	Set rectangular display for complex numbers	 (MODE) RectC [†]	I 1-26
RectGC • no arguments	Set rectangular graphing coordinate format	 (FORMT) RectGC [†]	I 4-7
RectV • no arguments	Set rectangular display MODE for vectors	 (MODE) RectV [†]	I 1-27
ref arg1 • arg1 : real/cplx matrix	Returns row echelon form of matrix arg1	 (MATRIX) (OPS) ref	F 13-16

Table of Functions and Instructions (Continued)












Repeat arg1:commands... :End • arg1 : condition	Execute loop until condition is true	 (EDIT) (CTL) (Repeat)	1 16-16
Return • no arguments	Returns to calling program	 (EDIT) (CTL) (Return)	1 16-18
rnorm arg1 • arg1 : real/cplx matrix/ vectr	Returns row norm of matrix arg1	 [MATH] (MATH) (rnorm)	F 13-13
Root : arg1 $\sqrt{\arg2}$ • arg1 : real/cplx num/list • arg2 : real/cplx num/list	Returns arg1 root of arg2	 [MATH] (MISC) ($\sqrt{}$)	F 3-10
rotL arg1 • arg1 : real integer	Returns arg1 with bits rotated to left	 [BASE] (BIT) (rotL)	F 10-8
rotR arg1 • arg1 : real integer	Returns arg1 with bits rotated to right	 [BASE] (BIT) (rotR)	F 10-8
round (arg1,arg2) • arg1 : real/cplx num/list/ matrix/vectr • arg2 : 0=integer,11=opt	Returns arg1 rounded to arg2 decimal places	 [MATH] (NUM) (round)	F 3-4 13-11 13-26
rref arg1 • arg1 : real/cplx matrix	Returns matrix arg1 in reduced row echelon form	 [MATH] (OPS) (rref)	F 13-16
rSwap (arg1,arg2,arg3) • arg1 : real/cplx matrix • arg2 : integer > 0 • arg3 : integer > 0	Returns matrix with row arg2 of matrix arg1 swapped with row arg3	 [MATH] (OPS) (rSwap)	F 13-16
Scatter arg1,arg2 • arg1 : lx list (real) (opt) • arg2 : y list (real) (opt)	Draw a scatter plot of stat data using lists arg1 and arg2 or xStat and yStat	 (DRAW) (Scatter)	1 15-17
Sci • arguments	Set scientific display MODE	 [MODE] (Sci)	1 1-25

Table of Functions and Instructions (Continued)













seq (arg1,arg2,arg3,arg4,arg5) • arg1 : expression • arg2 : var name • arg3 : real num • arg4 : real num • arg5 : real num	Returns list created by evaluating expression arg1, for variable arg2, beginning at arg3, ending at arg4, with increment arg5	 (MATH) (MISC) seq  (LIST) (OPS) seq	F 3-9 12-8
SeqG • no arguments	Set sequential graphing format	 (FORMAT) (SeqG) [†]	1 4-7
Shade (arg1,arg2,arg3,arg4) • arg1 : expression in x • arg2 : expression in y • arg3 : real num (opt) • arg4 : real num (opt)	Shade area above arg1, below arg2, to right of x=arg3 (default lower), to left of x=arg4 (default upper)	 DRAW (Shade)	1 4-32
shftL arg1 • arg1 : real integer	Returns arg1 with bits shifted to left	 (BASE) (BIT) shftL	F 10-8
shftR arg1 • arg1 : real integer	Returns arg1 with bits shifted to right	 (BASE) (BIT) shftR	F 10-8
ShwSt • no arguments	Display current stat result	 CALC ShwSt	1 15-16
sign arg1 • arg1 : real num/list	Returns -1 if arg1<0, 1 if arg1>0, 0 if arg1=0	 (MATH) (NUM) sign	F 3-6
SimulG • no arguments	Set simultaneous graphing format	 (FORMAT) (SimulG) [†]	1 4-7
simult (arg1,arg2) • arg1 : real/cplx matrix • arg2 : real/cplx vectr	Returns a vector of the solution to a system of simultaneous equations	 (SIMULT) [†]	F 14-11
sin arg1 • arg1 : real/cplx num/list/ or square real matrix	Returns sine of arg1		W 3-2 13-11
sin⁻¹ arg1 • arg1 : real/cplx num/list	Returns arcsin of arg1	 (SIN ⁻¹)	F 3-2

Table of Functions and Instructions (Continued)













sinh arg1 • arg1 : real/cplx num/list	Returns hyperbolic sine of arg1	 [MATH] OHP: (sinh)	F 3-8
sinh⁻¹ arg1 • arg1 : real/cplx num/list	Returns hyperbolic arsin of arg1	 [MATH] OHP: (sinh ⁻¹)	F 3-8
Solver (arg1,arg2,arg3,arg4) • arg1 : equation • arg2 : var name • arg3 : real num or 2 element real list • arg4 : 2 element real list (opt)	Solves equation arg1 for variable arg2 using arg3 guess(es) within bounds specified by arg4, store in variable arg2	 [SOLVER]	I 14-5
sortA arg1 • arg1 : real/cplx list	Returns list arg1 with elements in ascending order	 [OPS] (sortA)	F 12-8
sortD arg1 • arg1 : real/cplx list	Returns list arg1 with elements in descending order	 [LIST] (sortD)	F 12-8
Sortx (arg1,arg2) • arg1 : x list (real) • arg2 : y list (real)	Sort statistical data in order of x elements	 Sortx	I 15-17
Sorty (arg1,arg2) • arg1 : x list (real) • arg2 : y list (real)	Sort statistical data in order of y elements	 (Sorty) [†]	I 15-17
arg1 → Sph • arg1 : real 2-D/3-D vectr	Display result arg1 as spherical coordinates	 [VECTR] (OPS) (→Sph)	I 13-29
SphereV • no arguments	Set spherical display MODE for vectors	 [MODE] (SphereV) [†]	I 1-27
Square root :  arg1 • arg1 : real/cplx num/list	Returns square root of arg1	 $\sqrt{}$	F 3-8
Squaring : arg1 ² • arg1 : real/cplx num/list or square matrix	Returns arg1 multiplied by itself		F 3-2 13-10

Table of Functions and Instructions (Continued)












StEq arg1, arg2 • arg1: string/ var name • arg2: number/ var name	Convert string arg1 to an equivalent of store in equation arg2	 (StEq)	F 9-5
StGDB arg1 • arg1: database name	Store the current graph as database arg1	 (StGDB)	F 3-10
Stop • no arguments	End program execution, returns to Home screen	 (Stop)	F 16-18
Store var1, arg1=arg2 • arg1: real/cplx num/list • arg2: real/cplx num/list • arg2: var name	Store value of arg1 as variable arg2	 (Store)	F 2-5
StPic arg1 • arg1: picture name	Store the current picture as picture arg1	 (StPic)	F 4-11 15-17
sub (arg1, arg2, arg3) • arg1: string • arg2: integer > 0 • arg3: integer > 0	Returns subset of string arg1 beginning at position arg2, length arg3	 (STRNG) sub	F 9-4
Subtraction arg1=arg2 • arg1: real/cplx num/list • arg2: matrix/vector • arg2: real/cplx num/list • arg2: matrix/vector	Returns arg2 subtracted from arg1 Subtracts elements of list, matrix, or vector	 (F)	F 3-2 12-7 13-10 13-20
sum arg1 • arg1: real/cplx list	Returns sum of elements in list arg1	 (MATH) sum  (LIST) sum  (OPS) sum	F 3-9 F 12-8
tan arg1 • arg1: real/cplx num/list	Returns tangent of arg1	 (F)	F 3-2

Table of Functions and Instructions (Continued)














tan⁻¹ arg1 • arg1 : real/cplx num/list	Returns arctan of arg1	 (TAN ⁻¹)	F 3-2
tanh arg1 • arg1 : real/cplx num/list	Returns hyperbolic tangent of arg1	 (MATH) (HYP) (tanh)	F 3-8
tanh⁻¹ arg1 • arg1 : real/cplx num/list	Returns hyperbolic arctangent of arg1	 (MATH) (HYP) (tanh ⁻¹)	F 3-8
TanLn arg1, arg2 • arg1 : expression in X • arg2 : real num	Draw tangent of function arg1 at x=arg2	 (DRAW) (DRAW) (TanLn)	I 4-35
Then : If arg1:Then:commands...:End:commands... • arg1 : condition	Execute commands after Then if arg1 is true, after End if false	 (EDIT) (CTL) (Then)	I 16-16
Trace • no arguments	Display graph and enter TRACE mode	 (TRACE)	I 4-42
Transpose: arg1^T • arg1 : real/cplx matrix	Returns matrix with elements transposed	 (MATRIX) (MATH) (Transpose)	F 13-12
unitV arg1 • arg1 : real/cplx vectr	Returns unit vector of vector arg1	 (VECTR) (MATH) (unitV)	F 13-27
vc=li arg1 • arg1 : real/cplx vectr	Returns vector arg1 converted to a list	 (LIST) (OPS) (vc=li)  (VECTR) (OPS) (vc=li)	F 12-9 F 13-29
Vert arg1 • arg1 : x value	Draw vertical line at x=arg1	 (DRAW) (DRAW) (Vert)	I 4-35
While arg1 : commands...:End • arg1 : condition	Execute loop while condition is true	 (EDIT) (CTL) (While)	I 16-16
arg1 <= arg2 • arg1 : real num • arg2 : real num	Returns bit comparison of arg1 and arg2 (truncated to integer)	 (BASE) (LOG) (arg1 <= arg2)	F 10-7

Table of Functions and Instructions (Continued)

xyline arg1, arg2 • arg1 : liste x (réelle) (opt) • arg2 : liste y (réelle) (opt)	Draw a line plot of stat data using lists arg1 and arg2 or xStat and yStat	STAT (DRAW) xyline	1 15-17
ZDeem • no arguments	Display graph in new viewing rectangle	STAT (ZOOM) ZDeem	1 4-22
ZFit • no arguments	Display graph in new viewing rectangle	STAT (ZOOM) Zfit	1 4-22
ZIn • no arguments	Display graph in new viewing rectangle	STAT (ZOOM) Zin	1 4-20
ZInt • no arguments	Display graph in new viewing rectangle	STAT (ZOOM) Zint	1 4-22
ZOut • no arguments	Display graph in new viewing rectangle	STAT (ZOOM) Zout	1 4-20
ZPrev • no arguments	Display graph in new viewing rectangle	STAT (ZOOM) Zprev	1 4-22
ZRcl • no arguments	Display graph in new viewing rectangle	STAT (ZOOM) Zrcl	1 4-20
ZSqr • no arguments	Display graph in new viewing rectangle	STAT (ZOOM) Zsqr	1 4-22
ZStd • no arguments	Display graph in new viewing rectangle	STAT (ZOOM) Zstd	1 4-22
ZTrg • no arguments	Display graph in new viewing rectangle	STAT (ZOOM) Ztrg	1 4-22

Table of System Variables

The variables listed below are used by the TI-85 in various ways and have certain restrictions on them.

Reserved-Name Variables

The TI-85 stores to reserved-name variables during calculations. You cannot store to reserved-name variables.

Ans	IntErr	n	■	b
x	Sx	ox	ix	Σx^2
y	Sy	oy	iy	Σy^2
Exy	RegEq	corr	PRegC	

Variables Used by the TI-85

You can use the variable names listed below for user data of any type (except constants, programs, graph databases, or graph pictures). However, the TI-85 stores to them (during graphing, for example), so you may wish to avoid using the names.

e	y	t	t	θ
eqn	exp	Q1 ... Q9		Q1 ... Q9

Equation Variables

The variables below must be equations. You can store expressions or equations to them with an assignment instruction.

y1 ... y99	r1 ... r99
x1 ... x199	y1 ... y199
Q'1 ... Q'9	

STAT List Variables

The variables below must be real lists. You can store to them. The TI-85 stores to them during statistical calculations.

Σ	yStat
---	-------

Real Variables

The variables below must be real numbers. You can store to them. The TI-85 may store to them during calculations.

xMin	xMax	xScI		
yMin	yMax	yScI		
tMin	tMax	tStep	tPlot	
θMin	θMax	θStep		
zxMin	zxMax	zxScI		
zyMin	zyMax	zyScI		
ztMin	ztMax	ztStep	ztPlot	
zMin	zMax	zStep	Δx	Δy
xFact	yFact			
lower	upper	δ	tol	dltTol

Appendix B: Reference Information

This appendix provides supplemental information that may be helpful as you use the TI-85. It includes procedures that may help you correct problems with the calculator, and it describes the service and warranty provided by Texas Instruments.

Appendix Contents	Battery Information	B-2
	Accuracy Information	B-3
	Error Conditions	B-4
	In Case of Difficulty	B-9
	Two-Year contractual warranty	B-10

Battery Information

The TI-85 uses two types of batteries: four AAA alkaline batteries and a lithium battery as a back-up for retaining memory while you change the AAA batteries.

When to Replace the Batteries

As the batteries run down, the display begins to dim (especially during calculations), and you must adjust the contrast to a higher setting. If you find it necessary to set the contrast to a setting of 8 or 9, you will need to replace the batteries soon. You should change the lithium battery every three or four years.

Effects of Replacing the Batteries

If you do not remove both types of batteries at the same time or allow them to run down completely, you can change either type of battery without losing anything in memory.

Replacing the Batteries

1. Turn the calculator off and replace the slide cover over the keys to avoid inadvertently turning on the calculator. Turn the calculator so that the back is facing you.
2. Holding the calculator upright, push the latch on the battery cover down with your fingernail or a paper clip and pull the cover out.
3. Replace all four AAA alkaline batteries or the lithium battery. To avoid loss of information stored in memory, the calculator must be off; do not remove the AAA batteries and the lithium battery at the same time.

- To replace the AAA alkaline batteries, remove all four discharged AAA batteries and install new ones as shown on the polarity diagram located in the battery compartment.
- To replace the lithium battery, remove the screw and clip holding the lithium battery. Install the new battery, + side up. Then replace the screw and clip. Use a CR1616 or CR1620 (or equivalent) lithium battery.

Dispose of used batteries properly. Do not incinerate or leave within reach of small children.

4. Replace the cover. When you turn the calculator on, the display shows the Home screen as it was when you last used it.

Accuracy Information

To maximize accuracy, the TI-85 carries more digits internally than it displays.

Computational Accuracy

Values in memory are stored using up to 14 digits with a 4-digit exponent.

You can store a value in the **RANGE** variables, **lower**, and **upper** using up to 12 digits (14 digits for **xSci**, **ySci**, **tStep**, and **aStep**).

When a value is displayed, the displayed value is rounded as specified by the **MODE** setting (pages 1-22 to 1-25), with a maximum of 12 digits and a 3-digit exponent.

Information on calculations in hexadecimal, octal, and binary number bases is on page 7-2.

Error Conditions

When the TI-85 detects an error, it displays an error message **ERROR** in type and the error menu. The general procedure for correcting errors is described on page 1-28. Each error type, including possible causes and suggestions for correction, are shown below.

01 OVERFLOW*	You are attempting to enter, or have calculated, a number that is beyond the range of the calculator.
02 DIV BY ZERO*	You are attempting to divide by zero. You are attempting a stat calculation with lists that are not appropriate.
03 SINGULAR MAT*	A singular matrix (determinate = 0) is not valid as the argument for r^{-1} , Simult , or LU . You are attempting a stat calculation with lists that are not appropriate.
04 DOMAIN*	The argument to a function or instruction is out of the valid range. See Appendix A and the appropriate chapter. You are attempting a stat calculation with lists that are not appropriate.
05 INCREMENT*	The increment in seq is 0 or has the wrong sign. The increment a loop is 0.
06 BREAK	You have pressed the ON key to break execution of a program, halt a DRAW instruction, or stop evaluation of an expression.
07 SYNTAX	The command contains a syntax error. Look for misplaced functions, arguments, parentheses, or commas. See Appendix A and the appropriate chapter. Exponents cannot be more than three digits. = is not valid in parentheses except where an expression is required. Matrices, vectors, and list cannot be entered directly in an element of a matrix, vector, or list even if the expression evaluates to a real or complex number. Use a matrix, vector, or list variable in the expression instead. Axes in DWEq must be Q , t , or Q'

* Errors 1 to 5 do not occur during graphing. The TI-85 allows for undefined values on a graph.

06 NUMBER BASE	<p>You have entered an invalid digit in a number base; for example, 7b.</p> <p>You are attempting an operation that is not allowed in Bin, Hex, or Oct MODE.</p>
06 MODE	<p>You are attempting to store to a RANGE variable in another graphing MODE or to perform an instruction while in the wrong MODE, such as Driv in a graphing MODE other than Func.</p>
10 DATA TYPE	<p>You have entered a value or variable that is the wrong data type.</p> <p>A function (including implied multiplication) or an instruction has an argument that is an invalid data type; for example, a complex number where a real number is required. See Appendix A and the appropriate chapter.</p> <p>In an editor, you have entered a type that is not allowed; for example, a complex number in the STAT editor. See the appropriate chapter.</p> <p>You are attempting to store to a protected data type. You cannot store another type over a constant, program, picture, or graph database. In addition, some system variables are restricted by type; for example, xStat must be a real list. See Appendix A.</p>
11 ARGUMENT	<p>A function or instruction does not have the correct number of arguments. See Appendix A and the appropriate chapter.</p>
12 DIM MISMATCH	<p>You are attempting to perform an operation that has more than one list, matrix, or vector argument, but the dimensions do not match.</p>

Error Conditions (Continued)

13 DIMENSION	<p>The dimension of the argument is not appropriate for the operation.</p> <p>Matrix element dimensions and vector element dimensions must be positive integers between 1 and 255. List dimensions must be integers ≥ 1.</p> <p>A matrix must be square to invert it.</p>
14 UNDEFINED	<p>You are referencing a variable that is not currently defined. For example, you have not stored a value to the variable, or you are referencing a STAT result variable that is not current.</p>
15 MEMORY	<p>There is insufficient memory in which to perform the desired command. You must delete item(s) from memory (Chapter 18) before executing this command.</p>
16 RESERVED	<p>You are attempting to use a system variable inappropriately. See Appendix A.</p>
17 INVALID	<p>You are attempting to reference a variable or use a function in a place where it is not valid. For example, $y(x)$ cannot reference y.</p>
18 ILLEGAL NEST	<p>You are attempting to use an invalid function in an argument to seq or a CALC function, for example, der1(der1(x-3,x),x).</p>
19 BOUND	<p>You must define lower < upper. For tMin and tMax, the third argument must be less than the fourth argument.</p> <p>There is a problem with the RANGE variables.</p> <p>You may have defined xMax<xMin, yMax<yMin, tStep=0, tMax<tMin and Tstep>0 (or vice versa), or tPlot not between tMin and tMax.</p> <p>RANGE variables are too small or too large to graph correctly, which can occur if you attempt to zoom in or out so far that you are not within the numerical range of the calculator.</p> <p>You cannot "go to" this error. Correct the RANGE variables.</p>

Error Conditions (Continued)

21 ZOOM	A point or a line, rather than a box, is defined in ZBOX or a math error resulted from a ZOOM operation.
22 LABEL	The label in the Goto instruction is not defined with a Lbl instruction in the program.
23 STAT	You are attempting a stat calculation with lists that are not appropriate; for example, you are requesting a statistical analysis with fewer than two statistical data points. The frequency (y value) for a 1-VAR analysis must be an integer ≥ 0 . $(xMax-xMin) \times xSci$ must be ≤ 63 for a histogram.
24 CONVERSION	The "from" and "to" unit are not in the same conversion type.
25 SOLVER	In the SOLVER editor, the equation does not contain a variable, or you are attempting to solve with the cursor positioned on bound or left-rt.
26 SINGULARITY*	The SOLVER equation contains a singularity (a point at which the function is not defined)
27 NO SIGN CHNG*	The SOLVER did not detect a sign change.
28 ITERATIONS*	The SOLVER has exceeded the maximum number of iterations permitted.
29 BAD GUESS*	Initial guess must be within the bound. The initial guess and several points around the guess are undefined.

* Errors 26 to 29 occur during the solving process. Examine a graph of the function in GRAPH or a graph of the variable vs. left-rt in the SOLVER. If the equation has a solution, change bound and/or the initial guess.

Error Conditions (Continued)

30 DIF EQ SETUP	Equations in the Q'(t) editor must be Q'1...Q'n and each must have an associated initial condition Q1t...Qnt.
31 DIF EQ MATH	The step size used by the fitting algorithm has gotten too small. Check the equations and initial values. Try a larger value for difTol. Try changing tmin or tmax to examine a different region of the solution.
32 POLY	All coefficients are 0.
33 TOL NOT MET	The algorithm cannot return a result accurate to the requested tolerance.
34 LINK MEMORY FULL	Unable to transmit item because there is insufficient available memory in the receiving unit. You may skip the item or exit RECV mode.
35 LINK TRANSMISSION ERROR	Unable to transmit item. Check to see that the cable is firmly connected to both units and that the receiving unit is in RECV mode. [C] was used to break during transmission.
36 LINK DUPLICATE NAME	Unable to transmit item because a variable with that name already exists in receiving unit.
37 LINK BACK UP MEMORY	Unable to transmit memory backup. The receiving unit does not have enough memory to receive all items in memory on the sending unit. A message indicates the number of bytes the sending unit must delete to do the memory backup. Delete items and try again.

In Case of Difficulty

If you have difficulty operating the calculator, the following suggestions may help you to correct the problem.

Handling a Difficulty

1. If an error occurs, follow the procedure on page 1-28. Refer to the more detailed explanations about specific errors beginning on page B-4, if necessary.
2. If you cannot see anything on the display, follow the instructions on page 1-3 to adjust the contrast.
3. If the cursor is in chessboard pattern, memory is full. Press **[MC]** (MEM) (DELET) and delete some items from memory.
4. If the calculator does not appear to be working at all, be sure the batteries are installed properly and that they are fresh.
5. If the difficulty persists, see page B-10 for information on contacting Consumer Relations to discuss the problem or obtain service.
6. If the dotted bar busy indicator is displayed, a graph or program is paused and the TI-85 is waiting for input.

Two (2) year contractual warranty

1. ¹ The terms and conditions set out hereinunder shall not apply where you have purchased this calculator directly from Texas Instruments Ltd. in which case the conditions of sale of Texas Instruments Ltd. shall apply.
2. This electronic calculator (including charger if applicable) from Texas Instruments is warranted to the original purchaser for a period of two (2) years from the original purchaser for a period of two (2) years from the original purchase date - ~~normal use and wear~~ - against defective materials or workmanship. For this warranty to apply, the calculator must be used as intended. This warranty does not cover damage resulting from any battery leakage. Batteries delivered with calculators are for demonstration purposes only. The warranty is void if: the calculator has been damaged by accident or other causes not arising out of defects in material or workmanship.
During the above two-year period, the calculator or its defective parts will be repaired, adjusted and/or replaced with a reconditioned model of equivalent quality, ("RECONDITIONED") at manufacturer's option without charge to the purchaser when the calculator is returned by way of the dealer to Texas Instruments within 90 days of purchase date. COSTS RETURN FREIGHT (PROOF OF PURCHASE DATE WILL BE RETURNED AT THE CARRIAGE RATES IN EFFECT AT THE TIME OF RETURN).
In the event of replacement with a reconditioned model, the replacement unit will continue to be covered by the warranty of the original calculator product or for a period 90 days, whichever is longer.
THIS CONDITION 2 SHALL NOT AFFECT THE STATUTORY RIGHTS OF A CONSUMER AS DEFINED IN THE CONSUMER TRANSACTIONS (RESTRICTIONS ON STATEMENTS) ORDER 1978 (AS AMENDED).
3. Save as expressly provided in Condition 2, Texas Instruments shall be under no liability of whatsoever kind, howsoever caused whether or not due to the negligence or wilful default of Texas Instruments or its servants or agents arising out of or in connection with this calculator provided that nothing contained in this condition 3 shall exclude or restrict:
 - (I) Any liability of Texas Instruments for death or personal injury resulting from the negligence of Texas Instruments or its servants or agents; or
 - (II) Any liability of Texas Instruments for loss or damage arising from this calculator (within the meaning of Sec. 5 (2) (A) Unfair Contract Terms Act, 1977) and resulting from the negligence of Texas Instruments or its servants or agents.

This index contains an alphabetical listing of major topics covered in this guidebook and their page references. (See also the Table of Commands in Appendix A.)

A

A variable, 15-8, 15-10, A-22
abs function, 1-8, 3-8, 3-14, 11-3, 11-4, 13-18, 13-30, A-2
Absolute value, 3-5, 11-4, 13-18, 13-30
Accent character, 1-25
Accuracy, 4-13, 4-16, B-3
Addition function (+), 1-8, 3-2, 3-14, 12-7, 13-10, 13-26
Alpha key, 1-4, 1-5
Alpha-lock, 1-5
and Boolean function, 1-8, 10-7, A-2
ANGLE menu, 3-3, 3-7
angle function, 1-8, 11-3, 11-4, 13-18, 13-30, A-2
Angle entry indicators $^{\circ}$, $'$, $"$, 3-7
Angle of complex number, 11-4
Angle vector display format, 13-20
Angle MODE, 1-35
Ans variable, 1-12, 4-28 to 4-29, 16-2, A-22
Antilog, 3-2
APD, 1-2
arc function, 1-8, 3-12, 3-16, 4-43, A-2
Arc length, 3-16, 4-28, 4-43
ARC operation, 4-24, 4-28
Arcsin, arccos, arctan, 3-2
Arclength instruction, 2-9 to 2-11
arg function, 1-8, 13-14, A-2
Argument matrices, 13-14
Arrow keys, Down, 1-2
Axis DfEq instruction, 7-2, 7-4, A-2
AxisOff, AxesOn FORMT instructions, 4-0, 4-7, A-3
Axes in graphing, 4-7, 7-2

B

b binary designator, 10-4
b variable, 15-7, 15-10, A-22
BASE menu, 10-3
Base number, 10-2 to 10-8
Bar notation, 1-2, 1-4, B-2
Bin MODE instruction, 1-24, 1-26, A-3
Bin mode operation, 10-8, A-3
Binary constant display, 1-26, 10-6
Binary constants, 10-2 to 10-9
Bit manipulation, 10-8
Boolean operations, 10-7

bound, 14-3 to 14-5
Busy indicator, 1-7, 4-14, 4-22

C

c (speed of light constant), 8-2
CALC menu, 3-12
Calculus commands, 3-12 to 3-16, 4-26 to 4-28
Calculator program, 16-19
Cancel key, 3-12 to 3-19
CATALOG menu, 1-22
Cc (Coulomb constant), 8-2
CE/CLR key, 3-6
Clearance, 3-16 to 3-18
Clear instruction, 4-30, 4-46, 4-48, A-3
Clearing display, 1-36
CIDrv instruction, 4-30, 4-31, 4-43, 10-12, 15-17, A-3
CILCD instruction, 16-9, 16-13, A-3
Clearing an expression, 1-10
Clearing drawings, 4-30, 4-31, 4-43, 15-12, 15-17
Clearing the display, 16-9, 16-13
Clearing stored data, 15-7
cnorm function, 1-8, 13-13, A-3
Coefficients, polynomial, 3-10, 14-8, 14-9
Coefficients, regression equation, 13-8, 13-11
Coefficients, simultaneous equations, 14-10, 14-11
Column sum norm, 13-13
Combinations, probability, 3-6
Commands, xii, 1-12, A-2 to A-21
Comparing, 3-18
Complex conjugate, 11-3, 13-18
Complex number display, 1-26
Complex numbers, 11-2 to 11-4
Concatenating commands, 1-12, 1-14
Concatenating strings, 9-4
cond function, 1-8, 13-13, A-3
Condition number of a matrix, 13-13
Congruent integers, 3-5
conj function, 1-8, 11-3, 13-18, 13-30, A-3
Conjugate of complex number, 11-3
Conjugate of complex matrix, 13-18
Conjugate of complex vector, 13-30

dxDer1 MODE instruction, 1-24, 1-27, 3-16, A-6
dxNDer MODE instruction, 1-24, 1-27, 3-16, A-6

E

e 0 (permittivity of a vacuum) constant, 8-2
e (natural log) constant, 3-2
E(t), B-2
ea function, 1-8, 3-12, 3-14, 3-16, A-6
ec instruction, charge constant, 8-2
Editing, 1-20, 1-21
 ~~command~~, 8-4, 8-5
 ~~cursor~~, 1-17, 1-18
 ~~matrix~~, 13-6 to 13-8
 ~~program~~, 16-6 to 16-8
 ~~stat~~, 15-2, 15-7
 ~~vector~~, 13-21, 13-25
Eigenvalues, 13-13
Eigenvectors, 13-13
elgVc function, 1-8, 13-13, A-6
elgVl function, 1-8, 13-13, A-8
Element of list, 1-9, 12-2, 12-3
Element of matrix, 1-9, 13-16, 13-19
Element of vector, 1-9, 13-21, 13-28
Else instruction, 16-14, 16-15, A-6
End instruction, 16-14, 16-15, A-6
Eng MODE instruction, 1-24, 1-25, A-6
Engineering display MODE, 1-26
entering
 ~~complex number~~, 11-2
 ~~constants~~, 8-4, 8-5
 ~~expressions~~, 1-12, 1-13
 ~~exponents~~, 2-3
 ~~graph functions~~, 4-8 to 4-10
 ~~lists~~, 12-2 to 12-6
 ~~matrices~~, 13-2 to 13-9
 ~~negative numbers~~, 1-9
 ~~program~~ commands, 16-6 to 16-8
 ~~statistics~~, 15-2 to 15-7
 ~~vectors~~, 13-21 to 13-25
EOS™, 1-8, 1-9
Eq-Sl instruction, 9-5, A-7
eqn variable, 3-12, 14-2, A-22
Equal sign (=), 1-8, 4-10, 14-2, A-7
Equal to function (==), 1-8, 3-18, 13-11, 13-26, A-7
Equation Operating System, 1-8, 1-9
Equation to string conversion, 9-5
Equation variables, xii, 2-9 to 2-11
Equations, parametric, 6-2 to 6-6
Equations, solving, 14-2 to 14-11
Erasing a program, 16-2, 16-3
Errors, 1-28, 8-4 to 8-8
E(t), 8-2, 8-3

EVAL feature, 4-29, 5-5, 6-5, 7-8
eval function, 1-8, 3-10, 4-29, 5-5, 6-5, 7-6, A-7
evalF function, 1-8, 3-12, 3-14, 3-16, A-7
Evaluating functions, 3-12, 4-29
Evaluating expressions, 1-8, 1-9
Exact differentiation MODE, 1-27
Exclusive or, 10-7
Executing programs, 16-2, 16-3, ~~exp~~ variable, 3-12, 14-2, 14-3, A-22
Exponent, entering, 2-3
Exponents, 1-12, 1-13
Exponential regression, 15-8, 15-16
ExpR instruction, 15-16, A-7
Expressions, xii, 1-6 to 1-12

F

Factorial function (!), 1-9, 3-6, A-7
Family of curves, 4-16
fcstx, fcsty functions, 1-8, 15-16, A-7
FHI instruction, 12-8, 12-9, 13-14, 13-28, A-7
Fix MODE instruction, 1-24, 1-25, 16-20, A-7
Fixed decimal MODE, 1-25
Floal MODE instruction, 1-24, 1-25, A-7
Floating decimal MODE, 1-25
fMax, fMin functions, 1-8, 3-12, 3-14, 3-16, 4-43, A-8
fint function, 1-8, 3-12, 3-14 to 3-16, A-8
finitErr variable, 3-15, A-22
FnOff, FnOn instructions, 4-11, A-8
For instruction, 16-14, 16-16, A-8
Forecasting statistical values, 15-14, 15-16
FORMAT screen, 4-6
fPart function, 1-8, 3-4, 13-11, 13-26, A-8
Free instruction, 3-10, A-8
Function display, 3-10
Function part, 3-4, 13-11, 13-26
Free-moving cursor, 4-16
Friendly window **ZDecm**, 4-22
Func MODE instruction, 1-24, 1-26, A-8
Format, graphing, 4-6, 4-7, 16-20
Function graphing MODE, 1-26
Function integral, 1-15
Function maximum, 3-16
Function min mode, 3-16
Functions, in, A-5 to A-20
Functions in DHEq graphing, 7-2, 7-3
Functions in Func graphing, 4-8 to 4-10
Functions in Param graphing, 6-2, 6-3

Functions in Pol graphing, 6-2, 6-3
Fundamental theorem of calculus, 17-4

G

g (Earth's gravity) constant, 8-2
Gc (gravitational) constant, 8-2
gcd function, 1-8, 3-10, A-8
getKy function, 1-8, 16-9, 16-13, A-9
Goto instruction, 16-14, 16-17, A-9
Graph database, 2-12, 4-40
Graph picture, 2-12, 4-41
Graphing, 4-2 to 4-45, 5-2 to 5-8, 6-2 to 6-8, 7-2 to 7-10
Graphing format, 4-6, 4-7, 16-20
Graphing MODE, 1-26
Greater than function ($>$), 1-8, 3-18, A-9
Greater than or equal to function (\geq), 1-8, 3-18, A-9
Greatest common divisor, 3-10
Greatest integer, 3-4, 13-11, 13-26
Grid, graphing with, 4-6
GridOff, GridOn FORMT instruction, 4-6, 4-7, A-9
Graph, formatting, 4-6, 4-7, 16-20
Grid, graphing format, 4-6, 1-7

H

h (hex) designation, 1-3
h (Planck's) constant, 8-2
Hex MODE instruction, 1-24, 1-26, A-9
Hex instruction, 1-3, 1-9
Hexadecimal characters, 1-3, 1-9
Hexadecimal MODE, 1-26
Hexadecimal numbers, 1-3 to 1-9
Hexadecimal result display, 1-9
Hist instruction, 16-14, A-11
Histograms, 16-12, 16-17
Home screen, xii, 1-6
HYP menu, 3-3, 3-8
Hyperbolic functions, 3-8

I

ident function, 1-8, 13-14, A-9
Identity matrix, 13-14
If instruction, 16-14, 16-16, A-9
img function, 1-8, 11-3, 13-18, 13-30, A-10
Imaginary numbers, 11-3 to 11-4
Imaginary multiplication, 1-3, 1-9
Increment and Skip, 16-18
Independent variable, 4-9, 5-3, 6-3, 7-3, 15-2
Inflection point, 4-27
inpSt instruction, 16-9, 16-12, A-10
Input instruction, 16-9, 16-10, A-10

Input to programs, 16-9 to 16-13
Instructions, xii, 1-12, A-2 to A-20
Integer part, 3-4, 13-11, 13-26
Integrals, 3-15, 4-26
International characters, 9-8
int function, 1-8, 3-4, 13-11, 13-26, A-10
INTER editor, 3-3, 3-11
Inter function, 1-8, 3-11, A-10
Intercept, 4-28
International character interpolation, 1-11
Interpolation, 4-26
Inverse hyperbolic functions, 3-8
Inverse of functions, 4-37, 4-43
Inverse of a matrix, 13-10
Inverse logs, 3-2, 3-14
Inverse trig functions, 3-2
Inverse function (f^{-1}), 1-8, 3-2, 3-14, 13-10
IO menu, 16-9
IPart function, 1-8, 3-4, 13-11, 13-26, A-10
IS> instruction, 10-14, 16-18, A-10

K

k (Boltzman's) constant, 6-2

L

LabelOff, LabelOn FORMT instruction, 4-6, 4-7, A-11
Labels in programming, 16-17
Labels, axis, 4-7
Last Answer, 1-13, 16-2
Last Entry, 1-14, 16-2
Lbl instruction, 16-14, 16-17, A-11
lcm function, 1-8, 3-10, A-11
Least common multiple, 3-9
left-rt variable, 14-4, 14-6
Length of an arc, 3-16, 4-28, 5-5, 6-5
Length of a string, 9-4
Less than function ($<$), 1-8, 3-18, A-11
Less than or equal to function (\leq), 1-8, 3-18, A-11
Line instruction, 4-30, 4-34, 4-43, A-11
Line stat drawing, 15-12
Linear regression, 15-8
LinR instruction, 15-8, 15-16, A-11
LIST menu, 12-4
Lists, xii, 12-2 to 12-10
As arguments, 12-7
Dimensions, 12-10
Elements, 1-9, 12-2, 12-3
Entering and editing, 12-2 to 12-6
Graphing with, 4-15
If-vc function, 1-8, 12-8, 12-9, 13-28, 13-29, A-11

ln function, 1-8, 3-2, 3-14, A-11
 lngh function, 1-8, 0-4, A-11
 LnR instruction, 15-9, 15-16, A-11
 log function, 1-8, 3-2, 3-14, A-11
 Logarithm, 3-2
 Logarithmic regression, 15-9
 Logic functions, 10-7
 lower variable, 4-25 to 4-28, 14-3 to
 14-5, 14-7, A-23
 LU instruction, 13-12, A-12
 LU matrix decomposition, 13-12



μ 0 (permeability of a vacuum)
 constant, 8-2
 Magnitude of complex numbers, 1-26,
 3-5, 11-2 to 11-4
 Magnitude of vectors, 13-20
 MATH menus, 3-3, 4-24, 13-12, 13-27
 Mathematical functions, 1-8, 3-2
 MATH menu, 13-12 to 13-19
 ANGLE, 13-13
 BASE, 13-13 to 13-12
 DEGREE, 13-13
 Elements, 13-2 to 13-9
 Inserting and editing, 13-2 to 13-9
 Inversion, 13-10
 Math operations, 13-10 ■ 13-13
 Menus, 13-5
 Negation, 13-10
 Rounding, 13-11
 Row operations, 13-16, 13-17
 Squaring, 13-10
 Transpose, 13-12

MAX function, 13-5
 max function, 1-8, 3-5, 12-8, A-12
 Maximum of a function, 3-16, 4-27
 MATH menu, 13-12 to 13-19
 Mc (neutron mass) constant, 8-2
 MATH menu, 13-12 to 13-19
 MEMORY, 18-2
 Memory, 1-2, 18-2 to 18-6
 Menu, 13-12 to 13-19, 16-14, 16-17, A-12
 Menus, xii, 1-16 ■ 1-20
 ANGLE, 3-7
 BASE, 13-3
 DEGREE, 13-3
 ELEMENTS, 13-3
 GRAPH, 13-3
 HYP, 3-7
 INTEGR, 3-7
 LIST, 13-4
 MATH, 3-3, 4-24, 4-38, 13-12, 13-27
 MATRIX, 13-3
 MC, 13-3
 MODE, 13-3
 NAME, 13-3
 DEF, 13-14, 13-27
 PRGM, 13-3
 PROB, 13-3
 QCD, 13-2
 QNT, 13-2
 STAT, 13-3
 STRNG, 13-4
 TEST, 13-3
 VARS, 13-4 to 13-2
 VECTOR, 13-21
 VX, 13-4 to 13-2
 ZOOM, 13-18, 13-20

GRAPH, 4-4, 4-42, 4-43, 5-2, 6-2, 7-2
 HYP, 3-7
 IOL, 13-2
 LIST, 13-4
 MATH, 3-3, 4-24, 4-38, 13-12, 13-27
 MATRIX, 13-3
 MC, 13-3
 MODE, 13-3
 NAME, 13-3
 DEF, 13-14, 13-27
 PRGM, 13-3
 PROB, 13-3
 QCD, 13-2
 QNT, 13-2
 STAT, 13-3
 STRNG, 13-4
 TEST, 13-3
 VARS, 13-4 to 13-2
 VECTOR, 13-21
 VX, 13-4 to 13-2
 ZOOM, 13-18, 13-20

min function, 1-8, 3-5, 12-8, A-12
 Minimum of a function, 3-16, 4-27
 Minimum value, 3-5, 12-8
 MISC menu, 3-3, 3-9
 Miscellaneous characters, 9-7
 Mn (neutron mass) constant, 8-2
 mod function, 1-8, 3-5, A-12
 MODE screen, 1-24
 MODE settings, 1-24 to 1-27, 16-20
 Modulus, 3-5
 Modulus of complex numbers. See
 Magnitude of complex numbers
 Mp (proton mass) constant, 8-2
 mRAdd function, 1-8, 13-16, A-12
 Multiargument functions, 1-8
 Multiplication function (*), 1-8, 3-2,
 3-14, 12-7, 13-10, 13-26, A-12
 multR function, 1-8, 13-16, A-12

N

n variable, 15-10, A-22
 N (Avogadro's number) constant, 8-2
 Natural log and inverse log, 3-2
 nCr function, 1-8, 3-6, A-12
 nDer function, 1-8, 3-12 to 3-14, 3-16,
 A-11
 Negating a matrix, 13-10
 Negation function (-), 1-8, 1-9, 3-2,
 13-10, 13-26, A-13
 Nonreal numbers, 11-2 to 11-4
 norm function, 1-8, 13-12, 13-27, A-13
 Normal MODE instruction, 1-24, 1-25,
 A-13

Normal display MODE, 1-25
not $\frac{\square}{\square}$ function, 1-8, 10-7, A-13
Not equal function (\neq), 1-8, 3-18, 13-11,
13-26, A-13
Notation display format, 1-25
nPr function, 1-8, 3-8, A-13
NUM menu, 3-3, 3-4
Number base MODE, 1-26
Number bases, 10-2 to 10-8
Numeric differentiation MODE, 1-27
Numerical derivative, 3-13, 4-26

O

o octal designator, 10-4
Oct MODE instruction, 1-24, 1-28, A-13
oOct instruction, 10-6, A-13
Octal MODE, 1-26
Octal numbers, 10-3 to 10-6
Octal result display, 10-4, 10-6
OFF key, 1-2
ON key, 1-2
OneVar instruction, 15-16, A-13,
One-variable stat analysis, 15-2, 15-16
OPS menu, 13-14, 13-28
or Boolean function, 1-8, 10-7, A-13
Outpt instruction, 16-9, 16-12, A-14

P

P2Reg, P3Reg, P4Reg instructions,
15-16, A-15
Param MODE instruction, 1-24, 1-26,
A-14
Parametric equations, 6-2 to 6-6
Parametric graphing MODE, 1-26,
6-2 to 6-6
Parentheses, 1-6, 1-9
Pause instruction, 16-14, 16-18, A-14
PEN feature, 4-38
Percent function (%), 1-8, 3-10, A-14
Permutations, 3-6
pEval function, 1-8, 3-10, A-14
Pi, 3-2
Pictures, 2-12, 4-41
Pixel, 4-13
Plotting statistical data, 15-12
Points, drawing, 4-39
Pol MODE instruction, 1-24, 1-26, A-14
*Pol instruction, 11-3, 11-4, 13-29,
A-14
Polar coordinate display, 4-7
Polar equations, 5-2 to 5-6
Polar graphing MODE, 1-26, 5-2 to 5-6
Polar complex number MODE, 1-26
Polar result display, 11-3, 11-4
Polar vector, 1-27, 13-20

PolarC MODE instruction, 1-24, 1-26,
A-14
PolarGC FORM1 instruction, 4-6, 4-7,
A-14

POLY feature, 14-8
poly function, 1-8, 14-9, A-14
Polynomial evaluation, 3-10
Polynomial regression, 15-8, 15-11
Polynomial root finder, 14-8, 14-9
Power function (\wedge), 1-8, 3-2, 3-14,
13-10, 13-14, A-15
Power of ten function ($10\wedge$), 1-8, 3-2,
3-14, 13-14, A-15

Power regression, 15-8
PRegC variable, 15-11, A-22

Plot MODE instruction, 1-24

Plot instruction, 16-9

Plotting statistical data, 15-12

prod instruction, 1-8, 3-10, 13-29, A-15

Program, 2-12, 16-2 to 16-9

Program mode, 16-2 to 16-18

Prompt instruction, 16-9, 16-11, A-15

Prompt instruction, 16-9, 16-11, A-15

PtChg, PtOn, PtOff instructions, 4-39

1-27, 1-28, A-15

PwrR instruction, 15-16, A-15

Q

Q(t), 7-2, 7-3
Q1, 7-2, 7-3
Quadratic regression, 15-8
Quartic regression, 15-8
QuickZoom, 4-17, 5-4, 6-4, 7-5

R

r function, 1-8, 3-7, A-16
r(0), 5-2
rAdd function, 14-16, A-16
Radial MODE instruction, 1-8, 1-24,
1-25, A-16
Radians, 7
Radial MODE, 1-25
rand instruction, 1-8, 3-6, A-16
randM instruction, 1-8, 14-14, A-16
Random number generator, 13-14
Random number generator, 3-6
RANGE editor, 4-12, 4-13
RANGE variables, 4-12, 4-13, 5-3, 6-3,
7-4
Rc (gas) constant, 8-2
RcGDS instruction, 4-40, 4-43, 5-3,
6-2, 7-3, A-16
RCL feature, 2-10, 2-11
RcPlc instruction, 4-41, 4-43, 5-3, 6-2,
7-3, 15-17, A-16

real function, 1-8, 11-3, 13-18, 18-20, A-16

• **Rec instruction**, 11-3, 11-4, 13-29, A-16

Recalling a value, 2-10, 2-11

Recalling an expression, 2-10, 2-11

Reciprocal, 3-2

RectC MODE instruction, 1-24, 1-26, A-16

RectGC FORMT instruction, 4-6, 4-7, A-16

RectV instruction, 1-24, 1-27, 13-21, A-16

Rectangular coordinates, 4-7

Rectangular plotting MODE, 1-26

Rectangular complex numbers, 1-26, 11-2

Rectangular result display, 11-4

Rectangular vector MODE, 1-27

Redisplay rows below cursor, 1-16

rel function, 1-8, 13-16, A-16

RegEq variable, 15-11, A-22

Regression analysis, 15-8 to 15-16

Regression equation, 15-10 to 15-14

Regression models, 15-8

Relational functions, 3-18, 12-7, 13-11, 13-26

Repeat instruction, 16-14, 16-16, A-17

Reserved name variables, A-22

Resetting the TI-85, 18-5

Return instruction, 16-14, 16-18, A-17

norm function, 1-8, 13-18, A-17

Root function ($\sqrt{}$), 1-8, 3-10, A-17

Rotate bits, 10-8

roll, rolR functions, 1-8, 10-8, A-17

round function, 1-8, 3-4, 13-11, 13-26, A-17

Rounding, 3-4, 13-11, 13-26

Row echelon form, 13-16

Row norm, 13-13

Row operations, 13-16, 13-17

rref function, 13-16, 13-17, A-17

rSwap instruction, 1-8, 13-16, A-17

Running a program, 16-2, 16-3

S

Scalar instruction, 15-17, A-17

Scalar plot, 15-12

Sci MODE instruction, 1-24, 1-26, A-17

Scientific display MODE, 1-25

Scientific notation, 2-3

Second derivative, 1-4

Selecting a character for graphing, 4-11

Selecting the menu item, 1-18, 1-19

seq function, 1-8, 3-9, 12-8, 12-9, A-17

SeqG FORMT instruction, 4-6, 4-7, A-17

Sequence, 3-9, 3-14, 12-8, 12-9

Sequential plotting FORMT, 4-6, 4-7

Series, 1-15, 3-9, 12-8, 12-9

Setting graph formats, 4-6, 4-7

Setting MODE, 1-24 to 1-27, 16-20

Setting viewing rectangle, 4-12

Setting ZOOM factors, 4-21

Shade instruction, 4-30, 4-32, 4-33, A-18

Shading a drawing, 4-32, 4-33

shnL, shnR functions, 1-8, 10-8, A-18

Shift bits, 10-8

ShwSt instruction, 15-16, A-18

sign function, 1-8, 3-5, 3-14, A-18

SimulG FORMT instruction, 4-6, 4-7, A-18

SIMULT feature, 14-10 to 14-12

simult function, 1-8, 14-11, A-18

Simultaneous equations, 14-10, 14-11

Simultaneous plotting FORMT, 4-6, 4-7

sin, sin⁻¹ functions, 1-8, 3-2, 3-14, 13-11, A-18

sinh, sinh⁻¹ functions, 1-8, 3-8, 3-14, A-18

Sines, 3-2

Smart Graph, 4-5, 4-14, 4-17, 4-31

SOLVER, 14-2

Solver instruction, 14-5, A-18

Solving equations, 14-2 to 14-12

sortA, sortD functions, 1-8, 12-8, A-19

Sortx, Sorty instructions, 16-16, 15-17, A-19

Sorting stat data, 15-7, 15-15, 15-17

Special characters, 9-7

• **Sph instruction**, 13-29, A-19

SphereV MODE instruction, 1-24, 1-27, 13-20, 13-21, 13-29, A-19

Spherical vector MODE, 1-27

Square-root function ($\sqrt{}$), 1-8, 3-2, 3-14, A-19

Square function (x^2), 1-8, 3-2, 3-14, 13-10, A-19

Standard deviation, 15-10

STAT menu, 15-3

Statistical analysis, 15-2 to 15-18

Statistical data, 15-2 to 15-7

Statistical result variables, 15-10, A-22

St=Eq instruction, 9-5, A-19

StGDB instruction, 4-40, 4-43, 5-3, 6-2, 7-3, A-19

Stop instruction, 16-14, 16-18, A-19

Storing

 Constants, 8-3, 8-4

 Equations, 2-9

Expressions, 2-9
Functions to graph, 4-6
Graphs, 4-40, 4-41, 5-3, 6-2, 7-3
Lists, 12-3 to 12-6
Numbers, 2-5
Pictures, 4-41, 5-3, 6-2, 7-3
Values, 2-5

SIPIC instruction, 4-41, 4-43, 5-3, 6-2,
7-3, 15-17, A-19

Strings, 9-2 to 9-8

STRNG menu, 9-4

sub function, 1-8, 9-4, A-20

Subroutines, 16-19

Subset of a string, 9-4

Subtraction function (-), 1-8, 3-2, 3-14,
12-7, 13-10, 13-26, A-20

sum function, 1-8, 3-9, 12-8, A-20

Summation, 3-9, 12-8

System of equations, 14-16 to 14-12

System variables, A-22

T

T variable, 3-12, 5-2, 5-3, A-22

TMin, **TMax**, **TStep** variables, 5-3,
A-22

t variable, 3-12, 5-2, 7-2, A-22

T function, 1-8, 13-12, A-20

tan, **tan⁻¹** functions, 1-8, 3-2, 3-14, A-20

tanh, **tanh⁻¹** functions, 1-8, 3-8, 3-14,
A-20

TanInv instruction, 4-30, 4-35

TanLn instruction, 4-30, 4-35, 4-43

A-20

TAN instruction, 4-28

TAN⁻¹ instruction, 4-28

TanLn instruction, 4-30, 4-35, 4-43

Tan instruction, 4-28, 4-35, 4-43

Tan⁻¹ instruction, 4-28, 4-35, 4-43

Tol variable, 3-15 to 3-17, 4-26 to 4-28,

A-22

TOLER editor, 3-17

Tolerances, 3-15 to 3-17, 4-26 to 4-28

tPlot variable, 7-4, A-22

TRACE feature, 4-17

Trace instruction, 4-17, A-20

Transp instruction, 4-17, A-20

Transp instruction, 4-17, A-20

Transp instruction, 4-17, A-20

tStep variable, 5-3, 7-4, A-22

Turning a function on and off, 4-11

Turning the **TI-85** On and Off, 1-2

Two-variable statistics, 15-2 to
15-17

U

u (atomic **u** unit) constant, 8-2

unhV function, 1-8, 13-27, A-20

Unit vectors, 13-27

upper variables, 4-23, 14-3, 14-5, 14-7,
15-22

Unselecting a function, 4-11

User-defined **ZOOM**, 4-23

V

Variables, xii, 2-4 to 2-12

VARS menu, 2-7

vc function, 1-8, 13-8, 12-9, 13-28,
13-29, A-20

Vectors, xii, 13-20 to 13-30

Vect instruction, 1-27

Vect instruction, 4-30, 4-35, 4-43, A-21

Viewing rectangle, 4-12, 4-13, 5-3, 6-3,
7-4

W

W instruction, 16-14, 16-16, A-21

X

x variable, 4-13, 4-16, 4-22

x variable, 3-12, 4-9, 4-14 to 4-16, A-22

xFact variable, 4-21, A-22

xMax, **xMin** variables, 4-12, 4-13, 5-3,
6-3, 7-4, A-22

xor Boolean function, 10-7, A-21

xSol variable, 4-12, 4-13, 6-3, 6-3, 7-4,
A-22

xStat list, 15-2, 15-4, 15-5, 15-15,
15-17, A-22

xt variables, 6-2, A-22

xyline instruction, 15-12, 15-17, A-21

Y

y variable, 4-13, 4-16, 4-22

y variable, 4-9, 4-14 to 4-16, A-22

y instruction, 4-26

y(x), 4-2 to 4-11

yFact variable, 4-21, A-22

yMax, **yMin** variables, 4-12, 4-13, 5-3,
6-3, 7-4, A-22

ySol variable, 4-12, 4-13, 6-3, 6-3, 7-4,
A-22

yStat list, 15-2, 15-4, 15-5, 15-15,
15-17, A-22

yt variables, 6-2, A-22

Z

ZDecm instruction, 4-18, 4-22, 4-42,
5-5, 5-5, 7-6, A-21

ZFACT screen, 4-21

ZFit instruction, 4-18, 4-22, 4-42, 5-5,
6-5, 7-6, A-21

ZIn instruction, 4-18, 4-20, 4-42, 5-5,
6-5, 7-6, A-21

ZInt instruction, 4-18, 4-22, 4-42, 5-5,
6-5, 7-6, A-21

ZOOM menu, 4-18

ZOOM BOX, 4-18, 4-19, 5-5, 6-5, 7-6

ZOOM factors, 4-18, 4-21, 5-5, 6-5, 7-8,
A-22

Zooming on a graph, 4-18 to 4-23

ZOOMX, **ZOOMY** operations, 4-18,
4-20, 5-5, 6-5, 7-6, A-21

ZOut instruction, 4-18, 4-20, 4-42, 5-5,
6-5, 7-6, A-21

ZPrev instruction, 4-18, 4-22, 4-42,
5-5, 6-5, 7-6, A-21

ZRcl instruction, 4-18, 4-23, 4-42, 5-5,
6-5, 7-6, A-21

ZSqr instruction, 4-18, 4-22, 4-42, 5-5,
6-5, 7-6, A-21

ZStd instruction, 4-18, 4-22, 4-42, 5-5,
6-5, 7-6, A-21

ZSTO operation, 4-23

ZTrig instruction, 4-18, 4-22, 4-42, 5-5,
6-5, 7-6, A-21

zxMax, **zxMin**, **zxSci**, **zyMax**, **zyMin**,
zySci variables, 4-23, A-22

1. The first part of the paper discusses the importance of the study of the history of the United States. It is argued that a knowledge of the past is essential for a full understanding of the present and for the development of a sound policy for the future.

2. The second part of the paper is devoted to a study of the early years of the Republic. It is shown that the early years were a period of great struggle and uncertainty, and that the country was not united until the end of the eighteenth century.

3. The third part of the paper is devoted to a study of the period of the Civil War. It is shown that this was a period of great crisis and that the country was divided into two warring camps.

4. The fourth part of the paper is devoted to a study of the period of Reconstruction. It is shown that this was a period of great struggle and that the country was not united until the end of the nineteenth century.

5. The fifth part of the paper is devoted to a study of the period of the Progressive Era. It is shown that this was a period of great reform and that the country was united in a common purpose.

6. The sixth part of the paper is devoted to a study of the period of the New Deal. It is shown that this was a period of great reform and that the country was united in a common purpose.


7. The seventh part of the paper is devoted to a study of the period of the Cold War. It is shown that this was a period of great crisis and that the country was divided into two warring camps.

8. The eighth part of the paper is devoted to a study of the period of the Vietnam War. It is shown that this was a period of great crisis and that the country was divided into two warring camps.

9. The ninth part of the paper is devoted to a study of the period of the Watergate scandal. It is shown that this was a period of great crisis and that the country was divided into two warring camps.

10. The tenth part of the paper is devoted to a study of the period of the Persian Gulf War. It is shown that this was a period of great crisis and that the country was divided into two warring camps.





TEXAS
INSTRUMENTS

Printed in Italy - Imprimé en Italie
Impresso em Itália - Impreso en Italia

1112375-0012

TI-85